


OFFICE OF THE BOARD OF COUNCILLORS OF BADURIA MUNICIPALITY
NORTH 24 PARGANAS

Memo No-BM/W/O- 2768

WORK ORDER

Dated- 09/12/2025

From: **The Chairman,**
Baduria Municipality,
Baduria, North 24 Parganas



To: **M/S/Shri - M.R. Enterprise**
Vill. + P. O. - Sayestanagar,
P. S. - Baduria, Dist. - North 24 Parganas

Sub: Work Order for Construction of Toilet Block C.T. /P.T. (Community Toilet) – Model No. - G, Civil, Non-Schedule and Electrical Works. (Toilet Seats 4 Nos and Urinal 5 Nos.)

Location:- Near the house of Ashoke Kumar Ghosh in ward no- 06 at Mouza.- Baikara, J.L. No.- 74, Dag No.- 356, Khatian No.- 2626, within Baduria Municipality.

Tender Reference. No.:- BM/NIT/E- 588, Dated. – 16/10/2025

Tender ID:- 2025_MAD_925663_1

Estimated Amount Put to Tender:- Rs.- 9, 90,958.00(Rupees nine lakh ninety thousand nine hundred fifty eight and zero zero only)

Quoted Rate: - @ 1.02% (One Point zero two) Less

Awarded Amount: - Rs- 9, 80,850.09(Rupees nine lakh eighty thousand eight hundred fifty and zero nine only)

Dear Sir,

Your rate @ **1.02% (One Point zero two) Less** than the estimated amount for the aforesaid work has been accepted by the undersigned on behalf of the councillors of Baduria Municipality. The accepted value of which stands to **Rs- 9, 80,850.09(Rupees nine lakh eighty thousand eight hundred fifty and zero nine only)** only including all taxes and other charges.

You are requested to execute an agreement with the undersigned within seven days from the date of issue of this order. In case of failure this letter of acceptance shall liable to be treated as cancelled and the earnest money so deposited with the tender will be forfeited in full without any further correspondence.

You are hereby requested to please start the work as per instruction of E.I.C. of Baduria Municipality. The work will have to be completed within the stipulated time period i.e. **90(ninety) days** from the date of receipt of this order. No extension of time will be allowed without valid and authenticated reasons. Penalty will be imposed as per rules for non-completion of the work within the schedule time.

No Supplementary item of work or excess quantity of work beyond tendered quantity should be executed without the written permission of the Engineer-in charge, otherwise no payment will be made on that account.

Please depute one responsible representative duly accredited at your own cost to remain present at work site during the working hours to receive orders and instruction in site order book which should be kept under your custody.

The terms & condition and corresponding agreement of tender will be binding upon him and it should be followed strictly and any deviation in this regard will not be entertained.

Security deposit, G.S.T, income tax and any other deduction will be made as per prevailing Govt. norms from progressive bill.


Necessary payment will be made at per accepted rates on the basis of actual measurement of the work done satisfactory in all respect & having necessary performance certificate in the bill from the competent authority.


Memo No. - **BM/W/O-2768/1,** Date: **09/12/2025**

Copy forwarded for information and necessary action to:

- 1) Councillor, Ward No.- 06, Baduria Municipality.
- 2) S.A.E., Baduria Municipality.

Yours faithfully,


Chairman
BADURIA MUNICIPALITY
North 24 Parganas



Percentage BoQ

Validate Print Help

Tender Inviting Authority: Chairman, Baduria Municipality

Name of Work: CONSTRUCTION OF TOILET BLOCK C.T.P.T. MODEL NO. G CIVIL NON- SCHEDULE AND ELECTRICAL WORKS.
 CONSTRUCTION OF COMMUNITY TOILET C.T. NEAR THE HOUSE OF ASHOKE KUMAR GHOSH IN WARD NO. 6 AT MOUZA BAIKARA J.L. NO. 74, DAG NO. 356. KHATIAN NO. 2626
 MODEL NO. G
 TOILET SEATS 4 NOS, URINAL 5 NOS.

Contract No:

Name of the Bidder/ Bidding Firm / Company

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	Civil Works						
1.01	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m, as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. PWD Building Works schedule Page - 1, Item -2, a	11.22	%Cu.m	11,927.00	1338.21	1338.21	INR One Thousand Three Hundred Thirty Eight & Paise Twenty One Only
1.02	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm, including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). (a) With earth obtained from excavation of foundation. PWD Building Works schedule, Page - 1, Item -3, a	7.48	%Cu.m	7,754.00	580.00	580.00	INR Five Hundred Eighty & Paise Zero Only
1.03	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) PWD Building Works schedule, Page - 2, Item -4, a	9.480	Cum	936.21	8875.27	8875.27	INR Eight Thousand Eight Hundred Seventy Five & Paise Twenty Seven Only
1.04	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. PWD Building Works schedule, Page -14, Item - 1 (Corri. Page-01, Date-04-06-2018)	28.01	Sqm	361.00	10111.61	10111.61	INR Ten Thousand One Hundred Eleven & Paise Sixty One Only
1.05	Cement concrete with graded stone (40 mm size) excluding shuttering in ground floor and foundation. (a) 1:3:6 proportion. PWD Building Works schedule, Page - 23, Item-B 1.a, (Corri. Page-09, Date-04-06-2018) Rate Analysts 1 (Corri. Page-01, Date-04-06-2018)	2.80	m3	5,248.44	14695.63	14695.63	INR Fourteen Thousand Six Hundred Ninety Five & Paise Sixty Three Only

1.06	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. a) Pakur Variety /Chandil Variety PWD Building Works schedule, p-26 Item 10 a (Rate Analysis)	10.93	Cum	6,087.41	66535.39	66535.39	INR Sixty Six Thousand Five Hundred Thirty Five & Paise Thirty Nine Only
1.07	25mm. thick damp proof course with cement concrete with stone.chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacturer's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2 nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately). (Chequering not required over concrete or painted surface). [Note: - Waterproofing as per item 9, polymer based paint as per item 8 (a) of subhead C of Section (C). PWD Building Works schedule, Page -47, Item -1 (Rate Analysis)	5.28	Sqm	265.95	1404.22	1404.22	INR One Thousand Four Hundred Four & Paise Twenty Two Only
1.08	125 mm brick work with 1st classbricks in cement mortar (1-4) in ground floor. PWD Building Works schedule, Page -16, Item-16, cori page -3, date -04.06.2018 (Rate Analysis)	20.00	Sq. M.	728.56	14571.20	14571.20	INR Fourteen Thousand Five Hundred Seventy One & Paise Twenty Only
1.09	Dampproof course or below flooring or roof terracing or foundation or foundation trenches. PWD Building Works schedule, Page -47, Item-3 Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)	23.21	Sq. M.	24.00	557.04	557.04	INR Five Hundred Fifty Seven & Paise Zero Four Only
1.1	(f) 25 mm to 30 mm shuttering without staging in foundation PWD Building Works schedule, Page -42, Item- 36.f	26.93	Sqm	209.00	5628.37	5628.37	INR Five Thousand Six Hundred Twenty Eight & Paise Thirty Seven Only
1.11	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-Charge. PWD Building Works schedule, Page -42, Item- 36.a Artificial stone in floor, dado, staircase with cement mortar (1:2:4)with stone chips listed in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) in cluding smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/ sq.m all complete including all materials and labour.	57.63	Sqm	335.00	19306.05	19306.05	INR Nineteen Thousand Three Hundred Six & Paise Zero Five Only
1.12	3 mm thick topping using gray cement (ii)25 mm PWD Building Works schedule, p-48 Item 6(ii) In ground floor	20.86	Sq.m	266.13	5551.47	5551.47	INR Five Thousand Five Hundred Fifty One & Paise Forty Seven Only

1.13	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m. (i) For steel/Mild Steel , Other than not specified PWD Building Works schedule, Page - 43, Item - 40 a.i.1(Corri. 10th Page-01, Date-23-01-2020) (Rate Analysis) 1.20% of item no. 06	1.030	M.T.	53,162.67	54757.55	54757.55	INR Fifty Four Thousand Seven Hundred Fifty Seven & Paise Fifty Five Only
1.14	Collapsible gate with 40 mm x 10 mm x 6 mm Tee as top and bottom guide rail , 20 mm x 10 mm x 2 mm vertical channels 100 mm apart in full stretched position 20m x 5 mm MS flats as collapsible bracings properly riveted and washed including 38 mm steel roller including locking arrangements , fitted and fixed in position with lugs set in cement concrete including cutting necessary hikes chasing etc in walls , floors etc and making good all damages. PWD Building Works schedule, Page -106, Item- 18	4.41	Sqm	4,330.00	19095.30	19095.30	INR Nineteen Thousand Ninety Five & Paise Thirty Only
1.15	Brick work with 1st class bricks in cement mortar (1:6) (a) Foundation and plinth grouting floor PWD Building Works schedule, Page -15, Item-7.a (Rate Analysis)	4.82	Cu.m	5,367.81	25872.84	25872.84	INR Twenty Five Thousand Eight Hundred Seventy Two & Paise Eighty Four Only
1.16	Brick work with 1st class bricks in cement mortar (1:6) (b) superstructure grouting floor PWD Building Works schedule, Page -15, Item-7.b (Rate Analysis)	11.79	Cu.m	5,590.81	65915.65	65915.65	INR Sixty Five Thousand Nine Hundred Fifteen & Paise Sixty Five Only
1.17	Labour for Chipping of concrete surface before taking up plastering work. PWD Building Works schedule, P-192, It-1	66.77	Sqm	21.00	1402.17	1402.17	INR One Thousand Four Hundred Two & Paise Seventeen Only
1.18	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor) [Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster PWD Building Works schedule, P-189 It- No. 1 (Rate Analysis)	115.33	Sqm	148.71	17150.72	17150.72	INR Seventeen Thousand One Hundred Fifty & Paise Seventy Two Only
1.19	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor) [Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (c) 10 mm thick plaster PWD Building Works schedule, P-189 It- No. 1 (ii) (Rate Analysis)	19.53	Sqm	130.71	2552.77	2552.77	INR Two Thousand Five Hundred Fifty Two & Paise Seventy Seven Only
1.2	Neat cement punning about 1.5 mm thick in wall, dado, window sills, floors etc. Note cement 0.152 m ³ /100 m ² PWD Building Works schedule, P-192 It- No. 15	11.58	Sqm	32.85	380.40	380.40	INR Three Hundred Eighty & Paise Forty Only

1.21	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria. (i) 66mm x 90mm PWD Building Works schedule, P-115, It - 3 (i)	19.80	Mtr	497.00	9840.60	9840.60	INR Nine Thousand Eight Hundred Forty & Paise Sixty Only
1.22	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. ii) 25 mm thick P-125, It- 14(i)	5.03	Sqm	2,581.00	12982.43	12982.43	INR Twelve Thousand Nine Hundred Eighty Two & Paise Forty Three Only
1.23	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufacture from extruded section conforming to I.S. 2047/4 fitted and fixed with cadmium plated screws. (vii) 225mm long x 10mm dia. bolt. PWD Building Works schedule, P-144, It No. 26 (vii)	5.00	Each	84.00	420.00	420.00	INR Four Hundred Twenty & Paise Zero Only
1.24	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark, (viii) 100mm X 75mm X 3.50mm. PWD Building Works schedule, P-140, It No. -5 (viii)	15.00	Each	66.00	990.00	990.00	INR Nine Hundred Ninety & Paise Zero Only
1.25	Anodised aluminium decorative handle (hexagonal / fluted) of approved quality fitted and fixed complete. (i) 150mm plate x 10mm dia rod x 12mm hexagonal/fluted. PWD Building Works schedule, Page -146 . Item no-31,(i)	10.00	Each	87.00	870.00	870.00	INR Eight Hundred Seventy & Paise Zero Only
1.26	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with concrete bolt and round fitting b)250mm long. PWD Building Works schedule, Page -141 . Item no-10 b)	5.00	Each	159.00	795.00	795.00	INR Seven Hundred Ninety Five & Paise Zero Only
1.27	Supplying and laying chequered tiles of any shade and of approved quality with (1:1.5:3) cement concrete laid in panels or patterns as directed in pavement ,footpath etc including necessary underlay, 25 mm thick (avg)cement mortar (1:3) complete in all respect with all labour and materials. (Using cement slurry @4.4kg/sq.m at back side and @2.4 kg/sq.m for joint filling). PWD Building Works schedule, Page -74 . Item no- 46(i), 25 mm thick	3.49	sq.m	471.00	1643.79	1643.79	INR One Thousand Six Hundred Forty Three & Paise Seventy Nine Only
1.28	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand (1.5 mm thick) In Ground Floor PWD Building Works schedule, PWD, P- 198, I - 5	123.28	Sqm	122.00	15040.16	15040.16	INR Fifteen Thousand Forty & Paise Sixteen Only

1.29	Applying interior grade Acrylic Primer of approved quality and brand on plastered and concrete surface old or new surface to receive Distemper Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the E-I-C (Ground Floor) (b) Two Coats PWD Building Works schedule, Page -195, Item no-7(b)(i).	51.08	%m2	4,420.00	2257.74	2257.74	INR Two Thousand Two Hundred Fifty Seven & Paise Seventy Four Only
1.3	Dry Destempering interior walls or ceiling including cleaning, washing, smoothing surface (b) two coats PWD Building Works schedule, Page -196, Item no-9(b)	51.08	m2	49.00	2502.92	2502.92	INR Two Thousand Five Hundred Two & Paise Ninety Two Only
1.31	Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Decorative Textured (Marrrt Finish) or Smooth Finish Acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC in Ground Floor (b) two coats. PWD Building Works schedule, Page -196, Item no-8(b)	77.96	m2	45.10	3516.00	3516.00	INR Three Thousand Five Hundred Sixteen & Paise Zero Only
1.32	Protective and Decorative Acrylic Exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over Acrylic primer as required. The rate includes cost of materials, labour, scaffolding and all incidental charges but excluding the cost of primer in ground floor (two coats)(a) normal acrylic emulsion. PWD Building Works schedule, Page -197, Item no-17(a)	77.96	m2	67.00	5223.32	5223.32	INR Five Thousand Two Hundred Twenty Three & Paise Thirty Two Only
1.33	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. PWD Building Works schedule, Page -200, Item no-1 (b)	6.35	Sqm	38.00	241.30	241.30	INR Two Hundred Forty One & Paise Thirty Only
1.34	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothing surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : Page -200, Item no-1 (b) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) PWD Building Works schedule, Page -200, Item no-2(A)(a)(iv)	6.35	Sqm	81.00	514.35	514.35	INR Five Hundred Fourteen & Paise Thirty Five Only
1.35	(a) M.S or W.I. Ornamental grill of approved design joints continuously welded with M.S. W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr. PWD Building Works schedule, P-104 Item-13 A (i) (3rd Corrigendum Page No 91)	0.520	Qntl	9,888.00	5141.76	5141.76	INR Five Thousand One Hundred Forty One & Paise Seventy Six Only
1.36	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. PWD Building Works schedule, P/200 Item-1(a)	7.44	Sqm	29.00	215.76	215.76	INR Two Hundred Fifteen & Paise Seventy Six Only

1.37	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothing surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white) PWD Building Works schedule, P-200, Item-2(b)(iv) Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91 Kg./sqm or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqm below mortar only, joints grouted with admixture of white cement and colouring. Pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) l (I) With application slurry @ 1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White	7.44	Sqm	79.00	587.76	587.76	INR Five Hundred Eighty Seven & Paise Seventy Six Only
1.38	(A) Deep Colour & White	35.24	Sqm	1,785.00	62903.40	62903.40	INR Sixty Two Thousand Nine Hundred Three & Paise Forty Only
1.39	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. B) Wall Area of each tile above 0.09 Sq.m ii) Other than Coloured decorative including white PWD Building Works schedule, page-64, Item:35.(B.) (b), (i) (3rd Corriganam, Page 36)	85.17	Sqm	1,047.00	89172.99	89172.99	INR Eighty Nine Thousand One Hundred Seventy Two & Paise Ninety Nine Only
1.4	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285-1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composite door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film i) Natural white h) Louvered window. j) Top, bottom and side member. PWD Building Works schedule, PWD, P-233, I- 1(h) i	8.40	Mtr	183.00	1537.20	1537.20	INR One Thousand Five Hundred Thirty Seven & Paise Twenty Only
1.41	ii) Louvered Section.	4.80	Mtr	658.00	3158.40	3158.40	INR Three Thousand One Hundred Fifty Eight & Paise Forty Only
1.42	iii) Cleat angle (Non-anodized).	6.40	Mtr	263.00	1683.20	1683.20	INR One Thousand Six Hundred Eighty Three & Paise Twenty Only

1.43	Labour charge for fabrication and installation of composite door, window, partitions made from anodized extruded alloy aluminium sections for the following units:- (A) Glazed aluminium sliding windows made of extruded and anodized alloy aluminium sections, fabrications, including cutting to proper shape and size, drilling and aligning of window shutter frame fitted with in built locking arrangements, sliding rollers and other necessary fittings, fixturing, adhesives and joineries along with extruded neoprene or EPDM gasketing in between window frame and masonry work (walls, column, beam lintels etc.) as well as between glass and shutter frame for fixing glass and Polysulphide sealant and in between shutter and window frame where necessary including cutting to requisite size and fixing glass as per drawing, specification and direction of EIC. The rate includes the hire charge of all tools and plants, including all incidental charges, adhesive, joineries such as screw, cleat angle etc. but excluding the cost of extruded aluminium sections, glass, neoprene / EPDM gasket, locking arrangement and rollers. v) Louvered window. PWD Building Works schedule SOR, PWD, P-243, I- 9	1.08	Sq.M.	730.00	788.40	788.40	INR Seven Hundred Eighty Eight & Paise Forty Only
1.44	Supplying bubble free float glass of approved make and brand conforming to IS- 2835-1987. iv) 5mm thick coloured / tinted / smoke glass. PWD Building Works schedule, P-243, I- 9	1.08	Sq.M.	585.00	631.80	631.80	INR Six Hundred Thirty One & Paise Eighty Only
1.45	Painting block letters or digits in Black Japan or any approved paint as per direction. e) Size above 7.5 cm. and upto 10 cm. PWD Building Works schedule, P-268, II-17(e)	450.00	Each	12.00	5400.00	5400.00	INR Five Thousand Four Hundred & Paise Zero Only
1.46	Supplying and planting of different plants / trees (supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads and lifts, carriage, handling, manuring applying pesticide and fertilizer etc. i) Furcarea Veriegated 10 to 12 leaves in height 20-30 cm in earthen pot of size 25 cm x) Ficus blakii (F- Vivicon) well branched (Bushy) of height 120cm - 135 cm in earthen pot of size 30cm. PWD Building Works schedule, Page-261, II- 9 (x)	10.00	Each	162.00	1620.00	1620.00	INR One Thousand Six Hundred Twenty & Paise Zero Only
1.47	xxvi) Areca Palm 4 - 5 suckers of height 90 cm to 105 cm in earthen pots of size 25 cm. PWD Building Works schedule, Page-261, II- 9 (xxvi)	3.00	Each	187.00	561.00	561.00	INR Five Hundred Sixty One & Paise Zero Only
1.48	SANITARY AND PLUMBING WORKS Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. a) With 'P' trap (with vent) PWD S&P Schedule, page-79, item no.-3 (e)	3.00	Each	127.00	381.00	381.00	INR Three Hundred Eighty One & Paise Zero Only
1.49	Supplying, fitting and fixing Flat back urinal (half stall position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (i) Plastic (yellow type) White PWD S&P Schedule, page-81, item no.10.b.i	4.00	Each	3,104.00	12416.00	12416.00	INR Twelve Thousand Four Hundred Sixteen & Paise Zero Only
1.51	Supplying, fitting and fixing Flat back urinal (half stall position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (ii) 470 mm X 280 mm X 340 mm PWD S&P Schedule, page 80, item no-6/(ii)	4.00	Each	380.00	1520.00	1520.00	INR One Thousand Five Hundred Twenty & Paise Zero Only
1.52		3.00	Each	945.00	2835.00	2835.00	INR Two Thousand Eight Hundred Thirty Five & Paise Zero Only

1.53	Supplying fitting and fixing squatting plate with integrated flushing in white vitreous set in cement concrete (6:3:1) with jhana chips complete. (Payment of concrete will be paid separately) (L) 450 mm x 350 mm	2.00	each	881.00	1762.00	1762.00	INR One Thousand Seven Hundred Sixty Two & Paise Zero Only
1.54	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete C.I. brackets including two coats of painting to bracket etc. P.W.D S&P Schedule, Page No.-36 Item No.-2.	4.00	Nos	1,015.00	4060.00	4060.00	INR Four Thousand Sixty & Paise Zero Only
1.55	Supplying, fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete i) Polythene Flush Pipe P.W.D S&P Schedule, Page no 81. Item no. 11.(i)	4.00	Each	155.00	620.00	620.00	INR Six Hundred Twenty & Paise Zero Only
1.56	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. (a) C.P. urinal flush pipe fittings range of one P.W.D S&P Schedule, S.P.81, item-12/a	2.00	Each	414.00	828.00	828.00	INR Eight Hundred Twenty Eight & Paise Zero Only
1.57	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., mending good all damages and painting the brackets with two coats of approved paint. (i) 550 mm X 400 mm size (ii) 550 mm X 400 mm size P.W.D S&P Schedule, P-41, It 2 (ii)	2.00	Each	2,208.00	4416.00	4416.00	INR Four Thousand Four Hundred Sixteen & Paise Zero Only
1.58	Supplying fitting and fixing pedestal of approved make for wash basin (White) P.W.D S&P Schedule, P-41, It 3	2.00	Each	1,497.00	2994.00	2994.00	INR Two Thousand Nine Hundred Ninety Four & Paise Zero Only
1.59	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia., (ii) 600 mm long P.W.D S&P Schedule, Page No.-43 Item No.-9-iii	5.00	Each	107.00	535.00	535.00	INR Five Hundred Thirty Five & Paise Zero Only
1.6	Supplying fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iv) 1050 mm long each P.W.D S&P Schedule, Page No.-10-iv	2.00	Each	91.00	182.00	182.00	INR One Hundred Eighty Two & Paise Zero Only
1.61	(f) Hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model - ALLIED of Jaquar or similar). P.W.D S&P Schedule, Page No.-3 Item No.- 3 f.	5.00	Each	1,251.00	6255.00	6255.00	INR Six Thousand Two Hundred Fifty Five & Paise Zero Only
1.62	(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). P.W.D S&P Schedule, Page No.-6 Item No.-7-a-i	7.00	Each	539.00	3773.00	3773.00	INR Three Thousand Seven Hundred Seventy Three & Paise Zero Only
1.63	(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar brand) P.W.D S&P Schedule, Page No.-6 Item No.-7-b-i	5.00	Each	493.00	2466.00	2466.00	INR Two Thousand Four Hundred Sixty Five & Paise Zero Only
1.64	Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand), P.W.D S&P Schedule, Page No.-6 Item No.-7-d-i.	5.00	Each	815.00	4075.00	4075.00	INR Four Thousand Seventy Five & Paise Zero Only
1.65	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cook - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand). (P. No. - 45, Item. No. - 19(a), Pwd Sanitary Plumbing Schedule 2017)	2.00	Each	555.00	1110.00	1110.00	INR One Thousand One Hundred Ten & Paise Zero Only

1.66	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS - 1239 (Part - I), with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work PVC Pipes, 25 mm Page No.-12 Item No.-19-(a), PWD,VOL-II, 2017-18	25.00	Mtr	177.00	4425.00	4425.00	INR Four Thousand Four Hundred Twenty Five & Paise Zero Only
1.67	(a) For Exposed Work PVC Pipes, 15 mm Page No.-12 Item No.-19-(a), PWD,VOL-II, 2017-18	10.00	Mtr	101.00	1010.00	1010.00	INR One Thousand Ten & Paise Zero Only
1.68	(b) For Concealed Work PVC Pipes, 15 mm Page No.-12 Item No.-19-(b), PWD,VOL-II, 2017-18	10.00	Mtr	137.00	1370.00	1370.00	INR One Thousand Three Hundred Seventy & Paise Zero Only
1.69	Supplying and fitting fixing of gunmetal wheel valve of approved brand and make tested to 21 Kg per sq. cm. 25 mm dia(E5) PWD S&P Schedule, P-5 It-5, vii).	2.00	Each	778.00	1556.00	1556.00	INR One Thousand Five Hundred Fifty Six & Paise Zero Only
1.7	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer PWD S&P Schedule, page 37, item no-6 (b)	2.00	Each	5,128.00	10256.00	10256.00	INR Ten Thousand Two Hundred Fifty Six & Paise Zero Only
1.71	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L. PWD S&P Schedule, page 37, item no-10 (i)(a)	2.00	Each	96.00	192.00	192.00	INR One Hundred Ninety Two & Paise Zero Only
1.72	Labour for punching hole in plastic water storage tank upto 50 mm dia. PWD S&P Schedule, (P. No. - 38, Item. No. - 13	4.00	Each	19.00	76.00	76.00	INR Seventy Six & Paise Zero Only
1.73	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992.(A) (i) Single Socketed 3 Meter Length, (b) 110 mm PWD S&P Schedule, Page No.-68 Item No. 23.(A)(i)(b)	30.00	Mtr	292.00	8760.00	8760.00	INR Eight Thousand Seven Hundred Sixty & Paise Zero Only
1.74	(B) Fittings (i) Coupler, (b) 110 mm	8.00	Each	85.00	680.00	680.00	INR Six Hundred Eighty & Paise Zero Only
1.75	(ii) Plain Tee, (b) 110 mm	12.00	Each	85.00	1020.00	1020.00	INR One Thousand Twenty & Paise Zero Only
1.76	(iii) Door Tee, (b) 110 mm	10.00	Each	195.00	1950.00	1950.00	INR One Thousand Nine Hundred Fifty & Paise Zero Only
1.77	(x) Bend 45°, (b) 110 mm	10.00	Each	89.00	890.00	890.00	INR Eight Hundred Ninety & Paise Zero Only
1.78	(xi) Door Bend (T.S.), (b) 110 mm	7.00	Each	147.00	1029.00	1029.00	INR One Thousand Twenty Nine & Paise Zero Only
1.79	(xvi) Pipe Clip, (b) 110 mm	30.00	Each	21.00	630.00	630.00	INR Six Hundred Thirty & Paise Zero Only
1.8	(xvii) W.C. Connector (150 mm long) 125 X 110(W/WC Ring), 75 mm	4.00	Each	142.00	568.00	568.00	INR Five Hundred Sixty Eight & Paise Zero Only
1.81	(xxx) Plain Floor Trap with Top tile & Strainer 75 mm	7.00	Each	144.00	1008.00	1008.00	INR One Thousand Eight & Paise Zero Only
1.82	L) Rubber Ring, (b) 110 mm	15.00	Each	17.00	255.00	255.00	INR Two Hundred Fifty Five & Paise Zero Only
1.83	C) Rubber Lubricant 500 ML	1.00	500 ML	187.00	187.00	187.00	INR One Hundred Eighty Seven & Paise Zero Only
1.84	D) Solvent Cement 250 ML	1.00	250 ML	103.00	103.00	103.00	INR One Hundred Three & Paise Zero Only

1.85	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in total pipeline including specials. (B) Under ground. (i) 110 mm dia. PWD S&P Schedule. (P - 74, Item. No. - 24 (B))	25.00	Mtr	84.00	2100.00	2100.00	INR Two Thousand One Hundred & Paise Zero Only
1.86	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS-13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materials (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete. A) UPVC Pipes: (i) 75 mm. Dia. (P - 212, Item. No. - 21 (A)(i) , (B),(c)(i) & (B), (d), (i), Pwd volume - i, 2017)	30.00	Mtr	188.00	5640.00	5640.00	INR Five Thousand Six Hundred Forty & Paise Zero Only
1.87	B) UPVC Fittings: c) Bend 87.5 degree (i) 75 mm. Dia.	6.00	Mtr	84.00	504.00	504.00	INR Five Hundred Four & Paise Zero Only
1.88	B) UPVC Fittings: d) Shoe (i) 75 mm. Dia.	2.00	Mtr	78.00	156.00	156.00	INR One Hundred Fifty Six & Paise Zero Only
1.89	Constructing inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling, 15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm.thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. i) With Pakur variety (Other than SAIL/JATA/RINL). PWD S&P Schedule, S.P.87, Item No-1(i), 7th Corrigenada Volume ii	3.00	Each	7,074.68	21224.04	21224.04	INR Twenty One Thousand Two Hundred Twenty Four & Paise Zero Four Only

1.9	<p>Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the 100mm thick R.C.C. (1:1.5:3) top slab with necessary fittings. 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C. (1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials.</p> <p>(i) For 20 users (ii) With Pakur variety. (Other than not specified) P.W.D S&P Schedule, S.P.88, Item No-3(i)(A) - 7th</p>	1.00	Each	45,305.21	45305.21	INR Forty Five Thousand Three Hundred Five & Paise Twenty One Only
1.91	<p>Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm intermediate cement brick work (1:4) band all round and cement brick work (1:4) upto 0.90 metre from top with 20mm thick cement plaster (1:4) to inside face upto the depth of cement brick work. 15mm thick cement plaster (1:4) on outer face from top of the well upto G.L. and 6 mm thick cement plaster (1:4) on top of the R.C.C. cover slab including filling bottom 1.00 metre of inside of the well with brick metal (50 mm to 63 mm size) including R.C.C. cover slab of 100 mm thick with cement conc (1:1.5:3) with stone chips with necessary reinforcement and shuttering including one 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the cover slab with necessary fittings, making necessary arrangements for pipe connections, excavation of well including shoring, dewatering and removing the excess earth from the premises as per direction complete in all respect with all costs of labour and materials. With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia.</p> <p>(Other than not specified) S.P.88, Item No-4 7th Corrigenda Volume ii</p>	1.00	Each	16,396.39	16396.39	INR Sixteen Thousand Three Hundred Ninety Six & Paise Thirty Nine Only
1.92	<p>Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long P.W.D S&P Schedule, p No 82 I No- 22 (a)(ii)</p>	2.00	Each	430.00	860.00	INR Eight Hundred Sixty & Paise Zero Only
1.93	<p>Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm P.W.D S&P Schedule, P-81, It-15(ii)</p>	2.00	Each	484.00	968.00	INR Nine Hundred Sixty Eight & Paise Zero Only
1.94	<p>Supplying, fitting and fixing soap holder. (b) Fibre glass Sanitary and plumbing work schedule P-82, It-18(b)</p>	4.00	Each	58.00	232.00	INR Two Hundred Thirty Two & Paise Zero Only

1.95	Supplying, fitting and fixing glass shelf with aluminium guard rails. (a) Ordinary type with 5.5 mm sheet glass (i) 450 mm X 125 mm Sanitary and plumbing work schedule P-81, II-16(a)(i)	2.00	Each	341.00	682.00	682.00	INR Six Hundred Eighty Two & Paise Zero Only
1.96	Add S.G.S.T. @ 18%	1.00	Nos	134420.54	134420.54	134420.54	INR One Lakh Thirty Four Thousand Four Hundred Twenty & Paise Fifty Four Only
1.97	Add Labour Welfare Cess. @ 1 %	1.00	Nos	8812.01	8812.01	8812.01	INR Eight Thousand Eight Hundred Twelve & Paise Zero One Only
2	NON SCHEDULE WORKS Superintending Engineer Approved of Rate of non-schedule items for Proposed Toilet Block (CT & PT)						
2.01	Standard plastic Dustbin (12 lits)	5	Each	350.00	1750.00	1750.00	INR One Thousand Seven Hundred Fifty & Paise Zero Only
2.02	Installation of Sinage	1	Each	2,071.00	2071.00	2071.00	INR Two Thousand Seventy One & Paise Zero Only
2.03	Air Freshner (Pack of 4 nos)	8	Each	216.00	1728.00	1728.00	INR One Thousand Seven Hundred Twenty Eight & Paise Zero Only
2.04	Air Freshner (Naphthaline 250 gm)	5	Each	210.00	1050.00	1050.00	INR One Thousand Fifty & Paise Zero Only
2.05	Supplying paper Napkin	5	Each	50.00	250.00	250.00	INR Two Hundred Fifty & Paise Zero Only
2.06	Supplying Sanitary Napkin (Whisper or simial make 50 pcs)	4	Each	520.00	2080.00	2080.00	INR Two Thousand Eighty & Paise Zero Only
2.07	Harpic (Blue 500 ml)	4	Each	300.00	1200.00	1200.00	INR One Thousand Two Hundred & Paise Zero Only
2.08	Harpic (Red 500 ml)	4	Each	150.00	600.00	600.00	INR Six Hundred & Paise Zero Only
2.09	Gala double lip floor wiper	4	Each	350.00	1400.00	1400.00	INR One Thousand Four Hundred & Paise Zero Only
2.1	Colin glass or surface cleaner	2	Lit	200.00	400.00	400.00	INR Four Hundred & Paise Zero Only
2.11	Muriatic Acid	2	Lit	145.00	290.00	290.00	INR Two Hundred Ninety & Paise Zero Only
2.12	Bleaching Powder	4	Kg	120.00	480.00	480.00	INR Four Hundred Eighty & Paise Zero Only
2.13	Dettol, Lifebuoy or similar make liquid soap	8	Lit	140.00	1120.00	1120.00	INR One Thousand One Hundred Twenty & Paise Zero Only
2.14	Rubber hand Gloves	6	Pair	80.00	480.00	480.00	INR Four Hundred Eighty & Paise Zero Only
2.15	Double Side plastic brush	6	Each	125.00	750.00	750.00	INR Seven Hundred Fifty & Paise Zero Only
2.16	Plastic Broom	4	Each	170.00	680.00	680.00	INR Six Hundred Eighty & Paise Zero Only
2.17	Signage ACP Base & reflective vinyl (EE)	1.00	Nos	3776.00	3776.00	3776.00	INR Three Thousand Seven Hundred Seventy Six & Paise Zero Only
2.18	SPS/any other ICT based feedback system (with number displayed on which SMS has to be sent) (A9)	1	Each	5,000.00	5000.00	5000.00	INR Five Thousand & Paise Zero Only
2.19	Glow sign board Name and contact details of the following are displayed prominently - Toilet identification number, name of ULB under whose jurisdiction toilet is covered, ward number and maintenance authority prominently displayed for each toilet block Supervisor, Supervisor's agency and area Sanitary Inspector (D3)	1	Each	5,000.00	5000.00	5000.00	INR Five Thousand & Paise Zero Only
2.2	Mini Tulu pump	1	Each	4,000.00	4000.00	4000.00	INR Four Thousand & Paise Zero Only
2.21	Supplying and fixing sinage with fixing stand post for public toilet for visible to passersby	5	Each	1,000.00	5000.00	5000.00	INR Five Thousand & Paise Zero Only
2.22	Supplying roaster/register for keeping account of regular cleaning (D1)	1	Each	200.00	200.00	200.00	INR Two Hundred & Paise Zero Only
2.23	Lettering on toilet wall for display of name and contact details of ULB, Ward number and name of maintenance authority, sanitary inspector, etc (D3)	1	Each	1,000.00	1000.00	1000.00	INR One Thousand & Paise Zero Only

2.24	Add L.W.C. @ 1%	1.00	Nos	403.05	403.05	403.05	403.05	403.05	INR Four Hundred Three & Paise Zero Five Only
3	ELECTRICAL WORK Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR'. (Precision make), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Plano Key Type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size 'Ph & N' copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish. [PWD Schedule Page No-E-14 Item No-2a] Average run 5 mtr	17.00	Point	624.24	10612.08	10612.08	10612.08	10612.08	INR Ten Thousand Six Hundred Twelve & Paise Zero Eight Only
3.02	Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Plano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish On Board (only for pay counter) [PWD Schedule Page No-E-15; I-4a]	2	Point	68.34	136.68	136.68	136.68	136.68	INR One Hundred Thirty Six & Paise Sixty Eight Only
3.03	Supplying and fixing 240V 32A Double Pole AC Type 30mA RCCB (Complete Set) (ISI marked) [Make-Legrand] (Cat No 4113/85) [Legrand Page No-92]	1	Nos	5,942.00	5942.00	5942.00	5942.00	5942.00	INR Five Thousand Nine Hundred Forty Two & Paise Zero Only
3.04	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necy, fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm) ECC [PWD Schedule Page No-E-14 Item No-1a(ii)]	17	No	121.38	2063.46	2063.46	2063.46	2063.46	INR Two Thousand Sixty Three & Paise Forty Six Only
3.05	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. a) For (2+4 way) (Make -Havells) [PWD Schedule Page No-D-9; Item No-13]	1	No	953.70	953.70	953.70	953.70	953.70	INR Nine Hundred Fifty Three & Paise Seventy Only
3.06	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection 6-32A SP MCB (Make -Havells) [PWD Schedule Page No-D-6; Item No-7]	4	Nos	171.36	685.44	685.44	685.44	685.44	INR Six Hundred Eighty Five & Paise Forty Four Only
3.07	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection. 40A DP MCB Isolator (Make -Havells) [PWD Schedule Page No-D-5; Item No-6]	1	Nos	212.16	212.16	212.16	212.16	212.16	INR Two Hundred Twelve & Paise Sixteen Only

3.08	Supply of TMC501 conventional industrial batten (Philips make) LED Tube, model no- TMC501 PXT-LED 22W P3241 [WB I & WD schedule P-113, I-5.3 F.22]	4	Nos	455.51	1822.04	1822.04	1822.04	INR One Thousand Eight Hundred Twenty Two & Paise Zero Four Only
3.09	Fixing only single twin fluorescent light fitting complete with all accessories directly on wall/ceiling by screws etc. [PWD Schedule Page No-C-2, Item No-14a]	4	Nos	87.72	350.88	350.88	350.88	INR Three Hundred Fifty & Paise Eighty Eight Only
3.1	Supply & fixing Bulk head light fittings with die cast aluminium housing frosted/clear glass on wall/ceiling incl S/F 9 watt LED Lamp complete set. [Make - Havells] [PWD sch - Page-D-13, I-23]	6	Nos	665.58	3993.48	3993.48	3993.48	INR Three Thousand Nine Hundred Ninety Three & Paise Forty Eight Only
3.11	Supply & fixing smart bright street light complete with all accessories to be fixed from the wall of building or on pole incl. making holes /providing clamping arrangement & necy. GI reducer as required S&F 40 mm GI Pipe 1.5 mtr average length & s&f necy length of 1.5 sqmm pvc insulated single core copper wire & making connections as required & mending good damages incl wall painting. (30 Watt) (Make - Bajaj) [WB I&WD sch P-111, I-F 9.0.2]	1	Nos	3,046.16	3046.16	3046.16	3046.16	INR Three Thousand Forty Six & Paise Sixteen Only
3.12	Supply of 8" domestic metal exhaust fan 9" (225mm) SWEEP, TRANS AIR - (Make-Crompton/Havells/Bajaj) [UD & MA schedule P-14, I-5]	4	Nos	1,863.00	7452.00	7452.00	7452.00	INR Seven Thousand Four Hundred Fifty Two & Paise Zero Only
3.13	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: 22.5 cm (9") [PWD Schedule Page No-C-4, Item No-28(b)]	4	Nos	251.94	1007.76	1007.76	1007.76	INR One Thousand Seven & Paise Seventy Six Only
3.14	Fixing only louver shutter/cover on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For 22.5 cm (9") Exhaust fan [PWD Schedule Page No-C-4, Item No-30(b)]	4	Nos	83.64	334.56	334.56	334.56	INR Three Hundred Thirty Four & Paise Fifty Six Only
3.15	Supply of 240V A.C Ceiling Fan (48" sweep, 1200 mm complete) [Make-Crompton] (for counter only) [UD & MA schedule P-23, I-70]	1	Each	2,283.00	2283.00	2283.00	2283.00	INR Two Thousand Two Hundred Eighty Three & Paise Zero Only
3.16	Fixing only Ceiling Fan [PWD sch P-C-3, I-21(a)]	1	Each	67.32	67.32	67.32	67.32	INR Sixty Seven & Paise Thirty Two Only
3.17	Supply & Fixing 240 V, 16/20 A. Piano key type switch (Brand approved by EIC) on sheet metal switch board incl. S & F 100x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brass screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required. (For Hand Dryer machine) [PWD sch P-E-6, I-17(b)]	2	Each	205.02	410.04	410.04	410.04	INR Four Hundred Ten & Paise Zero Four Only
3.18	S/F 240V 25A Modular type starter (brand approved by EIC) with 25 A. Modular switch DP MCB (C-Curve) and 4 Module G.I. Modular type switch board with 4 Module Top Cover Plate flushed in wall incl. S/F switch board and Cover Plate and making necy. Connections with PVC Copper wire and earth connectivity wire etc. as per schedule (for Pump) [PWD Schedule Page No-E-19, Item No-17] (Please follow in details)	1	Nos	799.68	799.68	799.68	799.68	INR Seven Hundred Ninety Nine & Paise Sixty Eight Only

3.19	Supply and Fixing of 2 mm Polyvinyl glow sign board made of 22 SWG GI sheet box with 1"X1" aluminum channel for fixing the vinyl board after necessary cutting the letter as required & slit LED tube light fittings along with all accessories. (16 sqft @495.00/sqft) (UD & MA schedule P-14, I-4)	1	Nos	7,920.00	7920.00	7920.00	INR Seven Thousand Nine Hundred Twenty & Paise Zero Only
3.2	Earthing installation by GI earth Spike (1830 X 20 mm) including 8SWG GI EarthWire & GI nuts, bolts, washer etc.	1	Nos	450.00	450.00	450.00	INR Four Hundred Fifty & Paise Zero Only
3.21	Add 18% GST	1.00	Nos	9097.64	9097.64	9097.64	INR Nine Thousand Ninety Seven & Paise Sixty Four Only
3.22	Cess@1%	1.00	Nos	596.40	596.40	596.40	INR Five Hundred Ninety Six & Paise Forty Only
Total In Figures					990957.86	990957.86	INR Nine Lakh Ninety Thousand Nine Hundred Fifty Seven & Paise Eighty Six Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					



Sub-Assistant Engineer
BADURIA MUNICIPALITY
North 24 Parganas



Chairman
BADURIA MUNICIPALITY
North 24 Parganas