



OFFICE OF THE COUNCILLORS  
**Jiaganj-Azimganj Municipality**

P.O.-Azimganj; Dist.-Murshidabad  
West Bengal; PIN-742122.

e-mail – jamunicipality@gmail.com  
Phone: 03483-253222

Memo No. **4551** /P.W.D./XXII-2(DMA)/J.A.M./2025,

Date : **23.9.2025**

**From: Chairman, Jiaganj – Azimganj Municipality.**

**To:**

S.S Construction,  
Jiaganj, Dist. Murshidabad.

**Sub : Work Order for** “Construction of Public Toilet (P.T) at Jiaganj Bhattapara, ward No -2, within Jiaganj - Azimganj Municipality. MODEL NO - G Civil Works, Electrical works and Non- schedule works TOILET- 4 NOS AND URINAL - 5 NOS.”

**Ref : N.I.e.T. Memo No – 3006/P.W.D/XXII-2(DMA)/J.A.M./2025. Date – 15.7.2025, NleT No – 16/2025, SI No - 10, Tender ID :- 2025\_MAD\_889057\_10**

Estimated amount : Rs. **9,46,538.00**  
Tender Amount : Rs. **9,44,549.99**

Contractual percentage : **0.21% (Zero point Two One percent) Below of schedule rate.**

Dear Sir(s),


In connection of the above subject and reference, you are hereby requested to start the work immediately. The time of completion is **60(Sixty) days**.

It should be noted clearly that the time bound completion of work is the essence of contract made with you.

This letter shall be treated as formal work order. You are hereby requested to please execute a formal agreement with the undersigned within 7(seven) working days from the date of this letter. You are also abide all terms and condition as per tender norms.

Thanking you,

Yours faithfully,

  
Chairman  
Jiaganj-Azimganj Municipality.

Chairman  
Jiaganj-Azimganj Municipality  
Date **23.9.2025**.

Memo No: **4551(7)**/P.W.D./XXII-2/J.A.M./2025,

Copy forwarded for information and necessary action to:

1. The Director, State Urban Development Agency (SUDA), ILGUS Bhaban, H.C. Block, Salt Lake City, Kolkata – 700 091 District Magistrate, Murshidabad.
2. The Executive Engineer, MED., Berhampore Division, You are requested for execution the above work.
3. The Executive Officer, Jiaganj-Azimganj Municipality.
4. The Finance Officer, Jiaganj - Azimganj Municipality.
5. Ataur Rahaman, Sub Assistant Engineer, Jiaganj – Azimganj Municipality.
6. Kausik Pandey, Technical Supervisor, Jiaganj – Azimganj Municipality.
7. The Account – in – charge, Jiaganj – Azimganj Municipality.

  
Chairman  
Jiaganj-Azimganj Municipality  
Chairman  
Jiaganj-Azimganj Municipality

Validate

Print

Help

[Percentage BoQ](#)

Tender Inviting Authority: Chairman, Jiaganj - Azimganj Municipality

Name of Scheme:-Construction of Public Toilet (P.T) at Jiaganj Bhattapara, ward No -2, within Jiaganj - Azimganj Municipality. MODEL NO - G Civil Works, Electrical works and Non- schedule works TOILET- 4 NOS AND URINAL - 5 NOS

Contract No: e N.I.T. No - 17/PWD/2025 SL NO-10

Bidder Name : SS CONSTRUCTION

**PRICE SCHEDULE**

**(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )**

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55		
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	8.696	cum	119.27	1037.17	INR One Thousand & Thirty Seven and Paise Seventeen Only		
2	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). (a) With earth obtained from excavation of foundation.	8.696	cum	77.54	674.29	INR Six Hundred & Seventy Four and Paise Twenty Nine Only		

3	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	7.542	cum	599.61	4522.26	INR Four Thousand Five Hundred & Twenty Two and Paise Twenty Six Only
4	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	37.10	sqm	326.00	12094.60	INR Twelve Thousand & Ninety Four and Paise Sixty Only
5	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. a) Pakur Variety / Chandil Variety PWD Building Works schedule, p-26 Item 10 a (Rate Analysis)	7.61	cum	5838.40	44430.22	INR Forty Four Thousand Four Hundred & Thirty and Paise Twenty Two Only
6	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering in ground floor and foundation. (a) 1:3:6 proportion.	3.710	cum	5061.44	18777.94	INR Eighteen Thousand Seven Hundred & Seventy Seven and Paise Ninety Four Only
7	25mm. thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacturer's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately). (Chequering not required over concrete or painted surface). [Note: - Waterproofing as per item 9, polymer based paint as per item 8(a) of subhead C of Section (C).	5.96	sqm	188.16	1121.43	INR One Thousand One Hundred & Twenty One and Paise Forty Three Only
8	125 mm brick work with 1st class bricks in cement mortar (1:4) in ground floor.	27.00	sqm	669.56	18078.12	INR Eighteen Thousand & Seventy Eight and Paise Twelve Only
9	Supplying and laying polythene sheet (150 gm/sq.m) over damp proof course or below flooring or roof terracing or foundation or foundation trenches.	23.21	sqm	24.00	557.04	INR Five Hundred & Fifty Seven and Paise Four Only
10	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (f) 25 mm to 30 mm shuttering without staging in foundation PWD Building Works schedule, Page -42, Item- 36.f	16.25	sqm	205.00	3331.25	INR Three Thousand Three Hundred & Thirty One and Paise Twenty Five Only

11	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. PWD Building Works schedule, Page -42, Item- 36.a	42.75	sqm	330.00	14107.50	INR Fourteen Thousand One Hundred & Seven and Paise Fifty Only
12	Artificial stone in floor ,dado, staircase with cement mortar (1:2:4)with stone chips lised in panels as directed with topping made with ordinary or white cement (as necessary) and marbel dust in proportion (1:2) in cluding smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/ sq.m all complete including all materials and labour. In ground floor 3 mm thick topping using gray cement (ii)25 mm	23.21	sqm	257.13	5967.99	INR Five Thousand Nine Hundred & Sixty Seven and Paise Ninety Nine Only
13	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m. (i) Tor steel/Mild Steel , JSPL/SWAYN/ELETRO/STEEL	0.724	MT	55366.22	40085.14	INR Forty Thousand & Eighty Five and Paise Fourteen Only
14	Collapsible gate with 40 mm x 10 mm x 6 mm Tee as top and bottom guide rail , 20 mm x 10 mm x 2 mm vertical channels 100 mm apart in full stretched position 20m x 5 mm MS flats as collapsible bracings properly reveted and washered including 38 mm steel roller including locking arrangements , fitted and fixed in position with lugs set in cement concrete including cutting necessary hikes chasing etc in walls , floors etc and making good all damages .	4.20	sqm	4330.00	18186.00	INR Eighteen Thousand One Hundred & Eighty Six Only
15	Brick work with 1st class bricks in cement mortar (1:6) (a) Foundation and plinth ground floor	3.785	cum	4882.81	18481.44	INR Eighteen Thousand Four Hundred & Eighty One and Paise
16	Brick work with 1st class bricks in cement mortar (1:4) (b) superstructure ground floor	17.89	cum	5105.81	91342.94	INR Ninety One Thousand Three Hundred & Forty Two and Paise Ninety Four Only

17	Labour for Chipping of concrete surface before taking up Plastering work.	23.21	sqm	21.00	487.41	INR Four Hundred & Eighty Seven and Paise Forty One Only
18	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster	184.29	sqm	139.71	25747.16	INR Twenty Five Thousand Seven Hundred & Forty Seven and Paise Sixteen Only
19	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (c) 10 mm thick plaster	23.21	Sqm	124.71	2894.52	INR Two Thousand Eight Hundred & Ninety Four and Paise Fifty Two Only
20	Neat cement punning about 1.5 mm thick in wall, dado, window sills, floors etc. . Note cement 0.152 m3/100 m2	14.48	Sq.m	32.85	475.67	INR Four Hundred & Seventy Five and Paise Sixty Seven Only
21	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria. (i) 66mm x 90mm	19.80	Mtr	497.00	9840.60	INR Nine Thousand Eight Hundred & Forty and Paise Sixty Only
22	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. (ii) 25 mm thick P-125, It- 14(ii)	6.30	Sqm	2581.00	16260.30	INR Sixteen Thousand Two Hundred & Sixty and Paise Thirty Only
23	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws . (vii) 225mm long x 10mm dia. bolt.	5.00	Each	84.00	420.00	INR Four Hundred & Twenty Only
24	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (viii) 100mm X 75mm X 3.50mm.	15.00	Each	66.00	990.00	INR Nine Hundred & Ninety Only

25	Anodised aluminium decorative handle (hexagonal / fluted) of approved quality fitted and fixed complete. (i) 150mm plate x 10mm dia rod x 12mm hexagonal/fluted.	10.00	Each	87.00	870.00	INR Eight Hundred & Seventy Only
26	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with concrete bolt and round fitting. b) 250mm long.	5.00	Each	159.00	795.00	INR Seven Hundred & Ninety Five Only
27	Supplying and laying chequered tiles of any shade and of approved quality with (1:1.5:3) cement concrete laid in panels or patterns as directed in pavement, footpath etc including necessary underlay 25 mm thick (avg) cement mortar (1:3) complete in all respect with all labour and materials. (Using cement slurry @4.4kg/sq.m at back side and @2.4 kg/sq.m for joint filling).	4.00	sq.m	467.00	1868.00	INR One Thousand Eight Hundred & Sixty Eight Only
28	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) In Ground Floor	207.50	Sqm	122.00	25315.00	INR Twenty Five Thousand Three Hundred & Fifteen Only
29	Applying interior grade Acrylic Primer of approved quality and brand on plastered and concrete surface old or new surface to receive Distemper Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the E-I-C (Ground Floor) ( b ) Two Coats	52.68	m2	44.20	2328.46	INR Two Thousand Three Hundred & Twenty Eight and Paise Forty Six Only
30	Dry Destempering interior walls or ceiling including cleaning, washing, smoothing surface (b) two coats	52.68	m2	49.00	2581.32	INR Two Thousand Five Hundred & Eighty One and Paise Thirty Two Only
31	Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Decorative Textured (Marrr Finish) or Smooth Finish Acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC in Ground Floor (b) two coats.	72.39	m2	45.10	3264.79	INR Three Thousand Two Hundred & Sixty Four and Paise Seventy Nine Only
32	Protective and Decorative Acrylic Exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over Acrylic primer as required. The rate includes cost of materials, labour, scaffolding and all incidental charges but excluding the cost of primer in ground floor (two coats)(a) normal acrylic emulsion.	72.39	m2	67.00	4850.13	INR Four Thousand Eight Hundred & Fifty and Paise Thirteen Only

33	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	6.35	Sqm	38.00	241.30	INR Two Hundred & Forty One and Paise Thirty Only
34	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	6.35	Sqm	81.00	514.35	INR Five Hundred & Fourteen and Paise Thirty Five Only
35	(a) M.S. or W.I. Ornamental grill of approved design joints continuously welded with M.S., W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor.. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr.	0.516	Qntl	9888.00	5102.21	INR Five Thousand One Hundred & Two and Paise Twenty One Only
36	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	5.16	Sqm	29.00	149.64	INR One Hundred & Forty Nine and Paise Sixty Four Only
37	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white)	5.16	Sqm	79.00	407.64	INR Four Hundred & Seven and Paise Sixty Four Only

38	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91kg./sqm or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 kg of cement per sqm below mortar only, joints grouted with admixture of white cement and colouring Pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) i) With application slurry @1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White	23.21	Sqm	1691.00	39248.11	INR Thirty Nine Thousand Two Hundred & Forty Eight and Paise Eleven Only
39	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. B) Wall Area of each tile above 0.09 Sq.m ii) Other than Coloured decorative including white Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composite door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film i) Natural white h) Louvered window. ii) Louvered Section.	82.43	Sqm	1038.00	85562.34	INR Eighty Five Thousand Five Hundred & Sixty Two and Paise Thirty Four Only
40	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composite door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film i) Natural white h) Louvered window. ii) Louvered Section.	8.40	M	183.00	1537.20	INR One Thousand Five Hundred & Thirty Seven and Paise Twenty Only
41	ii) Louvered Section.	7.20	M	658.00	4737.60	INR Four Thousand Seven Hundred & Thirty Seven and Paise Sixty Only
42	iii) Cleat angle ( Non-anodized).	6.48	M	263.00	1704.24	INR One Thousand Seven Hundred & Four Only

43	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. iv) 5mm thick coloured / tinted / smoke glass.	1.08	Sq.M.	585.00	631.80	INR Six Hundred & Thirty One and Paise Eighty Only
44	Painting block letters or digits in Black Japan or any approved paint as per direction. e) Size above 7.5 cm. and upto 10 cm.	450.00	Each	12.00	5400.00	INR Five Thousand Four Hundred Only
45	Supplying and planting of different plants / trees (supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads and lifts, carriage, handling, manuring applying pesticide and fertilizer etc. j) Furcaria Variegated 10 to 12 leaves in height 20-30 cm in earthen pot of size 25 cm	10.00	Each	162.00	1620.00	INR One Thousand Six Hundred & Twenty Only
46	x) Ficus blakii (F. Vivicon) well branched (Bushy) of height 120cm - 135 cm in earthen pot of size 30cm.	3.00	Each	187.00	561.00	INR Five Hundred & Sixty One Only
47	xxvi) Areca Palm 4 - 5 suckers of height 90 cm to 105 cm in earthen pots of size 25 cm.	3.00	Each	127.00	381.00	INR Three Hundred & Eighty One Only
48	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. a) With 'p' trap (with vent)	4.00	Each	3104.00	12416.00	INR Twelve Thousand Four Hundred & Sixteen Only
49	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete. (b) Anglo Indian (i) Plastic (hallow type) White	4.00	Each	380.00	1520.00	INR One Thousand Five Hundred & Twenty Only
50	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (ii) 470 mm X 280 mm X 340 mm	3.00	Each	945.00	2835.00	INR Two Thousand Eight Hundred & Thirty Five Only
51	Supplying fitting and fixing squatting plate with integrated flushing in white vitreous set in cement concrete (6:3:1) with jhama chips complete. ( Payment of concrete will be paid separately ) ( I ) 450 mm x 350 mm	2.00	each	881.00	1762.00	INR One Thousand Seven Hundred & Sixty Two Only
52	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	4.00	Nos	1015.00	4060.00	INR Four Thousand & Sixty Only

53	Supplying, fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete. i) Polythene Flush Pipe	4.00	Each	155.00	620.00	INR Six Hundred & Twenty Only
54	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. (a) C.P. urinal flush pipe fittings range of one	2.00	Each	414.00	828.00	INR Eight Hundred & Twenty Eight Only
55	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., mending good all damages and painting the brackets with two coats of approved paint. (ii) 550 mm X 400 mm size	2.00	Each	2208.00	4416.00	INR Four Thousand Four Hundred & Sixteen Only
56	Supplying fitting and fixing pedestal of approved make for wash basin ( White )	2.00	Each	1497.00	2994.00	INR Two Thousand Nine Hundred & Ninety Four Only
57	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia., (iii) 600 mm long	5.00	Each	107.00	535.00	INR Five Hundred & Thirty Five Only
58	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iv) 1050 mm long each	2.00	Each	91.00	182.00	INR One Hundred & Eighty Two Only
59	(f) Hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	5.00	Each	1251.00	6255.00	INR Six Thousand Two Hundred & Fifty Five Only
60	(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	7.00	Each	539.00	3773.00	INR Three Thousand Seven Hundred & Seventy Three Only
61	(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	5.00	Each	493.00	2465.00	INR Two Thousand Four Hundred & Sixty Five Only
62	Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand).	5.00	Each	815.00	4075.00	INR Four Thousand & Seventy Five Only
63	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand). (P. No. - 45, item. No. - 19(a)),	2.00	Each	555.00	1110.00	INR One Thousand One Hundred & Ten Only

64	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I), with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work PVC Pipes, 25 mm	25.00	Mtr	177.00	4425.00	INR Four Thousand Four Hundred & Twenty Five Only
65	(a) For Exposed Work PVC Pipes, 15 mm	10.00	Mtr	101.00	1010.00	INR One Thousand & Ten Only
66	(b) For Concealed Work PVC Pipes, 15 mm	10.00	Mtr	137.00	1370.00	INR One Thousand Three Hundred & Seventy Only
67	Supplying and fitting fixing of gunmetal wheel valve of approved brand and make tested to 21 Kg per sq. cm. 25 mm dia(E5)	2.00	Each	778.00	1556.00	INR One Thousand Five Hundred & Fifty Six Only
68	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity	2.00	Each	5128.00	10256.00	INR Ten Thousand Two Hundred & Fifty Six Only
69	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L.	2.00	Each	96.00	192.00	INR One Hundred & Ninety Two Only
70	Labour for punching hole in plastic water storage tank upto 50 mm dia.	4.00	Each	19.00	76.00	INR Seventy Six Only
71	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992.(A) (i) Single Socketed 3 Meter Length, (b) 110 mm	30.00	Mtr	292.00	8760.00	INR Eight Thousand Seven Hundred & Sixty Only
72	(B) Fittings (i) Coupler, (b) 110 mm	8.00	Each	85.00	680.00	INR Six Hundred & Eighty Only
73	(ii) Plain Tee, (b) 110 mm	12.00	Each	85.00	1020.00	INR One Thousand & Twenty Only
74	(iii) Door Tee, (b) 110 mm	10.00	Each	195.00	1950.00	INR One Thousand Nine Hundred &
75	ix) Bend 45°, (b) 110 mm	10.00	Each	89.00	890.00	INR Eight Hundred & Ninety Only
76	xi) Door Bend (T.S.), (b) 110 mm	7.00	Each	147.00	1029.00	INR One Thousand & Twenty Nine

77	xvi) Pipe Clip, (b) 110 mm	30.00	Each	21.00	630.00	INR Six Hundred & Thirty Only
78	xvii) W.C. Connector (150 mm long) 125 X 110(W/WC Ring) 75 mm	4.00	Each	142.00	568.00	INR Five Hundred & Sixty Eight Only
79	xxx) Plain Floor Trap with Top tile & Strainer 75 mm	7.00	Each	144.00	1008.00	INR One Thousand & Eight Only
80	L) Rubber Ring, (b) 110 mm	15.00	Each	17.00	255.00	INR Two Hundred & Fifty Five Only
81	C) Rubber Lubricant 500 ML	1.00	500 ML	187.00	187.00	INR One Hundred & Eighty Seven Only
82	D) Solvent Cement 250 ML	1.00	250 ML	103.00	103.00	INR One Hundred & Three Only
83	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in total pipeline including specials. (B) Under ground, (ii) 110 mm dia.	25.00	Mtr	84.00	2100.00	INR Two Thousand One Hundred Only
84	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materials (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete. A) UPVC Pipes: (i) 75 mm. Dia. (P. - 212, Item. No. - 21 (A)(i) , (B),(C),(i) & (B), (d),(i), Pwd volume- I, 2017)	30.00	Mtr	188.00	5640.00	INR Five Thousand Six Hundred & Forty Only
85	B) UPVC Fittings: c) Bend 87.5 degree (i) 75 mm. Dia.	6.00	Mtr	95.00	570.00	INR Five Hundred & Seventy Only
86	B) UPVC Fittings: d) Shoe (i) 75 mm. Dia.	2.00	Mtr	78.00	156.00	INR One Hundred & Fifty Six Only

87	<p>Constructing inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling, 15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials.</p> <p>i) With Pakur variety (Other than SAIL/TATA/RINL).</p>	3.00	Each	6831.00	20493.00	INR Twenty Thousand Four Hundred & Ninety Three Only
88	<p>Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L. floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C (1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and filling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials.</p> <p>(ii) For 20 users A) With Pakur variety. (JSW/JISPL/SHYAM/SRMB/ELECTROSTEEL/SSL)</p>	1.00	Each	45939.00	45939.00	INR Forty Five Thousand Nine Hundred & Thirty Nine Only

89	Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm intermediate cement brick work (1:4) band all round and cement brick work (1:4) upto 0.90 metre from top with 20mm thick cement plastering (1:4) to inside face upto the depth of cement brick work, 15mm thick cement plaster (1:4) on outer face from top of the well upto G.L. and 6 mm thick cement plaster (1:4) on top of the R.C.C. cover slab including filling bottom 1.00 metre of inside of the well with brick metal (50 mm to 63 mm size) including R.C.C. cover slab of 100 mm thick with cement conc (1:1.5:3) with stone chips with necessary reinforcement and shuttering including one 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the cover slab with necessary fittings, making necessary arrangements for pipe connections, excavation of well including shoring, dewatering and removing the excess earth from the premises as per direction complete in all respect with all costs of labour and materials. With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia. (Other than SAIL/TATA/RINL) S.P. 89, Item No-4 7th Corrigenda Volume ii	1.00	Each	15535.00	15535.00	INR Fifteen Thousand Five Hundred & Thirty Five Only
90	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long	2.00	Each	430.00	860.00	INR Eight Hundred & Sixty Only
91	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	2.00	Each	484.00	968.00	INR Nine Hundred & Sixty Eight Only
92	Supplying, fitting and fixing soap holder. (b) Fibre glass	4.00	Each	58.00	232.00	INR Two Hundred & Thirty Two Only
93	Supplying, fitting and fixing glass shelf with aluminium guard rails, (a) Ordinary type with 5.5 mm sheet glass (i) 450 mm X 125 mm	2.00	Each	341.00	682.00	INR Six Hundred & Eighty Two Only
94	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Plano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size "ph & N" copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish. Average run 5mtr	18	Point	642.60	11566.80	INR Eleven Thousand Five Hundred & Sixty Six and Paise Eighty Only

95	Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish <b>On Board (only for pay counter)</b>	1	Point	70.35	70.35	INR Seventy and Paise Thirty Five Only
96	Supplying and fixing 240V 32A Double Pole AC Type 30mA RCCB, (Complete Set) (ISI marked) [Make- Legrand] (Cat No 4113/95) [ Legrand Page No- 92 ]	1	Nos	5942.00	5942.00	INR Five Thousand Nine Hundred & Forty Two Only
97	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necy. fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm) ECC	15	mtr	124.95	1874.25	INR One Thousand Eight Hundred & Seventy Four and Paise Twenty Five Only
98	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. <b>a) For (2+4 way) (Make -Havells)</b> <b>(upto 6 seats) or b) For (2+6 way) (Make -Havells)(above 6 seats)</b>	1	No	981.75	981.75	INR Nine Hundred & Eighty One and Paise Seventy Five Only
99	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection 6-32A SP MCB (Make-Havells)	4	Nos	176.40	705.60	INR Seven Hundred & Five and Paise Sixty Only
100	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection.32A DP MCB Isolator (Make -Havells)	1	Nos	218.40	218.40	INR Two Hundred & Eighteen and Paise Forty Only
101	Supply of TMC501 conventional industrial batten (Philips make) LED Tube, model no- TMC501 P1XT-LED 22W P3241	5	Nos	460.02	2300.10	INR Two Thousand Three Hundred and Paise Ten Only
102	Fixing only single/twin fluorescent light fitting complete with all accessories directly on wall/ceiling by screws etc..	5	Nos	90.30	451.50	INR Four Hundred & Fifty One and Paise Fifty Only

103	Supply & fixing Bulk head light fittings with die cast aluminium housing frosted/clear glass on wall/ceiling incl S/F 9 watt LED Lamp complete set. <b>[Make - Havells]</b>	6	Nos	682.95	4097.70	INR Four Thousand & Ninety Seven and Paise Seventy Only
104	Supply & fixing smart bright street light complete with all accessories to be fixed from the wall of building or on pole incl. making holes /providing clamping arrangement & necy. GI reducer as required. S&F 40 mm GI Pipe 1.5 mtr average length & s&f necy length of 1.5 sqmm pvc insulated single core copper wire & making connections as required & mending good damages incl wall painting. <b>(30 Watt) (Make - Bajaj)</b>	1	Nos	3076.32	3076.32	INR Three Thousand & Seventy Six and Paise Thirty Two Only
105	Supply of 12" domestic metal exhaust fan 9" (225mm) SWEEP. TRANS AIR - <b>(for 4 seats)</b> or 230V 50 Hz (Model- Trans Air 12" Grey) <b>(above 4 seats) ( Make- Crompton/Havells/Bajaj)</b>	4	Nos	1863.00	7452.00	INR Seven Thousand Four Hundred & Fifty Two Only
106	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: 22.5 cm ( 9" ) or 30 cm (12").	4	Nos	259.35	1037.40	INR One Thousand & Thirty Seven and Paise Forty Only
107	Fixing only lower shutter/cowl on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For 22.5 cm(9") Exhaust fan or For 30 cm(12") Exhaust fan	4	Nos	86.10	344.40	INR Three Hundred & Forty Four and Paise Forty Only
108	S/F 240V 25A Modular type starter (brand approved by EIC) with 25 A. Modular switch DP MCB (C-Curve) and 4 Module G.I. Modular type switch board with 4 Module Top Cover Plate flushed in wall incl. S/F switch board and Cover Plate and making necy. Connections with PVC Copper wire and earth connectivity wire etc. as per schedule <b>[for Pump]</b>	1	Nos	823.20	823.20	INR Eight Hundred & Twenty Three and Paise Twenty Only
109	Supply of 240V A.C Ceiling Fan ( 48" sweep, 1200 mm complete) <b>[Make-Crompton ( for counter only)]</b>	1	Each	2283.00	2283.00	INR Two Thousand Two Hundred & Eighty Three Only
110	Fixing only Ceiling Fan	1	Each	69.30	69.30	INR Sixty Nine and Paise Thirty Only

111	Supply & Fixing 240 V, 16/20 A Piano key type switch (Brand approved by EIC) on sheet metal switch board incl. S & F 100x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brass screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required. (For Hand Dryer machine)	2	Each	211.05	422.10	INR Four Hundred & Twenty Two and Paise Ten Only
112	Supply and Fixing of 2 mm Polyvinyl glow sign board made of 22 SWG GI sheet box with 1"X1" aluminum channel for fixing the vinyl board after necessary cutting the letter as required & s/v LED tube light fittings along with all accessories. (16 sqft @495.00/sqft)	1	Nos	7920.00	7920.00	INR Seven Thousand Nine Hundred & Twenty Only
113	Earthing installation by GI earth Spike (1830 X 20 mm) including 8SWG GI EarthWire & GI nuts, bolts, washer etc.	1	Nos	450.00	450.00	INR Four Hundred & Fifty Only
114	Non Shedule Item Sl. No. 91-106 ( Order as per SUDA) standard plastic dustbin (12lits)	8	Each	350	2800.00	INR Two Thousand Eight Hundred Only
115	Air freshner(pack of 4nos)	8	Each	216	1728.00	INR One Thousand Seven Hundred & Twenty Eight Only
116	Air freshner (Napthaline 250 gm)	6	Each	210	1260.00	INR One Thousand Two Hundred & Sixty Only
117	supplying paper Napkin	6	Each	50	300.00	INR Three Hundred Only
118	Supplying Sanitary Napkin ( Whisper or similar make 50 pcs )	6	Each	520	3120.00	INR Three Thousand One Hundred & Twenty Only
119	Harpic (blue 500 ml)	4	Each	300	1200.00	INR One Thousand Two Hundred Only
120	Harpic (Red 500 ml)	8	Each	150	1200.00	INR One Thousand Two Hundred Only
121	Gala double lip floor wiper	4	Each	350	1400.00	INR One Thousand Four Hundred Only
122	colin glass or surface cleaner	4	Lit	200	800.00	INR Eight Hundred Only
123	Muriatic Acid	4	Lit	145	580.00	INR Five Hundred & Eighty Only
124	Bleaching powder	6	Kg	120	720.00	INR Seven Hundred & Twenty Only
125	Dettol ,lifeboy or similar make liquid soap	10	lit	140	1400.00	INR One Thousand Four Hundred Only
126	Rubber hand gloves	6	Pair	80	480.00	INR Four Hundred & Eighty Only

127	Double side plastic brush	6	Each	125	750.00	INR Seven Hundred & Fifty Only
128	Plastic Broom	4	Each	170	680.00	INR Six Hundred & Eighty Only
129	supplying roaster /register for keeping account of regular cleaning	3	Each	200	600.00	INR Six Hundred Only
130	Signage ACP Base & reflective vinyl	1	Each	3776	3776.00	INR Three Thousand Seven Hundred & Seventy Six Only
131	Supplying and fixing sinage with fixing stand post for public toilet for visible to passersby	5	Each	1000	5000.00	INR Five Thousand Only
132	Add 18% GST over summation of sl no 01 to 113	1.000	Lot	138717.77	138717.77	INR One Lakh Thirty Eight Thousand Seven Hundred & Seventeen and Paise Seventy Seven Only
133	Add 1% Labour Welfare Cess over summation of sl no 01 to 132	1.000	Lot	9371.66	9371.66	INR Nine Thousand Three Hundred & Seventy One and Paise Sixty Six Only
<b>Total in Figures</b>					<b>946537.72</b>	
<b>Quoted Rate in Figures</b>					<b>944549.99</b>	
<b>Quoted Rate in Words</b>					<b>INR Nine Lakh Forty Four Thousand Five Hundred and Paise Ninety Nine Only</b>	

  
S.A.E. 23/9/24  
Jiaganj Azimganj Municipality

  
Chairman  
Jiaganj Azimganj Municipality