

**CONSTRUCTION OF TOILET BLOCK (CT) AT BANSBERIA GANGES HIGH SCHOOL - 2 IN WARD NO 9,
UNDER BANSBERIA MUNICIPALITY (MODEL NO - B CIVIL WORKS)
TOILET SEATS- 8 NOS URINAL -14 NOS**

SL.NO	Item Description & Item No.	Quantity	Rate	Unit	Ammount
1	<p>Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete.</p> <p>(a) Depth of excavation not exceeding 1,500 mm. PWD Building Works schedule Page - 1, Item -2.a</p> <p>COLM. $4 \times 3 \times 1.20 \times 1.20 \times 1.00 = 17.28$ M3 Ramp $2 \times 2.50 \times 0.375 \times 0.150 = 0.281$ M3 partition wal $1 \times 1.00 \times 0.375 \times 0.150 = 0.056$ m3 Bondary wall $2 \times 14.00 \times 0.500 \times 0.375 = 5.250$ m3 $1 \times 10.50 \times 0.500 \times 0.375 = 1.969$ m3</p>	24.836	11927.00	%Cu.m	2962.19
2	<p>Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work).</p> <p>(a) With earth obtained from excavation of foundation. PWD Building Works schedule, Page - 1, Item -3.a</p>	17.617	7754.00	%Cum	1366.02
3	<p>(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)</p> <p>PWD Building Works schedule, Page - 2, Item -4.a</p> <p>$1 \times 7.750 \times 7.40 \times 0.325 = 18.639$ m3</p>	18.639	71181.00	%Cum	13267.43
4	<p>Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. PWD Building Works schedule, Page- 14, Item - 1 (Corri. Page-01, Date-04-06-2018)</p> <p>$4 \times 3 \times 1.20 \times 1.20 = 17.28$ m2 $2 \times 2.50 \times 0.375 = 1.88$ m2 $1 \times 1.00 \times 0.375 = 0.375$ m2 $2 \times 1.50 \times 1.00 = 3.00$ m2 $1 \times 7.750 \times 7.40 = 57.35$ m2</p>	79.890	357.00	Sqm	28520.73

5	<p>Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes.</p> <p>a) Pakur Variety /Chandil Variety</p> <p>PWD Building Works schedule, p-26 Item 10 a (Rate Analysis) 4 x 3</p> <p>$4 \times 3 \times 1.20 \times 1.20 \times 0.150 = 2.592 \text{ m}^3$ 4 x 3 x</p> <p>$(1.20 \times 1.20) + (0.250 \times 0.250) / 2 \times 0.150 = 1.352 \text{ m}^3$ 4 x 3 x</p> <p>$0.250 \times 0.250 \times 3.90 = 2.926 \text{ m}^3$ 4 x 2 x</p> <p>$3.325 \times 0.250 \times 0.250 = 1.663 \text{ m}^3$ 3 x 3 x</p> <p>$2.25 \times 0.250 \times 0.250 = 1.266 \text{ m}^3$ 4 x 2</p> <p>$3 \times 3.325 \times 0.250 \times 0.150 = 0.998 \text{ m}^3$ 3</p> <p>$3 \times 2.25 \times 0.250 \times 0.150 = 0.759 \text{ m}^3$</p> <p>$1 \times 7.750 \times 7.40 \times 0.125 = 7.169 \text{ m}^3$</p>	17.057	5496.66	Cum	93756.53
6	<p>Cement concrete with graded jhama khoa (30 mm size) excluding shuttering in ground floor and foundation. (a) 1:3:6 proportion. PWD Building Works schedule, Page - 23, Item -B.1.a, (Corri. Page- 09, Date-04-06-2018) Rate Analysis1 (Corri. Page-01, Date-04-06-2018)</p> <p>$4 \times 3 \times 1.20 \times 1.20 \times 0.10 = 1.728 \text{ m}^3$</p> <p>$2 \times 2.50 \times 0.375 \times 0.100 = 0.188 \text{ m}^3$</p> <p>$1 \times 1.00 \times 0.375 \times 0.100 = 0.0375 \text{ m}^3$</p> <p>$2 \times 1.50 \times 1.00 \times 0.100 = 0.300 \text{ m}^3$</p> <p>$1 \times 7.75 \times 7.40 \times 0.100 = 5.735 \text{ m}^3$</p> <p>$2 \times 14.00 \times 0.500 \times 0.100 = 1.400 \text{ m}^3$</p> <p>$1 \times 10.50 \times 0.500 \times 0.100 = 0.525 \text{ m}^3$</p>	9.914	4784.44	m3	47430.55
7	<p>25mm. thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacturer's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2 nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately). (Chequering not required over concrete or painted surface). [Note:</p> <p>- Waterproofing as per item 9, polymer based paint as per item 8</p> <p>(a) of subhead C of Section (C).</p> <p>PWD Building Works schedule, Page -47, Item -1 (Rate Analysis)</p> <p>$3 \times 7.75 \times 0.250 = 5.81 \text{ m}^2$</p> <p>$2 \times 7.40 \times 0.250 = 3.70 \text{ m}^2$</p>	9.510	263.00	Sqm	2501.13

8	<p>125 mm brick work with 1st class bricks in cement mortar (1:4) in ground floor. P.W.D Building Works schedule, Page -16, Item-16, cori page -3, date -04.06.2018 (Rate Analysis) $2 \times 3.325 \times 3.00 = 19.95 \text{ m}^2$ $2 \times 11.00 \times 3.00 = 6.60 \text{ m}^2$ $2 \times 14.00 \times 1.50 = 4.20 \text{ m}^2$ $1 \times 10.50 \times 1.50 = 15.75 \text{ m}^2$</p>	46.500	714.56	Sq.M.	33227.04
9	<p>Supplying and laying polythine sheet (150 gm/sq.m) over dampproof course or below flooring or roof terracing or foundation or foundation trenches. P.W.D Building Works schedule, Page -47, Item-3</p>	57.350	24.00	Sq.M.	1376.40
10	<p>Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (f) 25 mm to 30 mm shuttering without staging in foundation P.W.D Building Works schedule, Page -42, Item- 36.f $3 \times 2 \times 7.75 \times 0.250 = 11.63 \text{ m}^2$ 4x 2 $3 \times 7.40 \times 0.25 = 14.80 \text{ m}^2$ 4 x $3 \times 4 \times 1.20 \times 0.150 = 22.32 \text{ m}^2$</p>	48.730	209.00	Sqm	10184.57
11	<p>Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. P.W.D Building Works schedule, Page -42, Item- 36.a $7.75 \times 7.40 = 57.35 \text{ m}^2$ 1 x $7.40 \times 0.125 = 3.79 \text{ m}^2$ 2(7.75 + $3 \times 3.00 = 39.60 \text{ m}^2$ 4 x 3x2(.30+.025 $7.75 \times 0.125 = 5.81 \text{ m}^2$ 3 x 2 x $7.40 \times 0.125 = 14.80 \text{ m}^2$ 3x 4 x 2x2 x</p>	121.350	335.00	Sqm	40652.25
12	<p>Artificial stone in floor ,dado, staircase etc with cement mortar (1:2:4) with stone chips sized in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/ sq.m all complete including all materials and labour. In ground floor 3 mm thick topping using gray cement (ii) 25 mm 7.75 x P.W.D Building Works schedule, p-48 Item 6(ii) 7.75 x $7.40 = 57.35 \text{ m}^2$</p>	57.350	254.13	Sq.m	14574.36

13	<p>Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m.</p> <p>(i) Tor steel/Mild Steel , JSPL/SWAYN/ELETRO/STEEL PWD Building Works schedule, Page - 43, Item - 40.a.i.1(Corri. 10th Page-01, Date-23-01-2020) (Rate Analysis) Item no , vol of conc. $17.06 \times 1.20 \% = 0.2047 \text{ m}^3 \times 35.315 \text{ c.ft} = 7.23 \text{ c.ft} \times 225 \text{ kg} = 1626.75 \text{ kg} = 1.627 \text{ MT}$</p>	1.627	54400.74	M.T.	88510.00 ✓
14	<p>Collapsible gate with 40 mm x 10 mm x 6 mm Tee as top and bottom guide rail , 20 mm x 10 mm x 2 mm vertical channels 100 mm apart in full stretched position 20m x 5 mm MS flats as collapsible bracings properly reveted and washered including 38 mm steel roller including locking arrangements , fitted and fixed in position with lugs set in cement concrete including cutting necessary hikes chasing etc in walls , floors etc and making good all damages .</p> <p>PWD Building Works schedule, Page -106, Item- .18 $2 \times 1.00 \times 2.10 = 4.20 \text{ m}^2$</p>	4.200	4330.00	Sqm	18186.00 ✓
15	<p>Brick work with 1st class bricks in cement mortar (1:4) (a) Foundation and plinth ground floor PWD Building Works schedule, Page -15, Item-7.a (Rate Analysis) $3 \times 7.75 \times 0.250 \times 0.600 = 3.488 \text{ m}^3$ $2 \times 7.40 \times 0.250 \times 0.600 = 2.22 \text{ m}^3$ $2 \times 2.50 \times 0.250 \times 0.600 = 0.750 \text{ M}^3$ $2 \times 1.00 \times 0.500 \times 0.300 = 0.300 \text{ M}^3$ Bondary wall $2 \times 14.00 \times 0.375 \times 0.225 = 2.363 \text{ m}^3$ 1 $1 \times 10.50 \times 0.375 \times 0.225 = 0.886 \text{ m}^3$</p>	9.332	5491.93	Cu.m	51250.69 ✓
16	<p>Brick work with 1st class bricks in cement mortar (1:4) (b) superstructure ground floor PWD Building Works schedule, Page -15, Item-7.b (Rate Analysis) $3 \times 7.75 \times 0.250 \times 3.00 = 17.438 \text{ m}^3$ $2 \times 7.40 \times 0.250 \times 3.00 = 11.10 \text{ m}^3$</p>	28.538	5714.93	Cu.m	163092.67 ✓
17	<p>Labour for Chipping of concrete surface before taking up Plastering work. PWD Building Works schedule, P-192, It-1</p>	57.350	21.00	Sqm	1204.35 ✓
18	<p>Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster PWD Building Works schedule, P-189 It- No. 1 (Rate Analysis) 2($7.75 + 7.40) \times 3.75 = 113.63 \text{ m}^2$ 2($7.75 + 7.40) \times 3.00 = 90.90 \text{ m}^2$ 10x2 $\times 1.60 \times 3.00 = 96.00 \text{ m}^2$ 11x $2 \times 1.20 \times 3.00 = 79.20 \text{ m}^2$ 2 x2 $\times 14.00 \times 1.50 = 84.00 \text{ m}^2$ 1x10.50 $\times 2 \times 1.50 = 63.00 \text{ m}^2$</p>	526.730	141.71	Sqm	74642.91 ✓

19	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (c) 10 mm thick plaster PWD Building Works schedule, P-189 It- No. 1 (ii)(c) (Rate Analysis) $7.75 \times 7.400 = 57.35 \text{ m}^2$	57.350	126.71	Sqm	7266.82 ✓
20	Neat cement punning about 1.5 mm thick in wall, dado, window sills, floors etc . Note cement 0.152 m3/100 m2 PWD Building Works schedule, P-192 It- No. 15 $(1 \times 7.40 + 2 \times 7.75) \times 0.75 = 17.18 \text{ m}^2$ $2(1 \times 11.00 + 2 \times 14.00) \times 0.750 = 58.50 \text{ m}^2$	75.680	32.85	Sq.m	2486.09 ✓
21	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria.. (i) 66mm x 90mm PWD Building Works schedule, P-115, It - 3 (i) 10 ($2 \times 2.10 + 0.75) = 49.50$	49.500	497.00	Mtr	24601.50 ✓
22	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. ii) 25 mm thick P-125, It- 14(ii) 10 $x 2.10 \times 0.75 = 15.75 \text{ m}^2$	15.750	2581.00	Sqm	40650.75 ✓
23	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws . (vii) 225mm long x 10mm dia. bolt. PWD Building Works schedule, P-144, It No. 26 (vii)	10.000	84.00	Each	840.00 ✓
24	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (viii) 100mm X 75mm X 3.50mm. PWD Building Works schedule, P-140, It No. -5 (viii)	30.000	66.00	Each	1980.00 ✓
25	Anodised aluminium decorative handle (hexagonal / fluted) of approved quality fitted and fixed complete. (i) 150mm plate x 10mm dia rod x 12mm hexagonal/fluted. PWD Building Works schedule, Page -146 . Item no-31,(i)	20.000	87.00	Each	1740.00 ✓
26	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with concrete bolt and round fitting. .b)250mm long. PWD Building Works schedule, Page -141 . Item no-10 b)	10.000	159.00	Each	1590.00 ✓
27	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) In Ground Floor PWD Building Works schedule, PWD, P- 198, I - 5 $526.73 + 57.35 = 584.08$	584.080	122.00	Sqm	71257.76 ✓

28	<p>Supplying and laying chequered tiles of any shade and of approved quality with (1:1.5:3) cement concrete laid in pannels or patterns as directed in pavement ,footpath etc including necessary underlay 25 mm thick (avg)cement mortar (1:3) complete in all respect with all labour and materials .(Using cement slurry @4.4kg/sq.m at back side and @2.4 kg/sq.m for joint filling). PWD Building Works schedule, Page -74 , Item no- 46(i) .</p> <p>25 mm thick $2 \times 1.50 \times 1.50 = 3.00 \text{ m}^2$ $2 \times 1.00 \times 2.125 = 4.25 \text{ m}^2$ $2 \times 14.00 \times 1.50 = 42.00 \text{ M}^2$ $1 \times 10.50 \times 1.50 = 15.75 \text{ M}^2$</p>	65.000	470.00	sq.m	30550.00 ✓
29	<p>Applying interior grade Acrylic Primer of approved quality and brand on plastered and concrete surface old or new surface to receive Distemper Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the E-I-C (Ground Floor) (b) Two Coats PWD Building Works schedule, Page -74 , Item no- 46(i) .</p> <p>$90.90 + 79.20 + 84.00 - 186.28 = 67.83$</p>	67.830	44.20	m2	2998.09 ✓
30	<p>Dry Destempering interial walls or ceiling including cleaning, washing, smoothening surface (b) two coats PWD Building Works schedule, Page -196 , Item no- 9(b) .</p>	67.830	49.00	m2	3323.67 ✓
31	<p>Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Decorative Textured (Martt Finish) or Smooth Finish Acrylic exterior emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC in Ground Floor (b) two coats. PWD Building Works schedule, Page -196 , Item no- 8(b)</p> <p>$113.63+84.00+63.00 = 260.63 \text{ m}^2$</p>	260.630	45.10	m2	11754.41 ✓

32	<p>Protective and Decorative Acrylic Exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over Acrylic primer as required. The rate includes cost of materials, labour, scaffolding and all incidental charges but excluding the cost of primer in ground floor (two coats)(a) normal acrylic emulsion. P.W.D Building Works schedule, Page -197 , Item no-17(a) $113.63+84.00 +63.00 = 260.63 \text{ m}^2$</p>	260.630	67.00	m2	17462.21 ✓
33	<p>(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. P.W.D Building Works schedule, Page -200 . Item no- 1 (b)</p>	6.350	38.00	Sqm	241.30 ✓
34	<p>(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : Page - 200 . Item no- 1 (b) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) P.W.D Building Works schedule, Page -200 . Item no- 2(A)(a)(iv)</p>	6.350	81.00	Sqm	514.35 ✓
35	<p>(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor.. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr. P.W.D Building Works schedule, P-104 Item-13 A (i) (3rd Corrigendum Page No 91) $10 \times 0.600 \times 0.600 = 3.60 \text{ m}^2$ $2 \times 2.00 \times 0.750 = 3.00 \text{ m}^2$ $= 6.60 \times 10.00 \text{ kg} = 66.00 \text{ kg} = 0.66 \text{ qtl}$</p>	0.660	9888.00	Qntl	6526.08 ✓
36	<p>a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. P.W.D Building Works schedule, P/200 Item-1(a) $10 \times 0.600 \times 0.600 = 3.60 \text{ m}^2$ $2 \times 2.00 \times 0.750 = 3.00 \text{ m}^2$</p>	6.600	29.00	Sqm	191.40 ✓
37	<p>(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white) P.W.D Building Works schedule, P-200 Item-2(b)(iv) $10 \times 0.600 \times 0.600 = 3.60 \text{ m}^2$ $2 \times 2.00 \times 0.750 = 3.00 \text{ m}^2$</p>	6.600	79.00	Sqm	521.40 ✓

38	<p>Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring Pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish</p> <p>complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrr[e]</p> <p>l (l) With application slurry @1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment.</p> <p>(A) Deep Colour & White PWD Building Works schedule, Page-66 Item-36 (A) (3rd Floor 7.75 x 7.40 = 57.35 m2</p>	57.350	1695.00	Sqm	97208.25 ✓
39	<p>Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.</p> <p>B) Wall</p> <p>Area of each tile above 0.09 Sq.m</p> <p>Other than Coloured decorative including white</p> <p>PWD Building Works schedule, page-64, Item:35.(B.) (b).(ii) (3rd Corrigendam ,Page 36)</p> <p>2(7.75 + 7.40) x 2.10 = 63.63 m2</p> <p>1.60 x 2.10 = 67.20 m2</p> <p>x 1.20 x 2.10 = 55.44 m2</p> <p>b) ii)</p> <p>10x2 x 11 x 2</p>	186.270	707.00	Sqm	131692.89 ✓
40	<p>Supplying Fitting and Fixing Black Stone slab used in kitchen slab, alcove wardrobe etc. laid and joined with adhesive cement mortar (1:2) including grinding or polishing as per direction of EIC in Ground Floor</p> <p>(a) Slab thickness 20 - 25 mm</p> <p>PWD S&P Schedule, page-53, item no -15 (a)</p> <p>2 x 7.60 x 0.750 = 11.40 m2</p>	11.200	642.00	m2	7190.40 ✓
41	<p>Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In- Charge. (Payment will be made on finished length of the work).</p> <p>(A) In 10-12 Micron thickness Anodizing film</p> <p>l) Natural white h) Louvered window.</p> <p>Top, bottom and side member.</p> <p>PWD Building Works schedule, PWD, P-233, l- 1(h) i</p> <p>i)</p>	8.400	183.00	M	1537.20 ✓
42	ii) Louvered Section.	7.200	658.00	M	4737.60 ✓

43	iii) Cleat angle (Non-annodized).				
44	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. iv) 5mm thick coloured / tinted / smoke glass. PWD Building Works schedule, P-243, I-9	6,480	263.00	M	1704.24
45	Painting block letters or digits in Black Japan or any approved paint as per direction. e) Size above 7.5 cm. and upto 10 cm. PWD Building Works schedule, P-268, It-17(e)	1,080	585.00	Sq.M.	631.80
46	Supplying and Planting of different plant / trees (Supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads & lift, carriage, handling, manuring, applying pesticide and fertilizer etc. . i) Furcaria variegated 10-12 leaves in height 20-30cm in earthen pots of size 25cm. PWD Building Works schedule, Page -261, It- 9 (i)	450	12.00	Each	5400.00
47	x) Ficus blakii (F. Vivicon) well branched (Bushy) of height 120cm - 135 cm in earthen pot of size 30cm. PWD Building Works schedule, Page -261, It- 9 (x)	4	162.00	Each	648.00
48	xxvi) Areca Palm 4 - 5 suckers of height 90 cm to 105 cm in earthen pots of size 25 cm. PWD Building Works schedule, Page -261, It- 9 (xxvi)	3	187.00	Each	561.00
	SANITARY AND PLUMBING WORKS				
49	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. a) With 'P' trap (with vent) PWD S&P Schedule, page-79, item no -3 (a)	8	3965.00	Each	31720.00
50	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete .(b) Anglo Indian (i) Plastic (hallow type) White PWD S&P Schedule, page-81,item no 10.b.i	8	572.00	Each	4576.00
51	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (ii) 470 mm X 280 mm X 340 mm PWD S&P Schedule, page.80,item no-6/(ii)	5	820.00	Each	4100.00
52	Supplying , fittingand fixing 18 mm thick marbel partition slab with chawk doongri square cut , both sides polished with two corners rounded and edges polished. PWD S&P Schedule, P-84 It-13), 5 x 1.20 x 0.600 = 3.60 m2	4	1426.00	m2	5133.60
53	Supplying fitting and fixing squatting plate with integrated flushing in white vitreous set in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately) (I) 450 mm x 350 mm	5	1103.00	each	5515.00
54	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete,C.I. brackets including two coats of painting to bracket etc. PWD S&P Schedule, Page Nö.-36 Item No.-2,	8	1181.00	Nos	9448.00


55	Supplying, fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete. i) Polythene Flush Pipe PWD S&P Schedule, Page no 81. Item no. 11(i)	14	181.00	Each	2534.00
56	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. (a) C.P. urinal flush pipe fittings range of one PWD S&P Schedule, S.P.81, Item-12/a	10	525.00	Each	5250.00
57	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., mending good all damages and painting the brackets with two coats of approved paint. (ii) 550 mm X 400 mm size PWD S&P Schedule, P-41, It 2 (ii)	10	2504.00	Each	25040.00
58	Supplying fitting and fixing pedestal of approved make for wash basin (White) PWD S&P Schedule, P-41, It 3	10	1911.00	Each	19110.00
59	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia., (iii) 600 mm long PWD S&P Schedule, Page No.-43 Item No.-9-iii PWD,	10	126.00	Each	1260.00
60	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iv) 1050 mm long each PWD S&P Schedule, Page No.-43 Item No. 10-iv	8	107.00	Each	856.00
61	(f) Hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar). PWD S&P Schedule, Page No.-3 Item No.- 3 f,	8	1611.00	Each	12888.00
62	(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). PWD S&P Schedule, Page No.-6 Item No.-7-a-i	15	689.00	Each	10335.00
63	(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar PWD S&P Schedule, Page No.-6 Item No.-7-b-i	15	629.00	Each	9435.00
64	Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand). PWD S&P Schedule, Page No.-6 Item No.-7-d-i,	8	1046.00	Each	8368.00
65	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand). (P. No. - 45, Item. No. - 19(a)i, Pwd Sanitary Plumbing Schedule 2017)	8	555.00	Each	4440.00

66	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work PVC Pipes, 25 mm Page No.-12 Item No.-19-i(a), PWD,VOL-II, 2017-18	45.000	186.00	Mtr	8370.00
67	(a) (a) For Exposed Work PVC Pipes, 15 mm Page No.-12 Item No.-19-i(a), PWD,VOL-II, 2017-18	20.000	106.00	Mtr	2120.00
68	(b) For Concealed Work PVC Pipes, 15 mm Page No.-12 Item No.-19-i(b), PWD,VOL-II, 2017-18	20.000	164.00	Mtr	3280.00
69	Supplying and fitting fixing of gunmetal wheel valve of approved brand and make tested to 21 Kg per sq. cm. 25 mm dia(E5) PWD S&P Schedule, P-5 It-5.vii).	4	963.00	Each	3852.00
70	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity PWD S&P Schedule, page.37,item no-6 (b)	2	6110.00	Each	12220.00
71	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L. PWD S&P Schedule, page.37,item no-10 (i)(a)	2	97.00	Each	194.00
72	Labour for punching hole in plastic water storage tank upto 50 mm dia. PWD S&P Schedule, (P. No. - 38, Item. No. - 13	4	19.00	Each	76.00
73	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992.(A) (i) Single Socketed 3 Meter Length, (b) 110 mm PWD S&P Schedule, Page No.-68 Item No. 23,(A)(i)(b)	50.000	348.00	Mtr	17400.00
74	(B) Fittings (i) Coupler, (b) 110 mm	16	101.00	Each	1616.00
75	(ii) Plain Tee, (b) 110 mm	20	182.00	Each	3640.00
76	(iii) Door Tee, (b) 110 mm	10	233.00	Each	2330.00
77	ix) Bend 45°, (b) 110 mm	10	106.00	Each	1060.00
78	xi) Door Bend (T.S.), (b) 110 mm	7	176.00	Each	1232.00
79	xvi) Pipe Clip, (b) 110 mm	30	25.00	Each	750.00
80	xvii) W.C. Connector (150 mm long) 125 X 110(W/WC Ring) 75 mm	10	169.00	Each	1690.00
81	xxxii) Plain Floor Trap with Top tile & Strainer 75 mm	14	171.00	Each	2394.00
82	L) Rubber Ring, (b) 110 mm	30	21.00	Each	630.00
83	C)Rubber Lubricant 500 ML	1	223.00	500 ML	223.00
84	D)Solvent Cement 250 ML	1	123.00	250 ML	123.00

85	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in total pipeline including specials. (B) Under ground, (ii) 110 mm dia. PWD S&P Schedule, (P. - 74, Item. No. - 24 (B)	50.000	85.00	Mtr	4250.00 ✓
86	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materials (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete. A) UPVC Pipes: (i) 75 mm. Dia. (P. - 212, Item. No. - 21 (A)(i) , (B),(c),(i) & (B), (d),(i), Pwd volume- i, 2017)	30.000	188.00	Mtr	5640.00 ✓
87	B) UPVC Fittings: c) Bend 87.5 degree (i) 75 mm. Dia.	6.000	95.00	Mtr	570.00 ✓
88	B) UPVC Fittings: d) Shoe (i) 75 mm. Dia.	2.000	78.00	Mtr	156.00 ✓
89	Constructing Inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling, 15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm.thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. i) With Pakur variety (Other than SAIL/TATA/RINL). PWD S&P Schedule, S.P.87,Item No-1/(i), 7th Corrigenda Volume ii	7	7031.00	Each	49217.00 ✓
90	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover(heavy type)of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C(1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials. (ii) For 50 users A) With Pakur variety. (JSW/JSPL/SHYAM/SRMB/ELECTROSTEEL/SSL) PWD S&P Schedule, S.P.88,Item No-3(ii)(A) 7th Corrigenda Volume ii	1	88461.00	Each	88461.00 ✓

91	Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm intermediate cement brick work (1:4) band all round and cement brick work (1:4) upto 0.90 metre from top with 20mm thick cement plastering (1:4) to inside face upto the depth of cement brick work, 15mm thick cement plaster (1:4) on outer face from top of the well upto G.L. and 6 mm thick cement plaster (1:4) on top of the R.C.C. cover slab including filling bottom 1.00 metre of inside of the well with brick metal (50 mm to 63 mm size) including R.C.C. cover slab of 100 mm thick with cement conc (1:1.5:3) with stone chips with necessary reinforcement and shuttering including one 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the cover slab with necessary fittings, making necessary arrangements for pipe connections, excavation of well including shoring, dewatering and removing the excess earth from the premises as per direction complete in all respect with all costs of labour and materials. With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia. (Other than SAIL/TATA/RINL)	1	16381.00	Each	16381.00
92	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long Schedule, p No 82 I No- 22 (a)(ii)	16	554.00	Each	8864.00
93	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm PWD S&P Schedule, P-81, It-15(ii)	6	485.00	Each	2910.00
94	Supplying, fitting and fixing soap holder. (b) Fibre glass Sanitary and plumbing work schedule P-82, It-18(b)	10	71.00	Each	710.00
95	Supplying, fitting and fixing glass shelf with aluminium guard rails. (a) Ordinary type with 5.5 mm sheet glass (i) 450 mm X 125 mm Sanitary and plumbing work schedule P-81, It-16(a)(i)	5	432.00	Each	2160.00
					1567421.62
Add S.G.S.T. @			9%		141067.95
Add C.G.S.T. @			9%		141067.95
Cost Of Civil Work					1849557.51
Add Labour.Welfare.Cess. @			1%		18495.58
Add Contengency @3%					55486.73
Total Amount Including L.W.C. and contengency					1923539.81
Say Rs.					1923540.00

RUPEES NINETEEN LAKH TWENTY THREE THOUSAND FIVE HUNDRED & FORTY ONLY.




Sign. Of S.A.E
Bansberia Municipality
Sub-Assistant Engineer
Bansberia Municipality





Sign. Of A.E
Bansberia Municipality
Assistant Engineer
Bansberia Municipality



Sign. Of Vice-Chairman
Bansberia Municipality
Silpi Chatterjee
Vice-Chairperson
Bansberia Municipality


26/11/25
Junior Engineer (Civil)
Hooghly Division
M.E. Directorate, Deptt. of U.D. & M.
Govt. of West Bengal


5/12/25
Assistant Engineer
Hooghly Division, M.E. Dto.
Deptt. of U.D. & M.A.
Govt. of West Bengal


04/10/26
Executive Engineer
Hooghly Division
M.E. Directorate, Deptt. of U.D & M.A.
Govt. of West Bengal