

## Community Toilet at Chakbazar Vegetable market, of Ward No.- 09 under Bishnupur Municipality

SCHEDULE OF RATES VOLUME -I BUILDING WORKS [With effect from 01.11.2017] & SECTION (A) - PLUMBING WORKS (A)-(II) G.I PIPE WORKS AND FITTINGS [With effect from 01.11.2017] & Latest Corrigendum

SL. NO.	DESCRIPTION OF ITEM	NO.	LENGT H(M)	BREAD TH(M)	HEIGHT(M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)	
PAGE NO.-26, ITEM NO.-10. P.W.D. SCHEDULE-2017 (3rd CORRIGENDA & ADDENDA)										
1	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (iv) ordinary hard black stone chips - 1ST FLOOR									
	Column upto Roof	7	0.250	0.250	3.000	1.310	Cu.M.			
	Roof	1	34.640		0.125	4.330				
	Landing	1	1.500	1.450	0.125	0.270				
	Lintel	3	5.600	0.250	0.100	0.420				
		2	5.380	0.250	0.100	0.260				
	Wall Beam	3	5.600	0.250	0.100	0.420				
		2	5.380	0.250	0.100	0.260				
					7.270	Cu.M.	✓	✓		
PAGE NO.-42, ITEM NO.-36. P.W.D. SCHEDULE-2017										
2	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (f) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge - 1ST FLOOR									
	For Column	28	0.250		3.000	21.000	Sq.M.			
	For Wall beam	6	5.600	0.250		8.400				
		2	5.380		0.250	2.690				
		2	7.100		0.250	3.550				
	For RCC Slab (cover area)	1	34.640			34.640				
	Landing	1	1.500	1.450		2.170				
	For Lintel	6	5.600		0.100	3.360				
		2	5.385		0.100	1.070				
		2	7.100		0.100	1.420				
					78.300	Sq.M.				✓
PAGE NO.-44, SL NO.-40. P.W.D. SCHEDULE-2017 (10TH CORRIGENDA)										
3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. - 1ST FLOOR (i) Tor steel/Mild Steel I. Other than SAIL/TATA/RINL									
	2% of RCC Vol					1.140	M.T.	✓	✓	
						1.140	M.T.	55200.87	62928.99	
PAGE NO.-15, ITEM NO.-8. P.W.D. SCHEDULE-2017										
4	Brick work with 1st class bricks in cement mortar (1:6)									
	(b) In superstructure, 1st Floor	2	5.100	0.250	3.000	7.650	Cu.M.			
		1	4.630	0.250	3.000	3.473				
		1	6.350	0.250	3.000	4.763				
						15.886				
	Deduction									
	For Ventilator	8	0.750	0.250	0.600	0.900				
	For CG	2	1.000	0.250	2.100	1.050				
						deduction (-)				1.950
					13.936	Cu.M.				✓

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREADTH(M)	HEIGHT(M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)
---------------------	-----	------------	------------	-----------	----------	------	----------	-------------

PAGE NO.-16, ITEM NO.-16. P.W.D. SCHEDULE-2017 (3rd CORRIGENDA & ADDENDA)

thick brick work with 1st class bricks in cement mortar (1:4) in

or.

Toilet	1	1.730		3.000	5.190	Sq.M.		
	1	3.300		3.000	9.900			
	1	4.800		3.000	14.400			
	1	1.490		3.000	4.470			
	1	2.580		3.000	7.740			
	3	1.140		3.000	10.260			
	1	1.630		3.000	4.890			
	1	1.020		3.000	3.060			
					59.910			
Deduction								
For Door	5	0.750		1.950	7.310			
For Ventilator	8	0.75		0.60	3.600			
				deduction (-)	10.910			
					49.000	Sq.M.	637.00	31213.00

PAGE NO.-189, ITEM NO.1 P.W.D. SCHEDULE-2017. (3rd CORRIGENDA & ADDENDA)

Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]

15mm thick (1:6)								
For Outside Wall	2	5.600		3.125	35.000	Sq.M.		
	1	5.380		3.125	16.810			
	1	7.100		3.125	22.180			
landing	2	1.450	1.500		4.350			
Deduction for V (1/3rd)	8	0.750		0.600	-1.180			
Deduction for CG (1/3rd)	2	1.200		2.100	-1.660			
					75.500	Sq.M.	139.00	10494.50
20mm thick (1:6)								
Ladis Toilet	1	3.300		3.000	9.900	Sq.M.		
	4	1.490		3.000	17.880			
	2	1.510		3.000	9.060			
	4	1.660		3.000	19.920			
Ladis Urinal	1	2.580		3.000	7.740	Sq.M.		
	2	1.660		3.000	9.960			
	1	2.270		3.000	6.810			
Free Area (Ladis Side)	1	1.590		3.000	4.770	Sq.M.		
	1	3.400		3.000	10.200			
	1	0.980		3.000	2.940			
Gents Urinal	1	3.330		3.000	9.990	Sq.M.		
	1	3.470		3.000	10.410			
	1	2.060		3.000	6.180			
	1	2.780		3.000	8.340			
Gents Toilet	6	1.140		2.400	16.410	Sq.M.		
	3	1.730		3.000	15.570			
	1	1.700		3.000	5.100			
	1	2.770		3.000	8.310			
	1	1.020		3.000	3.060			
	1	1.410		3.000	4.230			
Deduction for V (1/3rd)	-8	0.750		0.600	-3.600			
Deduction for CG (1/3rd)	-2	1.200		2.100	-5.040			
Deduction for D (1/3rd)	-5	0.750		2.100	-7.870			
					170.270	Sq.M.	157.00	26732.39
10mm thick (1:4)								
Ceiling	1	28.970			28.970	Sq.M.		
Cantiliver portion (Landing)	1	1.450	1.500		2.170	Sq.M.		
					31.140	Sq.M.	126.00	3923.64

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREADTH (M)	HEIGHT (M)	QUANTITY	UNIT	RATE (RS)	AMOUNT (RS.)
PAGE NO.-192, ITEM NO.-15. P.W.D. SCHEDULE-2017								
ment punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc.								
Out side Wall	1	23.680		0.300	7.104	Sq.M.		
Landing	1	1.450	1.500		2.170			
Septic Tank inner wall	2	3.600		1.950	14.040			
	2	0.750		1.950	2.925			
Tank Cover Plat	1	4.000	1.150		4.600			
					30.839	Sq.M.	34.00	1048.53

PAGE NO.-107, ITEM NO.-20. P.W.D. SCHEDULE-2017

8 Supplying, fitting and fixing windows and ventilators with or without integrated grills conforming to IS 1038-1975 and manufactured from rolled steel sections conforming to IS 7452-1974 with non-friction projecting type, box type hinges, glazing clips, lugs locking bracket, handle plate etc, including hoisting in position, straightening if required, fixing lugs in cement concrete ( 1:2:4) with stone chips 20 mm down cutting holes and mending good damages to match with existing surface complete in all respect excluding glazing. (b) Openable steel windows as per IS sizes with side hung shutters and horizontal glazing bars. [The extra rate admissible for the openable portion only]

	8	0.750	0.600		3.600	Sq.M.		
					3.600	Sq.M.	2199.00	7916.40

2225.39 8011.40

PAGE NO.-197, ITEM NO.-15 . P.W.D. SCHEDULE-2017

9 Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification. In Ground floor: (iii) Two coats.

					276.910	Sq.M.	49.00	13568.59
--	--	--	--	--	---------	-------	-------	----------

PAGE NO.-200, ITEM NO.-1 . P.W.D. SCHEDULE-2017

10 (a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.

Collapsible gate (M.F. - 1.5)	2	1		2.1	4	Sq.M.	20	191.84
					6.615	Sq.M.	31.00	205.07

PAGE NO.-200, ITEM NO.-2 . P.W.D. SCHEDULE-2017

11 (A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : With super gloss (hi-gloss) - iv) Two coats (with any shade except white)

Collapsible gate (M.F. - 1.5)	2	1		2.1	4	Sq.M.	81.00	510.30
-------------------------------	---	---	--	-----	---	-------	-------	--------

PAGE NO. - 64, ITEM NO. - 35. P.W.D. SCHEDULE-2017.

Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.

(B) Wall  
With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m.  
(a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative

Inner Wall - Ladis toilet	2	1.510		3.000	9.060			
	2	1.660		3.000	9.960			
	4	1.490		3.000	17.880			
Ladis Urinal	2	1.660		3.000	9.960			
	1	2.510		3.000	7.530			
	1	2.270		3.000	6.810			

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREADTH(M)	HEIGHT(M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)
Free Area	1	3.400		3.000	10.200			
	1	3.300		3.000	9.900			
	1	1.590		3.000	4.770			
Gents Toilet	1	3.280		3.000	9.840			
	1	1.700		3.000	5.100			
	3	1.730		3.000	15.570			
	1	1.630		3.000	4.890			
	2	1.020		3.000	6.120			
	1	2.780		3.000	8.340			
	2	1.630		3.000	9.780			
Gents Urinal	6	1.140		3.000	20.520			
	1	3.070		3.000	9.210			
Deducted (D)	-8	0.750		1.950	-11.700			
Deducted (CG)	-4	1.050		2.100	-8.820			
Deducted (ventiliter)	8	0.750		0.600	3.600			
					158.520	sq.mtr	742	

151.32 ✓

112279.44

117622

PAGE NO.-63, ITEM NO.-34. P.W.D. SCHEDULE-2017 (3rd Corrigendum)

13

Supplying, fitting and fixing Marble Slab/tile of 15 to 18 mm thickness in floor, lobby, stair, landing & treads etc. over 20 mm (av.) thck base of Cement mortar (1:2) laid with white cement slurry @ 4.4 kg/Sq.m before placing marble & jointed with white cement slurry @ 2.0 kg/Sq.m with necessary pigments including grinding and Granite polishing as per direction of Engineering -in - Charge in Ground Floor. { White cement and Pigment to be supplied by the Agency} (b) With Chawk Dungri (iii) Area of each tile exceeding 0.6 sq.m but not exceeding 1 Sq.M.

Gents Urinal area	1	9.920		9.920				
Gents Toilet	1	4.310		4.310				
Ladis Urinal	1	3.990		3.990				
Ladis Toilet	1	4.690		4.690				
Ladis Free Area	1	4.345		4.345				
					27.255	Sq.M.	2704.00	73696.71

PAGE NO.-117, ITEM NO.-8 . P.W.D. SCHEDULE-2017

14

Supplying fitting and fixing in position approved P.V.C. door frame (Matt finish) made of extruded P.V.C. multichamber hollow section having dimensions 60mm x 50mm x 2mm (+/-0.2mm), horizontal section will be joined with vertical section by galvanised steel screws after inserting two number steel brackets as reinforcement making suitable space for placing hinges, one steel tube 40mm x 20mm x 1.20 mm will be inserted on one full vertical side of the frame (hinge side) as reinforcement, the frame will then be fixed in the opening with the help of P.V.C. expandable fastner/wooden gutties and galvanised steel screws including cost of all materials and labour, hire charges of tools and appliances, carriage of all materials, taxes and all other incidental charges complete.

	5	1.463			7.313	Mtr	279	2040.19
--	---	-------	--	--	-------	-----	-----	---------

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREAD TH(M)	HEIGHT (M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)	
PAGE NO.-131, ITEM NO.-22, P.W.D. SCHEDULE-2017									
15	nick factory made Solid panel PVC Door shutter made out of single piece extruded solid profiles, 5 mm (± 0.2mm) thick, having styles & rails (except lock rail) of size 95 mm x 35 mm x 5 mm, out of which 75 mm shall be flat and 20 mm shall be tapered (on both side), having one side thickness of 15 mm integrally extruded on the hinge side of the profile for better screw holding power, including reinforcing with MS tube of size 40 mm X 20 mm x 1 mm, joints of styles & rails to be mitred cut & joint with the help of PVC solvent cement, self driven self tapping screws & M.S. rectangular pipes bracket of size 190 mm X 100 mm of cross section size 35 mm x 17 mm x 1 mm at each corner. Single piece extruded 5mm thick solid PVC Lock rail of size 115 mm x 35 mm x 35 mm, out of which 95 mm to be flat and 20 mm to be tapered at both ends, having 15 mm solid core in middle of rail section integrally extruded, fixing the styles & rails with the help of solvent and self driven self tapping screws of 125 mm x 8 mm, including providing 5 mm Single piece solid PVC extruded sheet inserted in the door as panel, all complete as per manufacturer's specification and direction of Engineer-in-charge.								
		5	0.750	1.950	7.313	Sq.M.	2872	21001.50	
PAGE NO.-104, ITEM NO.-13, P.W.D. SCHEDULE-2017									
16	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor .(i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr.								
		8	0.750	0.600	3.600	sq.mtr	✓	✓	
					0.360	Quntl	9986.88	3595.28	
PAGE NO.-206, ITEM NO.-07, P.W.D. SCHEDULE-2017									
17	Supplying, fitting and fixing in position fibre glass panes of approved quality with resin, nail, clip etc. as per IS:12866-1989. (In all floors for internal wall & upto 6 m height for external wall)(e) 4.0 mm thick (6.72 Kg/Sq.m). In Ground floor WINDOW						1710.00	6188.90	
		8	0.750	0.600	3.600	Sq.mtr.	1786.00	6429.60	
PAGE NO.-12, ITEM NO.-19(i), P.W.D. SCHEDULE (S&P)-2017									
18	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I), with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will be made seperately) (a) For Exposed Work PVC Pipes						✓	✓	
	15mm dia				13.000	mtr	101.00	1313.00	
	20mm dia				7.000	mtr	129.00	903.00	
	25mm dia				3.000	mtr	177.00	531.00	
	32mm dia				2.000	mtr	236.00	472.00	
PAGE NO.-6, ITEM NO.-7, P.W.D. SCHEDULE-2017									
19	Supplying, fitting and fixing bib cock or stop cock (d) ii) Chromium plated concealed Stop Cock heavy duty (Equivalent to Code No. 5083 & Model - Florentine of Jaquar or similar brand).						✓	✓	
					8.000	Nos.	953.00	7624.00	
PAGE NO.-79, ITEM NO.-4 P.W.D. SCHEDULE-(S&P)-2017									
20	Supplying, fitting and fixing Orissa pattern water closet in white glazed vitreous chinaware of approved make in position complete excluding 'P' or 'S' trap (excluding cost of concrete for fixing). (i) 580 mm X 440 mm						✓	✓	
					4.000	Nos	1613.00	6452.00	

	DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREAD TH(M)	HEIGHT (M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)
PAGE NO.-36, ITEM NO.-2 P.W.D. SCHEDULE-2017 ( Sanitary Works)									
	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with C.I. fittings complete, C.I. brackets including two coats of painting to bracket etc							✓	✓
		4	1			4.000	nos	1015	4060.00
PAGE NO.-80, ITEM NO.-7 P.W.D. SCHEDULE-(S&P)-2017									
22	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately). - (i) 450 mm X 350 mm					4.000	Nos	✓	✓
						4.000	Nos	881.00	3524.00
PAGE NO.-106, ITEM NO.-18. P.W.D. SCHEDULE-2017.									
23	Collapsible gate with 40mm x 40mm x 6mm Tee as top and bottom guide rail, 20mm x 10mm x 2mm vertical channels 100mm apart in fully stretched position 20mm x 5mm M.S. flats as collapsible bracings properly rivetted and washered including 38mm steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc. in walls, floors etc. and making good damages complete. (In ground floor.)							4373.30	18367.80
	COLLAPSIBLE GATES	2	1.000		2.100	4.200	Sq.M.		
						4.200	Sq.M.	4330.00	18186.00
PAGE NO.-6-7, ITEM NO.-7. P.W.D. SCHEDULE-(S&P)-2017									
25	(g) Supplying, fitting and fixing alloy iron with brass spindle bib cock/ stop cock of approved brand and make, spray painted and tested to 21 kg per sq. cm.							✓	✓
	(i) 15 mm					14.000	Nos	169.00	2366.00
PAGE NO.-43, ITEM NO.-9. P.W.D. SCHEDULE-(S&P)-2017									
26	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia.							✓	✓
	450mm long					4.000	Nos	82.00	328.00
PAGE NO.-43, ITEM NO.-10. P.W.D. SCHEDULE-(S&P)-2017									
27	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps							✓	✓
	iii) 900 mm long					7.000	Nos	75.00	525.00
PAGE NO.-70, ITEM NO.-23 P.W.D. SCHEDULE-(S&P)-2017									
28	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992 Plain Y 110mm dia							✓	✓
						2.000	Nos	206.00	412.00
PAGE NO.-71, ITEM NO.-23 (b) P.W.D. SCHEDULE-(S&P)-2017									
29	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992 xv) Vent Cowl (b) 110 mm							✓	✓
						1.000	Nos	33.00	33.00
PAGE NO.-72, ITEM NO.-23 (B) P.W.D. SCHEDULE-(S&P)-2017									
30	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992 xxi) 110 X 110 P Trap 75 mm							✓	✓
						2.000	Nos	281.00	562.00
PAGE NO.-68-69, ITEM NO.-23 (B) P.W.D. SCHEDULE-(S&P)-2017									
31	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992 (A) (i) Single Socketed 3 Meter Length b) 110 mm							✓	✓
						4.000	Nos	292.00	1168.00
PAGE NO.-37, ITEM NO.-6 P.W.D. SCHEDULE-2017 ( Sanitary Works)									
32	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (d) 1000 litre capacity							✓	✓
		1				1.000	nos	5128.00	5128.00
PAGE NO.-37, ITEM NO.-10 P.W.D. SCHEDULE-2017 ( Sanitary Works)									
33	Labour for hoisting plastic water storage tank.							✓	✓
		1	1.000			1.000	nos	96.00	96.00
PAGE NO.-38, ITEM NO.-13, P.W.D. SCHEDULE-2017 ( Sanitary Works)									
34	Labour for punching hole in plastic water storage tank upto 50 mm dia.							✓	✓
		3	1.000			3.000	nos	19.00	57.00

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREADTH(M)	HEIGHT(M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)
PAGE NO.-5, ITEM NO.-5 P.W.D. SCHEDULE-2017 ( Sanitary Works)								
Supplying, fitting and fixing gunmetal wheel valve of approved brand and tested to 21 kg per sq. cm. (for water lines only)					2.000	nos	778.00	1556.00
PAGE NO.-88, ITEM NO.-3 P.W.D. SCHEDULE-2017 ( Sanitary Works)								
Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover(heavy type)of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C(1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials. Note:- (i) Finished level of Septic Tank should be 400 mm. from Ground Level. (ii) Height of 50 mm. Ventilation pipe & Mosquito proof mesh, should be followed as per IS:2470,Part- I.Payment will be made separately on the basis of actual height based on relevant I.S.Code.								
(iii) For 20 users - A) with pakur variety JSW/JSPL/SHYAM/SRMB/BAMSL/ELECTROSTEEL/SSL					1	EACH	44120.00	44120.00
PAGE NO.-87, ITEM NO.-01, P.W.D. SCHEDULE-2017 ( Sanitary Works) (7th Corrigendum,01/11/2019)								
38 Constructing Inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling, 15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm.thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. i) with pakur variety JSW/JSPL/SHYAM/SRMB/BAMSL/ELECTROSTEEL/SSL					2.000	each	6481.00	12962.00
PAGE NO.-81, ITEM NO.-17, P.W.D. SCHEDULE-2017 ( Sanitary Works)								
39 Supplying, fitting and fixing liquid soap container.(a) Cromium plated.					7.000	nos	393.00	2751.00
PAGE NO.-81, ITEM NO.-18, P.W.D. SCHEDULE-2017 ( Sanitary Works)								
40 Supplying, fitting and fixing soap holder. (a) PTMT (Prayag or equivalent)					7.000	nos	135.00	945.00
PAGE NO.-82, ITEM NO.-19, P.W.D. SCHEDULE-2017 ( Sanitary Works)								
41 Supplying, fitting and fixing best quality Indian make mirror 5.5 mm thick with silvering as per I.S.I. specifications supported on fibre glass frame of any colour, frame size 550 mm X 400 mm					4.000	nos	613.00	2452.00

DESCRIPTION OF ITEM	NO.	LENGTH (M)	BREADTH (M)	HEIGHT (M)	QUANTITY	UNIT	RATE(RS)	AMOUNT(RS.)
PAGE NO.-82, ITEM NO.-22, P.W.D. SCHEDULE-2017 ( Sanitary Works)								
ng, fitting and fixing towel rail with two brackets. (a) C.P. over brass, (ii) 25 mm dia. and mm long								
	6	1.000			6.000	nos	430.00	2580.00
628918.97					TOTAL		(A)	636,525.24
113205.41					Add 18% GST Of A (B)			114,574.54
742124.38					TOTAL (A+B) (C)			751,099.78
7421.24					Add 1% Cess of C (D)			7,511.00
					TOTAL Rs. (C+D)			758,610.78
22263.72					Add 3% Contingency			22,532.99
771809.34					Total Rs.			781,143.77
771809.00					Say Rs.			781,144.00

*[Signature]*  
26/06/2023

S.A.E  
BISHNUPUR MUNICIPALITY  
**SAE**  
Bishnupur Municipality

*[Signature]*  
**Chairman**  
CHAIRPERSON  
Bishnupur Municipality  
BOARD OF MEMBERS  
BISHNUPUR MUNICIPALITY

VETTED

*[Signature]*  
02/06/23  
Junior Engineer (Civil)  
Bankura Divn. (Works)  
M.E. Directorate  
Govt. of West Bengal

*[Signature]*  
02/06/23  
Assistant Engineer  
Bankura Divn. (Works)  
M.E. Directorate  
Govt. of West Bengal

*[Signature]*  
02/06/23  
Executive Engineer  
Bankura Divn. (Works)  
M.E. Directorate  
Govt. of West Bengal