

SL NO.	SCHEDULE	ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
25	Sanitary & Plumb.2017 Page-66, Item No. 16	Supplying, fitting and fixing with cement jointing (3:1) salt glazed stoneware pipe including excavation of earth upto 1.50 metre depth in all sorts of soil both mixed or unmixed and refilling (but excluding concreting at bottom and sides).(iii) 150 mm	20	MTR	334.00	6680.00
26	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-18,l-46	Cement concrete (1:1.5:3) with graded stone chips 5.6mm. Size with hexagonal square mesh wire netting I.R.C. Fabric mesh or X P.M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scraping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement excluding the cost of wire netting I.R.C. or X P.M. but including cost of all handling and scaffolding complete as per direction of Engineer-in-charge. (a) 37.5mm thick.	33.25	SQM	593.00	19717.25
27	PWD.BLDG SCHEDULE_WEF 01.11.2017 10-1(B).2(a)	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m In ground floor including roof. (a) upto 150 mm. thick	9.14	M3	939.00	8582.46
28	PWD.BLDG SCHEDULE_WEF 01.11.2017 10-1(B).1(a)	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. (a) In ground floor including roof.	6.42	M3	447.00	2869.74
29	PWD.BLDG SCHEDULE_WEF 01.11.2017 10-1(B).3(a)	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish as directed within a lead of 75 m. including stacking of steel bars. (a) In ground floor including roof	3.02	M3	1956.00	5907.12
30	P.W.D. (Bldg) 2017 Page 47, Item No. 3	Supplying and laying polythene sheet (150gm/sqm.) over damp proof course or below flooring or roof terracing or in foundation trenches.	255.13	SQM	24.00	6123.12
31	PWD.BLDG SCHEDULE_WEF 01.11.2017 107-19B	Supplying fitting and fixing steel rolling grills link type, shutter with 18 B.G .of approved type steel to the section 75mm wide, fitted with coil wire spring to necciate the fitting of required Nos. of C.I. Pulleys on heavy type solid drawn seamless steel tube complete with locking arrangements both inside and outside specially builtup side guide channels including providing a hood for the steel rolling shutter in the room, painting two coats of approved aluminium paint over a coat of red lead primer complete.	6.3	SQM	2833.00	17847.90
32	P.W.D. (Bldg) 2017 Page 104, Item No. 13	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S. W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. (ii) Grill weighing above 16 Kg./sq.mtr and above	4.92	QTL	7,046.00	34666.32
33	PWD.BLDG SCHEDULE_WEF 01.11.2017 192-1.I.B.1	Labour for Chipping of concrete surface before taking up Plastering work.	90.5	SQM	21.00	1900.50
34	P.W.D. (S&P) 2017 ,7th corr. 22.01.2020,p-1,l-1	Constructing Inspection pit to a depth of 1.5 metre (inside), 250 mm thick 1st class brick work (1:4) in all sides over a layer of jhama brick soling and 150 mm thick cement concrete with stone chips (1:3:6) including necessary earth work, fitting and fixing approved type S.W. master trap, constructing masonry invert with cement concrete (1:1.5:3) with stone chips, plastering inside and outside (outside upto 300 mm below G.L.) with 20 mm thick cement plastering (1:4) and neat cement punning, including supplying,fitting and fixing one 560 mm. dia R.C.C. manhole cover of approved make with R.C.C. slab of 100 mm thick with cement concrete (1:1.5:3) with stone chips including necessary reinforcement (upto 1%) and shuttering and necessary corbelling brick work (1:4) so that the R.C.C. cover slab rests 150 mm above adjucent G.L., cement plaster (1:4) 10 mm thick on all external surfaces of the top slab as directed complete in all respect and removal of surplus earth with all costs of labour and materials (excluding the cost of master trap only).(i) 900 mm X 750 mm (inside) chamber including fitting and fixing S.W. master trap of 150 mm dia. of approved make A) With Pakur variety. (SAIL/TATA/RINL)	1	EA	11,959.00	11959.00
35	PWD.SANITARY AND PLUMBING 2017 93-B.B.IV.9.a(ii)	Supplying, fitting and fixing in position C.I. manhole/ pit cover with rim.(a) Round (ii) 450 mm X 100 mm X 25 kg (approx.)	1	EA	2,035.00	2035.00
36	P.W.D. (Bldg) 2017 Page-200/ ltm.1(a)	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	22.35	SQM	29.00	648.15

SATEG
 13/11/20
 Anshu
 17/11/20
 10/11/20

SL NO.	SCHEDULE	ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
37	P.W.D. (Bldg) 2017 Page-201/ Itm.2(b), (iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand paping etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	22.35	SQM	79.00	1765.65
38	PWD.SANITARY AND PLUMBING 2017 29-(A) (A)-(III) (a) 1(a)(i)	Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories,specials viz.(a) For Exposed Work (i) CPVC Pipes Class-1, SDR-11 (Dia) 25 MM	25	MTR	208.00	5200.00
39	PWD.SANITARY AND PLUMBING 2017 29-(A) (A)-(III) (a) 1(a)(i)	Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories,specials viz (b) For Concealed Work (i) CPVC Pipes Class-1,SDR-11(Dia) (a)15mm	45.6	MTR	140.00	6384.00
40	PWD.SANITARY AND PLUMBING 2017 29-(A) (A)-(III) (a) 1(a)(ii)	Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778: 2007 . with all necessary accessories,specials viz (b) For Concealed Work (i) CPVC Pipes Class-1,SDR-11(Dia) (a)20mm	57.00	MTR	171.00	9747.00
41	PWD.SANITARY AND PLUMBING 2017 3-A.(A)-(II) 3.(a) (i)	Supplying, fitting and fixing shower of approved brand and make. (a) (i) Chromium plated round shower with revolving joint 100 mm dia with rubid cleaning system (Equivalent to Code No. 542(N) & Model - Tropical / Sumthing Special of ESSCO or similar brand).	3	EA	452.00	1356.00
42	PWD.SANITARY AND PLUMBING 2017 5-A.(A)-(II) 5.(vii)	Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only). (vii) 25 mm dia	2	EA	778.00	1556.00
43	PWD.SANITARY AND PLUMBING 2017 6-A.(A)-(II) 7.(b) (i)	Supplying, fitting and fixing bib cock or stop cock. (b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	8	EA	493.00	3944.00
44	PWD.SANITARY AND PLUMBING 2017 36-(A) (A)-(IV)-2	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete,C.I. brackets including two coats of painting to bracket etc.	3	EA	1015.00	3045.00
45	PWD S&P-2017, Page:-37 It.No.-:6(b)	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (d) 1000 litre capacity.	1	EA	5,128.00	5128.00
46	P.W.D. (S&P) 2017 P:-37 It.:-:10(A) .	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity.(a) Upto 1st story from G.L	1	EA	96.00	96.00
47	PWD.SANITARY AND PLUMBING 2017 38-A-A-IV-13	original works 13 Labour for punching hole in plastic water storage tank upto 50 mm dia.	2	EA	19.00	38.00
48	PWD.SANITARY AND PLUMBING 2017 41-A-A-V-41)1)a)iii	Original Works 1 Wash basin vitreous china of approved make (without fittings) supplied,fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (iii) 630 mm X 450 mm size	4	EA	2,435.00	9740.00
49	PWD.SANITARY AND PLUMBING 2017 80- 7	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately).(i) 450 mm X 350 mm	1	EA	881.00	881.00
50	PWD.BLDG SCHEDULE_WEF 01.11.2017 63-1(D).A 34 (a)	Supplying,fitting & fixing granite slab 15mm to 18mm thick in floor, lobby, stair, landing and treads etc. over 20mm (avg) thick base of cement mortar (1:2) laid with white cement slurry @ 4.40Kg per Square meter before placing of granite and jointed with white cement slurry @ 2.0 Kg per square meter with necessary pigments and complete as per direction of Engineer-in-charge including cost of all materials, labours, curing and roughening of concrete surface complete. In ground floor (a) Area of each Granite slab upto 0.60 Square meter.	30.24	SQM	2,173.00	65711.52
51	PWD.SANITARY AND PLUMBING 2017 82-B-B(III)-(a).19	Supplying, fitting and fixing best quality Indian make mirror 5.5 mm thick with silvering as per I.S.I. specifications supported on fibre glass frame of any colour, frame size 550 mm X 400 mm	6	EA	613.00	3678.00
52	PWD.SANITARY AND PLUMBING 2017 82-B-B(III)-(a).18.(a)	Supplying, fitting and fixing soap holder.(a) PTMT (Prayag or equivalent)	12	EA	135.00	1620.00

Handwritten signature and date: 18/12/17

Handwritten signature and date: 17/12/17

SL NO.	SCHEDULE	ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
53	PWD.SANITARY AND PLUMBING 2017 P-4, It (f)	Supplying, fitting and fixing shower of approved brand and make (f) Hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	3	EACH	1251.00	3753.00
54	PWD.SANITARY AND PLUMBING 2017 82-B-B(III)-(a).22.(a)(ii)	Supplying, fitting and fixing towel rail with two brackets.(a) C.P. over brass.(ii) 25 mm dia. and 600 mm long	9	EA	430.00	3870.00
55	PWD.BLDG SCHEDULE_WEF 01.11.2017 63-1(D).A 34 (a)	Supplying and laying true to line and level Anti-Skid, Full Body, Homogeneous & Granular finish Vitrified Tiles conforming to IS:15622-2006 & IS 4457-2007 and testing shall be made in accordance with IS:13630 [Non- modular sizes for tiles with Skid resistance > 0.5, Mohr's hardness > 5.0, Staining resistance: Class-1, Water Absorption: E < 0.5%], MOR > 35 N/sq.mm in Internal area of building e.g. Toilet Block, Passage, Corridor, Accessible Open Terrace etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg./Sq.m or using Polymerised Adhesive (6 mm thick layer applied directly over finished artificial stone floor/ Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per Sqm below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles/ epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor).a) In Ground Floor: Sizes-300 mm x300mm x10 mm with breaking strength > 1200 N	35.4	SQM	897.00	31753.80
56	PWD.BLDG_SCHD_2 017_3rd CORRI_4.6.2018,P26-1(D).A.(20)	Supplying, fitting and fixing 18 mm. to 22 mm. thick kota stone slab in wall, dado in 15 mm thick [avg] cement mortar (1:3) including making suitable arrangement to hold the stone properly by brass / copper hooks including pointing in cement mortar	12.18	SQM	1,160.00	14128.80
57	PWD.SANITARY AND PLUMBING 2017 19-A.(A)-(ii) 20. A. (d)	. Supply of High Density Poly-ethylene Pipe conforming to IS - 4984 - 1985 (Dia) [PE - 63] A. 6 Kg / Sq.Cm. (Working Pressure) (Dia) (d) 75 mm	24	MTR	248.00	5952.00
58	PWD.BLDG SCHEDULE_WEF 01.11.2017 196-1.J.A.8(a)	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC	2.36	%SQ	3,140.00	7410.40
59	PWD.BLDG SCHEDULE_WEF 01.11.2017 197-1.J.A.17(ii)	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) a) Normal Acrylic Emulsion	235.84	SQM	67.00	15801.28
60	PWD.BLDG SCHEDULE_WEF 01.11.2017 115-1(G) A. 3 (i)	. Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria (i) 66mm x 90mm	29.7	MTR	497.00	14760.90
61	PWD.BLDG SCHEDULE_WEF 01.11.2017 125-1(G) B. 14 (i)	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor (i) 32 mm thick	9.45	SQM	2,763.00	26110.35
62	P.W.D. (Bldg) 2017 Page 145, Item No. 29	Anodised aluminium butt hinges of approved quality manufactured from extruded section conforming to IS specification (I.S. 205/66) and fitted and fixed with cadmium plated screws: 75 x 45 x 2.5mm	18		52.00	936.00
63	P.W.D. (Bldg) 2017 Page 144, Item No. 26	Anodised aluminium barrel/tower/socket bolt(full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws: 100mm long x 10mm dia bolt.	12		53.00	636.00
64	P.W.D. (Bldg) 2017 Page 146 It.no- 33, a (i)	Anodised aluminium grip handle with base plate of approved quality fitted and fixed complete. (a) With base plate. (i) 165mm grip x 12mm dia rod x 42mm plate x 3.2mm thick.	12		147.00	1764.00

D
 SPECS
 10/1/2018
 17/1/18
 A/E/10/18



SL NO.	SCHEDULE	ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
65	PWD.BLDG SCHEDULE_WEF 01.11.2017 109-1(F) A. 22	Supplying, fitting and fixing Stainless Steel railing consist of 38mm dia and 900mm height vertical balustrade at every two alternative steps, 50mm dia top rail, 3 (three) nos 19mm dia horizontal Strainless steel pipe and base/cover plate with Strainless Steel GRADE 304	5.70	MTR	5,974.00	34051.80
66	PWD.SANITARY AND PLUMBING 2017 81-B-B(III)- (a).12.(b)	Supplying, fitting and fixing urinal flush pipe fittings of approved brand.(b) C.P. urinal flush pipe fittings range of two	2	EACH	917.00	1834.00
67	PWD.BLDG SCHEDULE_WEF 01.11.2017 198- 1.J.B.5(a)	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick)	383.76	SQM	122.00	46818.72
68	PWD.SANITARY AND PLUMBING 2017 45-19-A (i)	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	4	EACH	555.00	2220.00
69	PWD.SANITARY AND PLUMBING 2017 6 - 7 b (i)	Supplying, fitting and fixing bib cock or stop cock (b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	12	EACH	493.00	5916.00
70	PWD.SANITARY AND PLUMBING 2017-7-8 a (i) - 7 b (i)	Supplying, fitting and fixing push cock of heavy quality and of approved make and brand. (a) Cast iron (i) 15 mm	2	EACH	201.00	402.00
71	PWD.BLDG SCHEDULE_WEF 01.11.2017 62-31	Supplying, fitting & fixing granite tiles 10mm to 12mm. thick in columns, wall, facia etc. with 15 thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging ,curing and roughening of concrete surface complete.	26.4	SQM	1,755.00	46332.00
72	PWD.BLDG SCHEDULE_W EF 01.11.2017 234-1 (R .1.(A)(I)(K)(i)	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).	14.1	MTR	311.00	4385.10
		b) 3- track sliding window i) Bottom frame				
73	PWD.BLDG SCHEDULE_W EF 01.11.2017 235-1(R .1.(A)(I)(K)(ii)a	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).b) 3- track sliding window ii) Top and side frame	40.50	MTR	270.00	10935.00
74	PWD.BLDG SCHEDULE_W EF 01.11.2017 235-1(R .1.(A)(I)(K)(ii)b	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).				
		Shutter for all track sliding window. i) Bottom & Top member.				
75	PWD.BLDG SCHEDULE_W EF 01.11.2017 235-1(R .1.(A)(I)(K)(ii)c	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).Shutter for all track sliding window. iii) Interlock member.	30.00	MTR	117.00	3510.00
76	PWD.BLDG SCHEDULE_W EF 01.11.2017 235-1(R .1.(A)(I)(K)(ii)d	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).h) Louvered window. i) Top, bottom and side member.	40.8	MTR	148.00	6038.40
			38.40	MTR	183.00	7027.20

Handwritten signature and date: 26/12/17

Handwritten signature and date: 27/12/17

SI NO.

SL NO.	SCHEDULE	ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
77	PWD.BLDG SCHEDULE_W EF 01.11.2017 250-1(R)27(b)	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285-1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - InCharge. (Payment will be made on finished length of the work).h) Louvered window. ii) Louvered Section.	19.20	SQ M	658.00	12633.60
78	PWD.BLDG SCHEDULE_W EF 01.11.2017 243-1(R)9.(iv)	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. iv) 5mm thick coloured / tinted / smoke glass.	16.29	SQ M	585.00	9529.65
79	PWD.BLDG SCHEDULE_W EF 01.11.2017 233-A 1 h ii))	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285-1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI iii) Cleat angle (Non-anodized).	19.2	MTR	263.00	5049.60
80	P.W.D. (Bldg) 2017 Page 297, Item No.26(b)	Providing and fixing of factory made uPVC casement window (White Colour) (U value=1.9-1.3 W/m 2 K, flame resistant, self extinguishing, lead free) comprising uPVC multi-chambered frame, Sash, & Mullion with having wall thickness of 2.3 mm (±0.2 mm) duly reinforced with G.I. section 1.6 mm (±0.2 mm) made from roll forming process of required length. All corners of frame and sash will be fusion welded. mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's, uPVC extruded glazing beads of appropriate dimension, EPDM gasket, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. shall be provided in all frame, sash & mullion, wherever necessary. Thereafter, 5 mm clear annealed glass shall be provided in the sash with the help of uPVC glazing bead and hardware, i.e., stainless steel (SS 304 grade) friction hinges & zinc alloy (white powder coated) casement handles (in window) & 3D Hinges & Multipoint Lock (in door) shall be provided. Window frame shall be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of	5.46	Sqm	8657.00	47267.22
81	P.W.D. (Bldg) 2017 Page 291, Item No.18	Supplying, fitting & fixing Stainless Steel 'D' or 'H' type of size 300 mm x 19 mm tubular Handle with Grade 304, CE certified, marked & conforming to EN - 1154, of approved quality of reputed brand as per direction of Engineer-inCharge fitted and fixed complete including all incidental charges.	4	Each	1571.00	6284.00
82	P.W.D. (S&P) 2017 Page: 80 It.No.: 6(i)	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass crewson /5mm X /5 mm X /5 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm.	6	Each	2869.00	17214.00
83	K.M.C. FAIR RATE approved by D.G.(Bustee), dt- 20.10.14	Decorative relief work of artistic nature on exposed surface of cement concrete, plaster or brick work etc. on the surface sketch drawn by artist including preparing the base by rough plaster of sand, cement (1:3) with water proofing compound including oil paint (Two Coats of approved shade, colour over a coat of primer) and applying two coats of decorative cement based paint to the rest portion of the back and other miscellaneous work complete including all materials, labours, scaffolding etc. as per direction of Engineer-in-Charge.	70	Sqm	3281.14	229679.80
84	P.W.D. (Bldg) 2017 Page -250,Item No. 27	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al./MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) (b) 4mm thick (0.50mm Al.+3.0mm LDPE +0.50mm Al. PVDF coating)	8.88	Sqm	2878.00	25556.64
85	PWD(W.B)2017- Building Works- P-67 It- 38(iii)	Supplying, fitting & fixing Glass mosaic tiles at finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design, fixing in customize design as per direction of Engineer-in Charge. The glass mosaic tiles to be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. The rate is inclusive of all operation, material and required pattern approved by Engineer in Charge. (At Ground Floor. iii) Mural aligned/ CAD Design Type	5.76	Sqm	3614.00	20816.64

 Executive Engineer (Civil)
 Uttaran Services Department
 K. M. C.

Dy. Chief Engineer (Civil)
 Uttaran Services Department
 K. M. C.

D. G.
 Uttaran Services Department
 K. M. C.

