



File No. KMC-27/71/2025-UTTARAN SEC(KMC)-KMC (Computer No. 1211494)  
 Generated from eOffice by TAMAL KRISHNA KHANRA, ASSTT. ENGR-C(TKK)(UTTARAN)(KMC), ASSTT. ENGR-C(UTTARAN)(KMC), KOLKATA MUNICIPAL CORPORATION on 31/01/2026 01:4

*Sd/-*  
 (S.A.P.C.)  
 21/01/26

*Obin*  
 31/01/26

*Sd/-*  
 31/01/26  
 Dy. Chief Engineer (Civil)  
 Uttaran Services Department  
 K. M. C.

*Sd/-*  
 31/01/26  
 Uttaran Services Department  
 K. M. C.

**NAME OF WORK:- CONSTRUCTION OF PAY AND USE TOILETS ALONGWITH LANDSCAPING WORK INFRONT OF INDIAN MUSIUM UNDER PARK STREET FLYOVER,  
KOLKATA IN WARD NO 63, BOROUGH-VII**

**CIVIL WORK**

**DETAILED OF ESTIMATE**

Estimate No-KMC/US/...../ Of 202 -2

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
1	P.W.D. (Bldg) 2017 Page 1, Item No. 1	Earthwork in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sand stone) including removing, spreading or stacking the spoils within a lead of 75m as directed. The item includes necessary trimming the sides of trenches levelling dressing and ramming the bottom bailing out water as required complete. Depth of excavation not exceeding 1500 mm							
		Footing	16	1.200	1.200	1.200	27.65		
		Below Tie Beam	7	4.350	0.375	0.250	2.85		
			3	3.500	0.375	0.250	0.98		
			2	3.775	0.375	0.250	0.71		
			3	3.776	0.375	0.250	1.06		
			3	3.250	0.375	0.250	0.91		
			2	2.325	0.375	0.250	0.44		
			2	1.460	0.375	0.250	0.27		
		Under Ground Reservoir	1	2.50	1.50	1.20	4.50		
			1	10.00	0.375	0.30	1.13		
		<b>Total</b>					<b>40.50</b>	<b>% Cum</b>	<b>11927.00</b>
		2	P.W.D. (Bldg) 2017 Page 1, Item No. 3(a)	Earthwork in filling in foundation trenches or plinth with good earth in layers not exceeding 150mm. Including watering andramming etc. layer by layer complete (Payment to be made on the basis of measurement of finished quantity of work). With earth obtained from excavation of foundation					
1/5 th of Excavated Earth						<b>8.10</b>	<b>%Cum</b>	<b>7754.00</b>	
3	P.W.D. (Bldg) 2017,5th Corr.16.04.2019 Page 2, Item 1	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm. As directed and consolidating same by thorough saturation with water ramming complete including the cost of supply of sand. (Payment to be made on measurement of finished quantity)							
			16	1.20	1.20	0.100	2.30		
			7	4.350	0.375	0.100	1.14		
			3	3.500	0.375	0.100	0.39		
			2	3.775	0.375	0.100	0.28		
			3	3.776	0.375	0.250	1.06		
			3	3.250	0.375	0.250	0.91		
			2	2.325	0.375	0.250	0.44		
			2	1.460	0.375	0.250	0.27		
			1	2.50	1.50	1.20	4.50		
			1	10.00	0.375	0.30	1.13		
							<b>12.42</b>	<b>%Cum</b>	<b>131714.00</b>

*S. Saha*  
31/01/26

*B. Biswas*  
31/01/26

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate		
4	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-1	Single brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with powdered earth or local sand.									
			16	1.200	1.200			23.04			
				7	4.350	1.200			36.54		
				3	3.776	0.375			4.25		
				3	3.250	0.375			3.66		
				2	2.325	0.375			1.74		
				2	1.460	0.375			1.10		
				1	2.50	1.50			3.75		
				3	3.850	3.526			40.73		
				1	3.000	3.526			10.58		
				2	1.348	2.075			5.59		
				1	2.371	2.075			4.92		
				1	3.000	3.850			11.55		
				1	3.775	0.375			1.42		
				1	3.775	1.000			3.78		
				2	0.375	0.375			0.28		
				1	9.250	0.375			3.47		
									<b>156.40</b>	<b>Sqm</b>	<b>361.00</b>
		5	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-10	Cement concrete with graded jharma khoa (30 mm. size) excluding shuttering in ground floor and foundation. a) 1:3:6 Proportion							
				outside	16	1.20	1.20	0.100		2.30	
	1			2.50	1.50	0.075		0.28			
	3			3.850	3.526	0.075		3.05			
	1			3.000	3.526	0.075		0.79			
	2			1.348	2.075	0.075		0.42			
	1			2.371	2.075	0.075		0.37			
	1			3.000	3.850	0.075		0.87			
	1			3.775	0.375	0.075		0.11			
	1			3.775	1.000	0.075		0.28			
	2			0.375	0.375	0.075		0.02			
	1			9.250	0.375	0.075		0.26			
								<b>8.75</b>	<b>Cum</b>	<b>4761.00</b>	
6	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-10			Cement concrete with graded jharma khoa (30 mm. size) excluding shuttering in ground floor and foundation. a) 1:4:8 Proportion							
			5	0.60	0.40	0.30		0.36			
			1	15.00	0.157			2.36			
							<b>2.72</b>	<b>Cum</b>	<b>4566.00</b>		

4  
S.M.R.  
21/01/26

S.M.R.  
21/01/26

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
7		Hire and Labour charges for shuttering with centering and necessary staging upto 4m using approved stout, props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns lintels, curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor).							
		25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-charge							
		Footing	16	4.80	0.175		13.44		
			16	2.00	0.500		16.00		
		Column	16	1.10	4.075		71.72		
			1	6.28	0.13	3.00	0.79		
		Tie Beam	7	4.350	0.60		18.27		
			3	3.500	0.60		6.30		
			2	3.775	0.60		4.53		
			3	3.776	0.60		6.80		
			3	3.250	0.60		5.85		
			2	2.325	0.60		2.79		
			2	1.460	0.60		1.75		
		Roof Beam	7	4.350	0.85		25.88		
			3	3.500	0.85		8.93		
			2	3.775	0.85		6.42		
			3	3.776	0.85		9.63		
			3	3.250	0.85		8.29		
			2	2.325	0.85		3.95		
			4	3.500	0.53		7.42		
			2	1.460	0.85		2.48		
		Slab	4	5.2	3.776		78.54		
			4	2.6	5.5		57.20		
			4	2.2	3.45		30.36		
			4	5.2	0.125		2.60		
			4	3.7	0.125		1.85		
			4	3.5	0.125		1.75		
		Lintel	8	1.05	0.150		1.26		
			8	0.75	0.150		0.90		
			3	1.50	0.250		1.13		
			3	1.00	0.150		0.45		
		For Reservoir	1	2.00	1.000		2.00		
			2	2.00	1.800		7.20		
			2	1.00	1.800		3.60		
							<b>410.08</b>	Sqm	<b>335.00</b>

P.W.D. (Bldg) 2017  
Page 42, Item No. 36(a)

SE  
31/01/22

BBISAD  
31/01/22

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate	
8	KMC.CONSO LIDAT E D RATE CIVIL_2018 2-2/b	Ordinary cement concrete(mix 1:1.5:3) with graded stone chips (20 mm. nominal size)excluding shuttering and reinforcement, if any, in ground floor as per IS codes. a) Pakur / Chandil Variety								
		Footing	16	1.20	1.20	0.175	4.03			
		Pedestal	16	0.50	0.50	0.45	1.80			
		Column	16	0.25	0.30	4.075	4.89			
			1	3.00	0.785	0.0625	0.15			
		Floor & Roof Beam	14	0.25	0.30	3.850	4.04			
			4	0.25	0.30	3.525	1.06			
			8	0.25	0.30	3.526	2.12			
			6	0.25	0.30	3.000	1.35			
			8	0.25	0.30	2.075	1.25			
			2	0.25	0.30	1.210	0.18			
			4	0.25	0.30	1.229	0.37			
			4	0.25	0.25	3.500	0.88			
		Slab	4	5.2	3.776	0.115	9.03			
			4	2.6	5.5	0.115	6.58			
			4	2.2	3.45	0.115	3.49			
		Lintel	8	1.05	0.25	0.15	0.32			
			8	1.00	0.25	0.15	0.30			
		Reservoir	1	2.50	1.50	0.115	0.43			
			2	2.00	1.80	0.075	0.54			
			2	1.00	1.80	0.075	0.27			
			2	3.00	0.450	0.15	0.41			
			<b>Total</b>					<b>43.49</b>	<b>Cum</b>	<b>6047.00</b>
9		PWD S.O.R-2017, 10TH Corr.- 1,dt.1.11.2019,p- 1/43	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m (i) Tor steel/Mild Steel III ISW/ISPL/SSI For 1st floor							
		1.1% OF CEMENT CONCRETE Total					<b>3.760</b>	<b>MT</b>	<b>54563.07</b>	
10	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-1,1-3	Brick work with 1st class bricks in cement mortar (4:1) a) In foundation and plinth	4	3.750	0.375	0.15	0.84			
			4	3.750	0.250	0.45	1.69			
			8	3.500	0.375	0.15	1.58			
			8	3.500	0.250	0.45	3.15			
			2	3.000	0.375	0.15	0.34			
			2	3.000	0.250	0.45	0.68			
			1	1.900	0.375	0.15	0.11			
			1	1.900	0.250	0.45	0.21			
			1	1.200	0.375	0.15	0.07			
			1	1.200	0.250	0.45	0.14			
			1	3.775	0.375	0.15	0.21			
		Step	1	1.20	0.750	0.45	0.41			
			1	10.00	0.375	0.15	0.56			
		<b>Total</b>					<b>9.99</b>	<b>cum</b>	<b>5682.00</b>	

9  
SHEK  
21/01/26

3/2/26

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate		
11	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-1,I-3	Brick work with 1st class bricks in cement mortar (4:1) b) In Superstructure & ground floor.	4	3.750	0.250	2.815	10.56				
			8	3.500	0.250	2.815	19.71				
			2	3.000	0.250	2.815	4.22				
			1	1.900	0.250	2.815	1.34				
			1	1.200	0.250	2.815	0.84				
			1	1.20	0.750	0.80	0.72				
			1	3.775	0.250	0.50	0.47				
			4	3.000	1.000	0.25	3.00				
			1	9.250	0.250	0.30	0.69				
			2	0.250	0.250	1.20	0.15				
									41.70	Cum	5905.00
			12	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-3,I-8	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	1	3.00	2.10		6.30	
6	1.350	2.10					17.01				
1	3.85	2.10					8.09				
1	2.50	2.10					5.25				
1	2.10	2.10					4.41				
1	1.60	2.10					3.36				
1	2.60	2.10					5.46				
1	2.50	2.10					5.25				
2	1.00	2.10					4.20				
9	1.80	0.75					12.15				
3	1.80	1.00					5.40				
									41.78	sqm	736.00
13	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-18,I-46	Cement concrete (1:1.5:3) with graded stone chips 5.6mm. Size with hexagonal square mesh wire netting I.R.C. Fabric mesh or X P.M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scraping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement excluding the cost of wire netting I.R.C. or X P.M. but including cost of all handling and scaffolding complete as per direction of Engineer-in-charge. (a) 37.5mm thick	2	2.000	1.500		6.00	sqm	593.00		
14	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-18,I-46	25mm. Thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacture's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately). (Chequering not required over concrete or painted surface.)	4	3.750	0.250		3.75				
			8	3.500	0.250		7.00				
			2	3.000	0.250		1.50				
			1	1.900	0.250		0.48				
			1	1.200	0.250		0.30				
			1	1.20	0.750		0.90				
			1	3.775	0.250		0.94				
									14.87	sqm	190.00
15	P.W.D. (Bldg) 2017 Page 47, Item No. 3	Supplying and laying polythene sheet (150gm/sqm.) over damp proof course or below flooring or roof terracing or in foundation trenches.	Same as Item No 7				410.08	Sqm	24.00		

4  
SATEL  
31/01/20

31/01/20

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate	
16	P.W.D. (Bldg) 2017,3rd corr. 04.06.2018,p-50,I-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).								
		(i) With 1:6 cement mortar								
		(b) 20 mm thick plaster(external) ground floor	1	4.35	3.60			15.66		
			2	5.20	3.60			37.44		
			4	3.775	3.60			54.36		
			1	2.10	2.00			4.20		
			4	4.35	0.30			5.22		
			4	3.50	1.00			14.00		
			4	2.60	5.200			54.08		
			4	2.20	4.500			39.60		
			4	1.70	3.000			20.40		
			1	5.00	2.500			12.50		
			2	1.00	1.200			2.40		
			2	9.25	0.900			16.65		
	2	0.25	0.250			0.13				
		<b>Total</b>					<b>276.64</b>	<b>Sqm</b>	<b>175.00</b>	
17	P.W.D. (Bldg) 2017 ,3rd corr. 04.06.2018,p-50,I-1	(i) With 1:6 cement mortarC)15 mm thick plaster(internal)	2	5.00	0.90		9.00			
			4	3.85	0.90		13.86			
			2	3.75	0.90		6.75			
			2	3.025	0.90		5.45			
			2	3.00	0.90		5.40			
			3	3.35	0.90		9.05			
			4	3.50	1.00		14.00			
				<b>Total</b>				<b>63.50</b>	<b>sqm</b>	<b>151.00</b>
18	P.W.D. (Bldg) 2017 ,3rd corr. 04.06.2018,p-50,I-1(ii)c	(ii) With 1:4 cement mortar (c) 10 mm thick plaster	4	2.60	5.200		54.08			
			4	2.20	4.500		39.60			
			4	1.70	3.000		20.40			
			1	5.00	2.500		12.50			
				<b>Total</b>				<b>126.58</b>	<b>sqm</b>	<b>133.00</b>
19	P.W.D. (Bldg) 2017 ,3rd corr. 04.06.2018,p-36,I-22	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. Wall (B) With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile Above 0.09 Sq.m								
		(a) Coloured decorative Toilet wall	2	3.000	2.10		12.60			
			2	3.025	2.10		12.71			
			14	3.85	2.10		113.19			
			16	1.35	2.10		45.36			
			2	1.50	2.10		6.30			
			4	1.60	2.10		13.44			
			6	3.98	2.10		50.09			
			2	5.00	2.10		21.00			
			2	1.994	2.10		8.37			
				<b>Total</b>				<b>283.05</b>	<b>Sqm</b>	<b>1109.00</b>

*Handwritten signature*  
31/10/22

*Handwritten signature*  
31/10/22

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate	
20	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-37,- 26	Supplying & laying 20 mm designer chequered tiles of any shade and of approved quality as per IS: 1237: 1980 laid in patterns as directed in pavement, footpath including necessary underlay 25 mm thick average cement mortar (1:3) complete in all respect with all labour and materials [using cement slurry @ 4.4 kg/Sq.m at back side of tiles. Cement of mortar & slurry will be supplied by the Department. Border concrete if necessary to be paid separately]								
			Front area	2	6.250	1.00		12.50		
				4	4.350	1.00		17.40		
				6	3.775	1.00		22.65		
			<b>Total</b>					<b>52.55</b>	<b>sqm</b>	<b>836.00</b>
21	P.W.D. (Bldg) 2017 Page 104, Item No. 13	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. ii) Grill weighing above 16 Kg./sq.mtr and above	Ventilator	4	2.00	0.45		3.60		
				4	6.35	0.75		19.05		
				6	4.775	0.75		21.49		
				2	7.25	0.75		10.88		
				4	0.50	1.00		2.00		
				2	8.00	0.60		9.60		
				4	5.00	0.60		12.00		
								78.61	Sqm	
					16 kg per sqm			1257.80	Kg	
			<b>Total</b>					<b>12.58</b>	<b>Qntl</b>	<b>7238.00</b>
22	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-37,- 25	Collapsible gate with 40mm.X40mm.X6mm. Tee as top and bottom guide rail 20mm.X10mm.X2mm. Vertical channels 100mm. Apart in fully stretcned position 20mm.X5mm. M.S. flats as collapsible bracing properly rivetted and washered including 38mm. Steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc. in walls, floors etc. and making good damares complete in ground floor.								
			Main gate	1	1.20	2.00		2.40	Sqm	4330.00
23	P.W.D. (Bldg) 2017 Page 297, Item No.26(b)	Providing and fixing of factory made uPVC casement window (White Colour) (U value=1.9-1.3 W/m 2 K, flame resistant, self extinguishing, lead free) comprising uPVC multi-chambered frame, Sash, & Mullion with having wall thickness of 2.3 mm (±0.2 mm) duly reinforced with G.I. section 1.6 mm (±0.2 mm) made from roll forming process of required length. All corners of frame and sash will be fusion welded. mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's, uPVC extruded glazing beads of appropriate dimension, EPDM gasket, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. shall be provided in all frame, sash & mullion, wherever necessary. Thereafter, 5 mm clear annealed glass shall be provided in the sash with the help of uPVC glazing bead and hardware, i.e., stainless steel (SS 304 grade) friction hinges & zinc alloy (white powder coated) casement handles (in window) & 3D Hinges & Multipoint Lock (in door) shall be provided. Window frame shall be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per approved drawing & direction of Engineer-InCharge. (Note: Profile manufacturer & Window Manufacturer must be one & same, Only manufacturer Warranty is acceptable) b) Casement Door with glass / uPVC panel frame of size 67 x 62 mm & Sash of size 67 x 115 mm & Mullion (if required) of size 67 x 78 mm both having wall thickness of 2.3 ± 0.2 mm.								
				1	1.20	2.00		2.40	Sqm	8657.00
24	P.W.D. (Bldg) 2017 Page 291, Item No.18	Supplying, fitting & fixing Stainless Steel 'D' or 'H' type of size 300 mm x 19 mm tubular Handle with Grade 304, CE certified, marked & conforming to EN - 1154, of approved quality of reputed brand as per direction of Engineer-inCharge fitted and fixed complete including all incidental charges.								
				2				2.00	Each	1571.00

STEEL  
STEEL

SHRINIVAS  
31/01/26

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
25	P.W.D. (Bldg) 2017 Page- 195 , Item- 7 (i)	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)(a) One Coat					126.58		
		ii) Solvent based interior grade Acrylic Primer For ceiling					63.50		
							190.08	%SqM	3370.00
26	P.W.D. (Bldg) 2017 Page- 196 , Item- 10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	Same as Item No 25				190.08	Sqm	70.00
27	P.W.D. (Bldg) 2017 Page- 196 , Item- 8 (b)	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: (a) One Coats					276.64		
		For outsid wall area					276.64	%SqM	3140.00
		<b>Total</b>							
28	P.W.D. (Bldg) 2017 Page- 197 , Item- 17	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) a) Normal Acrylic Emulsion					276.64		
		For outside wall area					276.64	Sqm	67.00
29	P.W.D. (Bldg) 2017 Page-200/ I tm.1(a)	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.					3.60		
		Ventilator	4	2.00	0.45		19.05		
		out side	4	6.35	0.75		21.49		
			6	4.775	0.75		10.88		
			2	7.25	0.75		2.00		
			4	0.50	1.00		3.00		
		Collapsible gate	1	1.50	2.00		60.01	sqm	29.00
		<b>Total</b>							
30	P.W.D. (Bldg) 2017 Page-200/ I tm.2(a), (iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)					60.01	Sqm	79.00
		Same as item no 29	4				4.00	Each	2435.00
31	P.W.D. (S&P) 2017 Page:-41 It.No.:- 1(iii)	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mmX75mmX75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. f(iii) 630 mm X 450 mm size (v) 900 mm long.					9.00	Each	147.00
32	Page:-43 It.No.:- 9(v) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia.	5				5.00	Each	1015.00
33	P.W.D. (S&P) 2017 Page:-36 It.No.:-2	Supplying, fitting and fixing 10 litre P.V.C. low-own cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.							

*Handwritten signature and date: 21/10/22*

*Handwritten signature and date: 31/01/26*

No	L	B	Ht.	Quantity	Unit	Rate
----	---	---	-----	----------	------	------

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
34	P.W.D. (Bldg) 2017 .7th corr. 22.01.2020,p-1,l-1	Constructing Inspection pit of inside measurement 600mm.X600mm.Xupto 600mm.(depth) with 250mm. Thick 1st class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100mm. Thick cement concrete (1:3:6) with stone chips over a layer of Jhama brick flat soling, 15mm. thick(1:4) cement plaster to inside walls and out-side walls upto G.L. and 20mm. thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100mm. thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcement upto 1% and shuttering including 6mm. thick cement plaster (1:4) in all external surfaces of the slab and one 560mm. dia R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earth work in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. With Pakur variety.	5				5.00	Each	7253.00
35	Sanitary & Plumb.2017 Page- 66. Item No. 16	Supplying fitting and fixing with cement jointing (3:1) salt glazed stoneware pipe including excavation of earth upto 1.50m depth in all sorts of soil both mixed or unmixed and refilling(but excluding concreting at bottom and sides). iii) 150 mm. Dia	1	15.00			15.00	Metre	334.00
36	P.W.D. (S&P) 2017 P: 81, It: 15(ii)(E2)	Supplying, fitting and fixing beveled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	8				8.00	Each	484.00
37	Page:-45 It.No.:- 19(a)(ii) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing pillar cock of approved make. a)(ii)C.P. Pillar Cock Super Deluxe with Aerator-15mm.(Equivalent to Code No. 508 & Model No. Tropical /Sumthing Special of ESSCO or similar brand)	4				4.00	Each	592.00
38	Page:-6 It.No.:- 7(a)(ii) of P.W.D'S Sanitary Schedule.	(ii)Chromium plated Bib Cock long body with wall flange with aerator (Equivalent to Code No. 512 & Model - Tropical / Sumthing Special of ESSCO or similar brand)	6				6.00	Each	659.00
39	P.W.D. (S&P) 2017 Page:-6 It.No.:- 7(b)(ii).	(ii) Chromium plated Concealed Stop Cock (Equivalent to Code No.514(A) & Model - Tropical / Sumthing Special of ESSCO or similar brand).	14				14.00	Each	674.00
40	Page:-29 It.No.:-1 of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778 :2007 .with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longs crew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing material sinany position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. Nos eparate payment will be made for accesories, specials. (a) For exposed work. (i) CPVC pipes Class-1, SDR-II 22mm Dia	5	1.00			5.00	Rm	283.00
41	Page:-29 It.No.:-1 of P.W.D'S Sanitary Schedule.	(a) For exposed work. (i) CPVC pipes Class-1, SDR-II 25mm Dia	8	5.00			40.00	Rm	208.00
42	P.W.D. (S&P) 2017 Page:-29 It.No.:-1, (b)	(b) For concealed work. (i) CPVC pipes Class-1, SDR-II 15mm Dia	15	2.50			37.50	Rm	140.00
43	Page:-5 It.No.:-5 (vi) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only). 32 mm dia	2	2.00			4.00	Each	1160.00

*Handwritten signature and date:*  
31/01/26

*Handwritten signature and date:*  
31/01/26

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
44	PWD S&P-2017, Page:-37 It.No.-6(b).	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (d) 1000 litre capacity.	2				2.00	Each	5128.00
45	Sanitary & Plumb.2017 Page-82, Item-22	Supplying, fitting and fixing towel rail with two brackets. C.P. over brass 25mm. Dia and 600mm. Long	5				5.00	Each	430.00
46	Sanitary & Plumb.2017 Page-19, Item No. 20	Supply of high density polythene pipe conforming to IS 4984-1985.A) 6Kg/sq.cm. (Working pressure )Dia75mm	6	3.00			18.00	Each	248.00
47	Sanitary & Plumb.2017 Page-19, Item No. 20	Supply of high density polythene pipe conforming to IS 4984-1985.A) 6Kg/sq.cm. (Working pressure )Dia 100mm	2	3.00			6.00	Each	545.00
48	Sanitary & Plumb.2017 Page-14, Item No.19(III)C	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). (C) Elbow (Dia)80 mm	4				4.00	Each	266.00
49	Sanitary & Plumb.2017 Page-14, Item No.19(III)E	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). (E) Tee (Dia)80 mm	4				4.00	Each	349.00
50	P.W.D. (S&P) 2017 P.-37 It.-10(A)	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity.(a) Upto 1st story from G.L.	2				2.00	Each	96.00
51	PWD(W.B)- Building Works- P-298 It- 27	Providing and fixing of factory made uPVC Louver window (White Colour) (U value=1.9-1.3 W/m <sup>2</sup> K, flame resistant, self extinguishing, lead free) comprising of uPVC multi-chambered with wall thickness of 2.3mm (±0.2 mm) duly reinforced with 1.6 mm (±0.2 mm) thick G. I. Section made from roll forming process of required length (shape & size according to uPVC profile). Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. Both vertical sides of the frame, adjustable louver mechanism having one lever shall be fitted with the provision of 4 mm glass. Window frame will be fixed to the wall with 100mm long and 8mm dia for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per as per approved drawing & direction of Engineer-in-Charge. a) Louver Window with provision of Exhaust Fan frame of size 67 x 62 mm & Sash / Mullion of size 67 x 78 mm both	7	0.50	0.50		1.75	sqm	7149.00
52	PWD(W.B)- Building Works- P-198 It- 5	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick					190.08		
							190.08	sqm	122.00
		Total							
53	P.W.D. (Bldg) 2017 Page 14 Item No. 1,3rd corr. 04.06.2018,p-80,I-1	Supplying and laying true to line and level Anti-Skid, Full Body, Homogeneous & Granular finish Vitrified Tiles conforming to IS:15622-2006 & IS 4457-2007 and testing shall be made in accordance with IS:13630 [Non-modular sizes for tiles with Skid resistance > 0.5, Mohr's hardness > 5.0, Staining resistance: Class-1, Water Absorption: E < 0.5%], MOR > 35 N/sq.mm in Internal area of building e.g. Toilet Block, Passage, Corridor, Accessible Open Terrace etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg./Sqm or using Polymerised Adhesive (6 mm thick layer applied directly over finished artificial stone floor/ Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per Sqm below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles/ epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) b) In Ground Floor: Sizes-600 mm x600mm x10 mm with breaking strength > 1500 N	1	8.300	3.850		31.96		

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
			1	3.500	3.525		12.34		
			1	3.850	5.000		19.25		
			1	3.525	3.850		13.57		
							<b>77.12</b>	sqm	<b>1589.00</b>

  
 21/01/20

  
 31/01/20

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
54	PWD(W.B)2017- Building Works- P- 62 It- 32	Supplying, fitting & fixing granite slabs 15mm to 18 mm. thick with uniform texture & without decorative veins in columns, wall, fascia etc. with 15 mm thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging, curing and roughening of concrete surface complete. Area of each Granite slab > 0.6 upto 1.0 square metre. [Using cement slurry at back side of granite @ 4.4 kg/sq.m & white cement slurry for joint filling @ 1.8 kg/sq.m]							
		Inside	6	1.20	0.50		3.60		
		out side	1	3.60	0.75		2.70		
			1	4.15	0.75		3.11		
			1	3.00	1.50		4.50		
			2	4.35	0.60		5.22		
			4	3.775	0.60		9.06		
			2	5.25	0.60		6.30		
			1	3.78	1.20		4.53		
			1	9.25	0.30		2.78		
		<b>TOTAL</b>					<b>41.80</b>	<b>sqm</b>	<b>2317.00</b>
55	Sanitary & Plumb.2017 Page- 79, Item No. 2	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc.(b) With 'S' trap	2				2.00	Each	1512.00
56	Sanitary & Plumb.2017 Page- 79, Item No. 2	Supplying, fitting and fixing Orissa pattern water closet in white glazed vitreous chinaware of approved make in position complete excluding 'P' or 'S' trap (excluding cost of concrete for fixing). (ii) 530 mm X 410 mm	3				3.00	Each	1522.00
57	Sanitary & Plumb.2017 Page- 80, Item No. 7	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately). (i) 450 mm X 350 mm	3				3.00	Each	881.00
58	Sanitary & Plumb.2017 Page- 80, Item No. 7	Supplying, fitting and fixing in position C.I. manhole/ pit cover with rim. (ii) 450 mm X 100 mm X 25 kg (approx.)	1				1.00	Each	2035.00
59	K.M.C. FAIR RATE approved by D.G.(Bustee), dt- 20.10.14	Decorative relief work of artistic nature on exposed surface of cement concrete, plaster or brick work etc. on the surface sketch drawn by artist including preparing the base by rough plaster of sand, cement (1:3) with water proofing compound including oil paint (Two Coats of approved shade, colour over a coat of primer) and applying two coats of decorative cement based paint to the rest portion of the back and other miscellaneous work complete including all materials, labours, scaffolding etc. as per direction of Engineer-in-Charge	2	2.50	2.000		10.00	Sqm	3281.14
60	PWD(W.B)2017- Building Works- P- 67 It- 38(iii)	Supplying, fitting & fixing Glass mosaic tiles at finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design, fixing in customize design as per direction of Engineerin- Charge. The glass mosaic tiles to be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. The rate is inclusive of all operation, material and required pattern approved by Engineer-in-Charge. [At Ground Floor] iii) Mural aligned/ CAD Design Type	4	3.000	2.000		24.00		
			2	3.000	2.000		12.00		
			2	4.35	1.20		10.44		
			2	3.775	1.20		9.06		
			1	1.200	1.00		1.20		
							<b>25.20</b>	<b>Sqm</b>	<b>3614.00</b>

24/11/24

31/11/24

Sl. No	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate
61	Sanitary & Plumb.2017 Page-88, Item No. 3	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560mm dia R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1: 1.5: 3) top slab with necessary fittings, 20mm thick cement plaster (4:1) with neat cement finish to the internal surfaces and 15mm thick cement plaster (4:1) to outside wall upto 200mm below G.L. floor finished with 25mm thick grey artificial stone over 100mm thick R.C.C (1: 1.5: 3) bottom slab including supplying, fitting, and fixing all necessary specials, fittings, S.W. tees, C.I foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including, constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @5% by weight of cement with all costs of labour and materials. iii) For 50 User (Pakur Variety)	1				1.00	Each	89678.00
62	PWD(W.B)2017-Building Works- P-261 It- 9(iv)	Supplying and Planting of different plant / trees (Supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads & lift, carriage, handling, manuring, applying pesticide and fertilizer etc. iv) Rangon hi-breed healthy plant.	120				120.00	Each	23.00
63	PWD(W.B)2017-Building Works- P-261 It- 9(vi)	vi) Duranta healthy plant of big size	80				80.00	Each	25.00
64	PWD(W.B)2017-Building Works- P-109 It- 22	Supplying, fitting and fixing Stainless Steel railing consist of 38mm dia and 900mm height vertical balustrade at every two alternative steps, 50mm dia top rail, 3 (three) nos 19mm dia horizontal Stainless steel pipe and base/cover plate with Stainless Steel GRADE 304 containing 7.5% nickle (Interior Grade) Brushed/Mat finish, complete as per direction of the Engineer-in-charge. Weight of Stainless Steel railing per metre 6.5 Kg (approx)	1	3.5			3.5	Mtr.	5974.00
65	PWD(W.B)2017-Building Works- P-243 It- 9-xiv	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987.	4	0.5	1		2		
		ii) 4mm thick coloured / tinted / smoke glass.	2	5	0.6		6		
							8	Sqm	468.00
66	PWD(W.B)2017-Building Works- P-115 ,It- 3-ii	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria.	2	4.5			9		
		(ii) 66mm x 70mm	9	4.35			39.15		
							48.15	Mtr.	497.00
67	PWD(W.B)2017-Building Works- P-125 ,It- 14-i	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor	2	1.8	0.9		3.24		
		i) 32 mm thick	10	0.75	1.8		13.5		
							16.74	Sqm	2763.00
68	Sanitary & Plumb.2017 Page-4, Item No. 3-d	Chromium plated Hand shower with Flexible Tube & fittings(Equivalent to Code No. Hsh-1937 & (Equivalent to Code No. 5037 & Model - Florentine of Jaquar or similar)).	2				2	Each	2390.00
69	Sanitary & Plumb.2017 Page-4, Item No. 3-iii	(iii) Chromium plated shower arm 240 mm long (Equivalent to Code No. 536(A) & Model- Tropical / Sumthing Special of ESSCO or similar brand).	2				2	Each	309.00

9  
SHEK  
31/01/26

10/01/26  
31/01/26  
26

Sl. No	Sch. Item	Description of item	No	L	B	Ht.	Quantity	Unit	Rate
70	PWD(W.B)2017-Building Works-P-259 ,It- 4	Supplying and fixing grasses tiles of grass Maxican Carpet/Selection No. 1 Healthy & fresh grasses (size 1'x1' or bigger) including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth as required by Engineer-in-charge. (Rate includes supply of labour, tools & plants including materials)	1	5.00	8.00		40	% Sq.M.	20142
71	PWD(W.B)2017-Building Works-P-261 It- 9(iv)	Supplying and Planting of different plant / trees ( Supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads & lift, carriage, handling, manuring, applying presticide and fertilizer etc. iv) Rangoon hi-breed healthy plant.	150				150	Each	23.00
72	PWD(W.B)2017-Building Works-P-261 It- 9(vi)	vi) Duranta healthy plant of big size	150				150	Each	25.00

g  
SHEC  
31/01/26

Executive Engineer (Civil)  
Bustee Services, K.M.C.

Inch.  
31/01/26  
Dy. Chief Engineer (Civil)  
Uttaran Services Department  
K. M. C.

D. G.  
Uttaran Services Department  
K. M. C.

NAME OF WORK:- CONSTRUCTION OF PAY AND USE TOILETS ALONGWITH LANDSCAPING WORK INFRONT OF INDIAN MUSIUM UNDER  
PARK STREET FLYOVER, KOLKATA IN WARD NO 63, BOROUGH-VII

rtmer

CIVIL WORK ABSTRACT

Estimated Amount:-Rs. 2471194.36

Estimate No-KMC/US/...../ Of 202 -2

Sl. No	Sch. Item	Description of Item	Quantity	Unit	Rate	Amount Rs.
1	P.W.D. (Bldg) 2017 Page 1, Item No. 1	Earthwork in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sand stone) including removing, spreading or stacking the spoils within a lead of 75m as directed. The item includes necessary trimming the sides of trenches levelling dressing and ramming the bottom bailing out water as required complete. Depth of excavation not exceeding 1500 mm.				
		<b>Total</b>	<b>40.50</b>	<b>% Cum</b>	<b>11927.00</b>	<b>4830.44</b>
2	P.W.D. (Bldg) 2017 Page 1, Item No 3(a)	Earthwork in filling in foundation trenches or plinth with good earth in layers not exceeding 150mm. Including watering andramming etc. layer by layer complete (Payment to be made on the basis of measurement of finished quantity of work). With earth obtained from excavation of foundation				
			<b>8.10</b>	<b>%Cum</b>	<b>7754.00</b>	<b>628.07</b>
3	P.W.D. (Bldg) 2017,5th Corr 16.04.2019 Page 2, Item 1	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm. As directed and consolidating same by thorough saturation with water ramming complete including the cost of supply of sand. (Payment to be made on measurement of finished quantity)				
			<b>12.42</b>	<b>%Cum</b>	<b>131714.00</b>	<b>16358.88</b>
4	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-1	Single brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with powdered earth or local sand.				
			<b>156.40</b>	<b>Sqm</b>	<b>361.00</b>	<b>56460.40</b>
5	P.W.D. (Bldg) 2017 .3rd corr. 04.06.2018,p-10	Cement concrete with graded jharma khoa (30 mm. size) excluding shuttering in ground floor and foundation. a) 1:3:6 Proportion				
			<b>8.75</b>	<b>Cum</b>	<b>4761.00</b>	<b>41658.75</b>
6	P.W.D. (Bldg) 2017 .3rd corr. 04.06.2018,p-10	Cement concrete with graded jharma khoa (30 mm. size) excluding shuttering in ground floor and foundation. a) 1:4:8 Proportion				
			<b>2.72</b>	<b>Cum</b>	<b>4566.00</b>	<b>12419.52</b>
7	P.W.D. (Bldg) 2017 Page 42, Item No 36(a)	Hire and Labour charges for shuttering with centering and necessary staging upto 4m using approved stout, props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns lintels, curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor). 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-charge.				
			<b>410.08</b>	<b>Sqm</b>	<b>335.00</b>	<b>137375.13</b>

*S. Saha*

*Abinav*  
09/01/2026

**Executive Engineer (Civil)**  
**Urban Services Department**  
**R. M. C.**

8	KMC.CONSolidate D RATE CIVIL_2018 2-2/b	Ordinary cement concrete(mix 1:1.5:3) with graded stone chips (20 mm. nominal size)excluding shuttering and reinforcement, if any, in ground floor as per IS codes. a) Pakur / Chandil Variety				
Total			43.49	Cum	6047.00	262984.03

9  
2/2/20

*Prisw...*  
09/01/20

9	PWD S.O.R-2017, 2ND Corr.- 1.d.18.04.2018,p-2	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m (i) Tor steel/Mild Steel iii ISW/ISPI SSJ For 1st floor					
10	P.W.D. (Bldg) 2017 3rd corr.	Brick work with 1st class bricks in cement mortar (4:1) a) In foundation and plinth	3.760	MT	68200.00	256432.00	
11	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-1,1-3	Brick work with 1st class bricks in cement mortar (4:1) b) In Superstructure & ground floor.	Total	9.99	cum	5682.00	56763.18
12	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-3,1-8	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	41.70	Cum	5905.00	246238.50	
13	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-18,1-46	Cement concrete (1:1.5:3) with graded stone chips 5.6mm. Size with hexagonal square mesh wire netting I.R.C. Fabric mesh or X P.M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scraping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement excluding the cost of wire netting I.R.C. or X P.M. but including cost of all handling and scaffolding complete as per direction of Engineer-in-charge. (a) 37.5mm thick	Total	41.78	sqm	736.00	30746.40
14	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-18,1-46	25mm. Thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacture's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately). (Chequering not required over concrete or painted surface.)	6.00	sqm	593.00	3558.00	
15	P.W.D. (Bldg) 2017 Page 47, Item No. 3	Supplying and laying polythene sheet (150gm/sqm.) over damp proof course or below flooring or roof terracing or in foundation trenches.	14.87	sqm	190.00	2825.06	
			410.08	Sqm	24.00	9841.80	
16	P.W.D. (Bldg) 2017,3rd corr. 04.06.2018,p-50,1-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). (i) With 1:6 cement mortar (b) 20 mm thick plaster(external) ground floor	Total	276.64	Sqm	175.00	48411.13
17	P.W.D. (Bldg) 2017 3rd corr.	(i) With 1:6 cement mortar C) 15 mm thick plaster (internal)	Total	63.50	sqm	151.00	9588.50
18	P.W.D. (Bldg) 2017 3rd corr. 04.06.2018,p-50,1-1(ii)c	(ii) With 1:4 cement mortar (c) 10 mm thick plaster					
			126.58	sqm	133.00	16835.14	

*S. Chel*

*09/01/2026*

19	P.W.D. (Bldg) 2017 .3rd corr. 04.06.2018,p-36,- 22	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. Wall (B) With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile Above 0.09 Sq.m (i) Coloured decorative					
Total			283.05	Sqm	1109.00	313907.77	
20	P.W.D. (Bldg) 2017 .3rd corr. 04.06.2018,p-37,- 26	Supplying & laying 20 mm designer chequered tiles of any shade and of approved quality as per IS: 1237: 1980 laid in patterns as directed in pavement, footpath including necessary underlay 25 mm thick average cement mortar (1:3) complete in all respect with all labour and materials [using cement slurry @ 4.4 kg/Sq.m at back side of tiles. Cement of mortar & slurry will be supplied by the Department. Border concrete if necessary to be paid separately]					
Total			52.55	sqm	836.00	43931.80	
21	P.W.D. (Bldg) 2017 Page 104, Item No. 13	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. ii) Grill weighing above 16 Kg /sq.mtr and above					
Total			12.58	Qntl	7238.00	91039.56	
22	P.W.D. (Bldg) 2017 .3rd corr. 04.06.2018,p-37,- 25	Collapsible gate with 40mm.X40mm.X6mm. Tee as top and bottom guide rail 20mm.X10mm.X2mm. Vertical channels 100mm. Apart in fully stretched position 20mm.X5mm. M.S. flats as collapsible bracing properly rivetted and washered including 38mm. Steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc. in walls, floors etc. and making good damages complete in ground floor.					
Total			2.40	Sqm	4330.00	10392.00	
23	P.W.D. (Bldg) 2017 Page 297, Item No.26(b)	Providing and fixing of factory made uPVC casement window (White Colour) (U value=1.9-1.3 W/m 2 K, flame resistant, self extinguishing, lead free) comprising uPVC multi-chambered frame, Sash, & Mullion with having wall thickness of 2.3 mm (±0.2 mm) duly reinforced with G.I. section 1.6 mm (±0.2 mm) made from roll forming process of required length. All corners of frame and sash will be fusion welded. Mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's, uPVC extruded glazing beads of appropriate dimension, EPDM gasket, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. shall be provided in all frame, sash & mullion, wherever necessary. Thereafter, 5 mm clear annealed glass shall be provided in the sash with the help of uPVC glazing bead and hardware, i.e. stainless steel (SS 304 grade) friction hinges & zinc alloy (white powder coated) casement handles (in window) & 3D Hinges & Multipoint Lock (in door) shall be provided. Window frame shall be fixed to the wall with 100mm long and 8mm dia. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per approved drawing & direction of Engineer-in-Charge. (Note: Profile manufacturer & Window Manufacturer must be one & same. Only manufacturer Warranty is acceptable) b) Casement Door with glass / uPVC panel frame of size 67 x 62 mm & Sash of size 67 x 115 mm & Mullion (if required) of size 67 x 78 mm both having wall thickness of 2.3 ± 0.2 mm.					
Total			2.40	Sqm	8657.00	20776.80	

*Handwritten signature/initials*

*Handwritten signature/initials*  
09.01/20

24	P.W.D. (Bldg) 2017 Page 291, Item No.18	Supplying, fitting & fixing Stainless Steel 'D' or 'H' type of size 300 mm x 19 mm tubular Handle with Grade 304, CE certified, marked & conforming to EN - 1154, of approved quality of reputed brand as per direction of Engineer-in-Charge fitted and fixed complete including all incidental charges.					
25	P.W.D. (Bldg) 2017 Page- 195, Item- 7 (i)	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)(a) One Coat ii) Solvent based interior grade Acrylic Primer	2.00	Each	1571.00	3142.00	
26	P.W.D. (Bldg) 2017 Page- 196, Item- 10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	190.08	%Sqm	3370.00	6405.70	
27	P.W.D. (Bldg) 2017 Page- 196, Item- 8 (b)	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor. (a) One Coat	190.08	Sqm	70.00	13305.60	
Total			276.64	%Sqm	3140.00	8686.34	
28	P.W.D. (Bldg) 2017 Page- 197, Item- 17	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) a) Normal Acrylic Emulsion					
29	P.W.D. (Bldg) 2017 Page-200/ Itm.1(a)	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	276.64	Sqm	67.00	18534.55	
Total			60.01	sqm	29.00	1740.36	
30	P.W.D. (Bldg) 2017 Page-200/ Itm.2(a). (iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary: (b) On steel or other metal surface: With super gloss (hi-gloss) - (i) In rooms (both any shade except white). Same as item no 29					
31	P.W.D. (S&P) 2017 Page-41 It.No.- 1(iii)	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mmX75mmX75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (iii) 640 mm X 450 mm size	60.01	Sqm	79.00	4740.99	
32	Page-43 It.No.-9(v) of P.W.D.'S Sanitary Schedule	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. (v) 900 mm long.	4.00	Each	2435.00	9740.00	
Total			9.00	Each	147.00	1323.00	

24	P.W.D. (Bldg) 2017 Page 291, Item No.18	Supplying, fitting & fixing Stainless Steel 'D' or 'H' type of size 300 mm x 19 mm tubular Handle with Grade 304, CE certified, marked & conforming to EN - 1154, of approved quality of reputed brand as per direction of Engineer-inCharge fitted and fixed complete including all incidental charges.				
25	P.W.D. (Bldg) 2017 Page- 195 , Item- 7 (i)	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)(a) One Coat ii) Solvent based interior grade Acrylic Primer	2.00	Each	1571.00	3142.00
26	P.W.D. (Bldg) 2017 Page- 196 , Item- 10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	190.08	%Sqm	3370.00	6405.70
27	P.W.D. (Bldg) 2017 Page- 196 , Item- 8 (b)	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: (a) One Coats	190.08	Sqm	70.00	13305.60
<b>Total</b>			<b>276.64</b>	<b>%Sqm</b>	<b>3140.00</b>	<b>8686.34</b>
28	P.W.D. (Bldg) 2017 Page- 197 , Item- 17	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) a) Normal Acrylic Emulsion	276.64	Sqm	67.00	18534.55
29	P.W.D. (Bldg) 2017 Page-200/ itm.1(a)	(a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc.				
<b>Total</b>			<b>60.01</b>	<b>sqm</b>	<b>29.00</b>	<b>1740.36</b>
30	P.W.D. (Bldg) 2017 Page-200/ itm.2(a), (iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothing surface by sand papering etc. including using of approved putty etc. on the surface, if necessary: (b) On steel or other metal surface: With super gloss (hi-gloss) - (iv) Two coats (with any shade except white) Same as item no 29	60.01	Sqm	79.00	4740.99
31	P.W.D. (S&P) 2017 Page:-41 It.No.:- 1(iii)	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mmX75mmX75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (iii) 630 mm X 450 mm size	4.00	Each	2435.00	9740.00
32	Page:-43 It.No.:-9(v) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling (v) 900 mm long. with heavy brass C.P. nut, 15 mm dia.	9.00	Each	147.00	1323.00
33	P.W.D. (S&P) 2017 Page:-36 It.No.:-2.	Supplying, fitting and fixing 10 litre P.V.C. low-own cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	5.00	Each	1015.00	5075.00

*S. S. S. S.*

*BABBAR*  
*09/01/26*

34	P.W.D. (Bldg) 2017 .7th corr. 22.01.2020,p-1,1-1	Constructing inspection pit of inside measurement 600mm.X600mm.Xupto 600mm.(depth) with 250mm. Thick 1st class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100mm. Thick cement concrete (1:3:6) with stone chips over a layer of Jhama brick flat soling, 15mm. thick(1:4) cement plaster to inside walls and out-side walls upto G.L. and 20mm. thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100mm. thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcement upto 1% and shuttering including 6mm. thick cement plaster (1:4) in all external surfaces of the slab and one 560mm. dia R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earth work in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. With Pakur variety.	5.00	Each	7253.00	36265.00
35	Sanitary & Plumb.2017 Page- 66 Item No. 16	Supplying fitting and fixing with cement jointing (3:1) salt glazed stoneware pipe including excavation of earth upto 1.50m depth in all sorts of soil both mixed or unmixed and refilling(but excluding concrete at bottom and sides).				
		iii) 150 mm. Dia	15.00	Metre	334.00	5010.00
36	P.W.D. (S&P) 2017 P. 81, It: 15(ii)(E2)	Supplying, fitting and fixing beveled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	8.00	Each	484.00	3872.00
37	Page:-45 It.No.:- 19(a)(ii) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing pillar cock of approved make. a)(ii)C.P. Pillar Cock Super Deluxe with Aerator-15mm.(Equivalent to Code No. 508 & Model No. Tropical /Sumthing Special of ESSCO or similar brand)	4.00	Each	592.00	2368.00
38	Page:-6 It.No.:- 7(a)(ii) of P.W.D'S Sanitary Schedule.	(ii)Chromium plated Bib Cock long body with wall flange with aerator (Equivalent to Code No. 512 & Model -Tropical / Sumthing Special of ESSCO or similar brand)	6.00	Each	659.00	3954.00
39	P.W.D. (S&P) 2017 Page:-6 It.No.:- 7(b)(ii)	(ii) Chromium plated Concealed Stop Cock (Equivalent to Code No.514(A) & Model - Tropical / Sumthing Special of ESSCO or similar brand)	14.00	Each	674.00	9436.00
40	Page:-29 It.No.:-1 of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing CPVC (Chlorinated Polyvinyl Chloride) pipes of approved make conforming to IS-15778 :2007 .with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longs crew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing material sinany position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. Nos eparate payment will be made for accesories, specials. (a) For exposed work. (i) CPVC pipes Class-1, SDR-II 32mm Dia	5.00	Rm	283.00	1415.00
41	Page:-29 It.No.:-1 of P.W.D'S Sanitary Schedule.	(a) For exposed work. 25mm Dia (i) CPVC pipes Class-1, SDR-II	40.00	Rm	208.00	8320.00
42	P.W.D. (S&P) 2017 Page:-29 It.No.:-1, ( b)	(b) For concealed work. 15mm Dia (i) CPVC pipes Class-1, SDR-II	37.50	Rm	140.00	5250.00
43	Page:-5 It.No.:-5 (vi) of P.W.D'S Sanitary Schedule.	Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only). 32 mm dia	4.00	Each	1160.00	4640.00
44	PWD S&P-2017, Page:-37 It.No.:-6(b)	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (d) 1000 litre capacity.	2.00	Each	5128.00	10256.00

45	Sanitary & Plumb.2017 Page-82, Item-22	Supplying, fitting and fixing towel rail with two brackets. C.P. over brass 25mm. Dia and 600mm. Long	5.00	Each	430.00	2150.00
46	Sanitary & Plumb.2017 Page-19, Item No. 20	Supply of high density polythene pipe conforming to IS 4984-1985.A) 6Kg/sq.cm. (Working pressure )Dia75mm	18.00	Each	248.00	4464.00
47	Sanitary & Plumb.2017 Page-19, Item No. 20	Supply of high density polythene pipe conforming to IS 4984-1985.A) 6Kg/sq.cm. (Working pressure )Dia 100mm	6.00	Each	545.00	3270.00
48	Sanitary & Plumb.2017 Page-14, Item No.19(III)C	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). (C) Elbow (Dia)80 mm	4.00	Each	266.00	1064.00
49	Sanitary & Plumb.2017 Page-14, Item No.19(III)E	Supply of PVC pipes & fittings Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). (E) Tee (Dia)80 mm	4.00	Each	349.00	1396.00
50	P.W.D. (S&P) 2017 P-37 It-10(A)	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity.(a) Upto 1st story from G.L.	2.00	Each	96.00	192.00
51	PWD(W.B)- Building Works- P- 298 It- 27	Providing and fixing of factory made uPVC Louver window (White Colour) (U value=1.9-1.3 W/m <sup>2</sup> K, flame resistant, self extinguishing, lead free) comprising of uPVC multi-chambered with wall thickness of 2.3mm (±0.2 mm ) duly reinforced with 1.6 mm (±0.2 mm) thick G. I. Section made from roll forming process of required length (shape & size according to uPVC profile). Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. Both vertical sides of the frame, adjustable louver mechanism having one lever shall be fitted with the provision of 4 mm glass. Window frame will be fixed to the wall with 100mm long and 8mm dia for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. Fasteners and after fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size, of approved quality complete in all respect as per as per approved drawing & direction of Engineer-in-Charge. a) Louver Window with provision of Exhaust Fan frame of size 67 x 62 mm & Sash / Mullion of size 67 x 78 mm both having wall thickness of 2.3 ± 0.2 mm	1.75	sqm	7149.00	12510.75
52	PWD(W.B)- Building Works- P- 198 It- 5	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick				
			190.08	sqm	122.00	23189.76

*S. S. S. S.*

*S. S. S. S.*  
09/01/26

53	P.W.D. (Bldg) 2017 Page 14 Item No. 1,3rd corr. 04.06.2018,p-80,1-1	Supplying and laying true to line and level Anti-Skid, Full Body, Homogeneous & Granular finish Vitrified Tiles conforming to IS:15622-2006 & IS 4457-2007 and testing shall be made in accordance with IS:13630 [Non- modular sizes for tiles with Skid resistance > 0.5, Mohr's hardness > 5.0, Staining resistance: Class-1, Water Absorption: E < 0.5%), MOR > 35 N/sq.mm in Internal area of building e.g. Toilet Block, Passage, Corridor, Accessible Open Terrace etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg./Sqm or using Polymerised Adhesive (6 mm thick layer applied directly over finished artificial stone floor/ Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per Sqm below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles/ epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) b) In Ground Floor: Sizes-600 mm x600mm x10 mm with breaking strength > 1500 N				
			77.12	sqm	1589.00	122543.68
54	PWD(W.B)2017- Building Works- P- 62 It- 32	Supplying, fitting & fixing granite slabs 15mm to 18 mm. thick with uniform texture & without decorative veins in columns, wall, fascia etc. with 15 mm thick [avg] cement mortar (1:2) including making suitable arrangements to hold the stones properly by brass / copper hooks including pointing in cement mortar (1:2) (1 white cement : 2 marble dust) with admixture of pigment matching the stone shades all complete as per direction of the Engineer-in-charge including cost of all materials, labours, scaffolding, staging ,curing and roughening of concrete surface complete. Area of each Granite slab > 0.6 upto 1.0 square metre. (Using cement slurry at back side of granite @ 4.4 kg/sq.m & white cement slurry for joint filling @ 1.8 kg/sq.m)	41.80	sqm	2317.00	96850.60
55	Sanitary & Plumb.2017 Page- 79, Item No. 2	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc.(b) With 'S' trap	2.00	Each	1512.00	3024.00
56	Sanitary & Plumb.2017 Page- 79, Item No. 2	Supplying, fitting and fixing Orissa pattern water closet in white glazed vitreous chinaware of approved make in position complete excluding 'P' or 'S' trap (excluding cost of concrete for fixing).(ii) 530 mm X 410 mm	3.00	Each	1522.00	4566.00
57	Sanitary & Plumb.2017 Page- 80, Item No. 7	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid separately). (i) 450 mm X 350 mm	3.00	Each	881.00	2643.00
58	Sanitary & Plumb.2017 Page- 80, Item No. 7	Supplying, fitting and fixing in position C.I. manhole/ pit cover with rim. (ii) 450 mm X 100 mm X 25 kg (approx.)	1.00	Each	2035.00	2035.00
59	K.M.C. FAIR RATE approved by D.G.(Bustee), dt- 20.10.14	Decorative relief work of artistic nature on exposed surface of cement concrete, plaster or brick work etc. on the surface sketch drawn by artist including preparing the base by rough plaster of sand, cement (1:3) with water proofing compound including oil paint (Two Coats of approved shade, colour over a coat of primer) and applying two coats of decorative cement based paint to the rest portion of the back and other miscellaneous work complete including all materials, labours, scaffolding etc. as per direction of Engineer-in-Charge	10.00	Sqm	3281.14	32811.40

9  
SMA

28/01/20

60	PWD(W.B)2017- Building Works- P- 67 It- 38(iii)	Supplying, fitting & fixing Glass mosaic tiles at finished plain wall surface of size 20 mm x 20 mm x 4 mm in all colour, design, fixing in customize design as per direction of Engineer-in-Charge. The glass mosaic tiles to be fixed on the wall surface with the help of approved adhesive applied at the rate of 2.5 kg per sqm and grouting of the same. The rate is inclusive of all operation, material and required pattern approved by Engineer-in-Charge. [At Ground Floor] Mural aligned / CAD Design Type	iii)				
61	Sanitary & Plumb.2017 Page- 88, Item No. 3	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560mm dia.R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1: 1.5: 3) top slab with necessary fittings, 20mm thick cement plaster (4: 1) with neat cement finish to the internal surfaces and 15mm thick cement plaster (4: 1) to outside wall upto 200mm below G.L. floor finished with 25mm thick grey artificial stone over 100mm thick R.C.C (1: 1.5: 3) bottom slab including supplying, fitting, and fixing all necessary specials, fittings, S.W. tees, C.I foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including, constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @5% by weight of cement with all costs of labour and materials. iii) For 50 User (Pakur Variety)		25.20	Sqm	3614.00	91072.80
62	PWD(W.B)2017- Building Works- P- 261 It- 9(iv)	Supplying and Planting of different plant / trees (Supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads & lift, carriage, handling, manuring, applying pesticide and fertilizer etc. iv) Rangon hi-breed healthy plant.		120.00	Each	23.00	2760.00
63	PWD(W.B)2017- Building Works- P-261 It- 9(vi)	vi) Duranta healthy plant of big size		80.00	Each	25.00	2000.00
64	PWD(W.B)2017- Building Works- P- 109 It- 22	Supplying, fitting and fixing Stainless Steel railing consist of 38mm dia and 900mm height vertical balustrade at every two alternative steps, 50mm dia top rail, 3 (three) nos 19mm dia horizontal Strainless steel pipe and base/cover plate with Strainless Steel GRADE 304 containing 7.5% nickle (Interior Grade) Brushed/Mat finish, complete as per direction of the Engineer-in-charge. Weight of Strainless Steel railing per metre 6.5 Kg (approx)		3.5	Mtr.	5974.00	20909.00
65	PWD(W.B)2017- Building Works- P- 243 It- 9-xiv	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. ii) 4mm thick coloured / tinted / smoke glass.		8	Sqm	468.00	3744.00
66	PWD(W.B)2017- Building Works- P- 115 ,It- 3-ii	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monoliteaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria. (ii) 66mm x 70mm		48.15	Mtr.	497.00	23930.55
67	PWD(W.B)2017- Building Works- P- 125 ,It- 14-i	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monoliteaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS.4020 door testing performance criteria. In ground floor i) 32 mm thick		16.74	Sqm	2763.00	46252.62

68	Sanitary & Plumb.2017 Page-4, Item No. 3-d	Chromium plated Hand shower with Flexible Tube & fittings(Equivalent to Code No. Hsh-1937 & (Equivalent to Code No. 5037 & Model - Florentine of Jaquar or similar).).	2	Each	2390.00	4780.00
69	Sanitary & Plumb.2017 Page-4, Item No. 3-iii	(iii) Chromium plated shower arm 240 mm long (Equivalent to Code No. 536(A) & Model- Tropical / Sumthing Special of ESSCO or similar brand).	2	Each	309.00	618.00
70	PWD(W.B)2017- Building Works- P- 259 ,It- 4	Supplying and fixing grasses tiles of grass Maxican Carpet/Selection No. 1 Healthy & fresh grasses (size 1'x1' or bigger) including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth as required by Engineer-in-charge. (Rate includes supply of labour, tools & plants including materials)	40	% Sq.M.	20142	8056.80
71	PWD(W.B)2017- Building Works- P-261 It- 9(iv)	Supplying and Planting of different plant / trees ( Supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads & lift, carriage, handling, manuring, applying presticide and fertilizer etc. (iv) Raneon hi-breed healthy plant.	150	Each	23.00	3450.00
72	PWD(W.B)2017- Building Works- P-261 It- 9(vi)	(vi) Duranta healthy plant of big size	150	Each	25.00	3750.00
<b>TOTAL</b>						<b>2471194.36</b>

Add 187.657 444814.98

Total - 2916009.34

Add 2404 - 29160.09

2945169.43

~ 2945170.00

*g*  
*SACIS*

*Abisalam*  
*09/01/26*

Executive Engineer (Civil)  
Uttaran Services Department  
K. M. C.

*Santhi*  
*09/01/26*

Dy. Chief Engineer (Civil)  
Uttaran Services Department  
K. M. C.

*M. 2144*  
D. G.  
Uttaran Services Department  
K. M. C.