

OF WORK:- ESTIMATE FOR ELECTRICAL WORK OF 2 SEATED PUBLIC/COMMUNITY TOILET AT
 DU MITRA BURNING GHAT, NETAJI SUBHAS ROAD, WARD 11, PLOT NO - 429, KHATAN NO - 480,
 ZA - RAMNARAYANPUR, WITHIN THE JAYNAGAR MAJILPUR MUNICIPALITY OF WEST BENGAL.

(MODEL NO - F)
 [ASPIRATIONAL PARAMETER]

As per PWD & I & WD schedule district charges will be applicable on PWD & I & WD schedule items

No district charges will be applicable on non-schedule items

Sl No.	Item Description	Unit	Quantity	Rate	Amount
1	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light fan/call bell points with Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size 'Ph. & N' copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish. [PWD Schedule Page No-E-14 Item No-2a] Average run 5-mtr	Point	12	612.00	7344.00
2	Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3-pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish On Board (only for pay counter) [PWD Schedule Page No-E-15; 1-4a]	Point	2	67.00	134.00
3	Supplying and fixing 240V 32A Double Pole AC Type 30mA RCCB (10 complete Sets) (ISI marked) [Make- Legrand] (Cat No 411395) [Legrand Page No-92]	Nos	1	5942.00	5942.00
4	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necessary fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm) ECC [PWD Schedule Page No-E-14 Item No-1a(ii)]	mtr	12	119.00	1428.00
5	Supplying and fixing double-dose SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. a) For (2+4 way) (Make -Havells) [PWD Schedule Page No-D-9; Item No-13]	No	1	935.00	935.00
6	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection to 12 x SP MCB (Make -Havells) [PWD Schedule Page No-D-6; Item No-7]	Nos	4	168.00	672.00

	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection. [PW D Schedule Page No-D-5;Item No-6]	Nos	1	208.00	208.00
8	Supply of TMC501 conventional industrial batten (Phillips make) LED Tube model no- TMC501 P1XT-LED 22W P3241 (WB I & WD schedule P-113, I- 5;J F.22)	Nos	3	451.00	1353.00
9	Fixing only single/twin fluorescent light fitting complete with all accessories directly on wall/ceiling by screws etc., [PW D Schedule Page No-C-2;Item No-14a]	Nos	3	86.00	258.00
10	Supply & fixing bulk head light fittings with die cast aluminium housing tinted/clear glass on wall/ceiling incl S/F 9 watt LED Lamp complete set. (Make - Havells) (PW D sch - Page--D-13, I-23)	Nos	3	654.00	1962.00
11	Supply & fixing smart bright street light complete with all accessories to be fixed from the wall of building or on pole incl. making holes providing clamping arrangement & necy. GI reducer as required.S&F 40 mm GI Pipe 1.5 mtr average length & s&f necy length of 1.5 sqmm pvc insulated single core copper wire & making connections as required & mending good damages incl wall painting. (30 Watt) (Make - Bajaj) (WB I&WD sch P-111, I-[9,0,2]	Nos	1	3016.00	3016.00
12	Supply of 9" domestic metal exhaust fan 9" (225mm)SWEEP, TRANS AIR - (Make-Crompton/Havells/Bajaj) (U D & MA schedule P-14, I-5)	Nos	3	1863.00	5589.00
13	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: 22.5 cm (9") [PW D Schedule Page No-C-4;Item No-28(b)]	Nos	3	247.00	741.00
14	Fixing only louver shutter/cowl on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For 22.5 cm(9") Exhaust fan [PW D Schedule Page No-C-4;Item No-30(b)]	Nos	3	82.00	246.00
15	Supply of 240V A.C Ceiling Fan (48" sweep,1200 mm complete) (Make-Crompton for counter only) (U D & MA schedule P- 23, I-70)	Each	1	2283.00	2283.00
16	Fixing only Ceiling Fan [PW D sch P- C-3, I-21(a)]	Each	1	66.00	66.00
17	Supply & Fixing 240 V, 16/20 A Piano key type switch (Brand approved by IEC) on street metal switch board incl. S & F 100x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brain screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required. (for Hand Dryer machine) [PW D sch P- E-6, I-17(b)]	Each	2	201.00	402.00

18	300V 25A Modular type starter (brand approved by LIC with 25 A, modular switch DP/MCB (C-Curve) and 4 Module G.I. Modular type switch board with 4 Module Top Cover Plate flush in wall incl. S/P switch board and Cover Plate and making necy. Connections with PVC copper wire and earth connectivity wire etc. as per schedule [for Pump] [PWD Schedule Page No-E-19, Item No-17] (Please follow in details)	Nos	1	784.00	784.00
19	Supply and Fixing of 2 mm Polyvinyl glow sign board made of 22 SWG GI sheet box with 1"X1" aluminum channel for fixing the vinyl board after necessary cutting the letter as required & s/f LED tube light fittings along with all accessories. (16 sqft @ 495.00/sqft) (UD & MA schedule P-14, I-4)	Nos	1	7920.00	7920.00
20	Earthing installation by GI earth Spike (1830 X 20 mm) including 8SWG GI Earth Wire & GI nuts, bolts, washer etc.	Nos	1	450.00	450.00
				Total	41733.00
				Add 18% GST	7511.94
				Total With GST (A)	49244.94
Cess Amount on "A"				Cess@1%	492.45
Contingency Amount on "A"				Contingency@3%	1477.35
(Total+GST)+Rs:				Total	51214.74
				Say Rs.	51215.00
Rupees Fifty one thousand Two hundred & Fifteen only)					

Service Connection Charges as per Quotation

Say Rs. 51,215.00

P. Dey 16/06/2025

Sub-Assistant Engineer
Jaynagar-Majilpur Municipality
South 24 Parganas

Shalda
Chairman 12/6/25

Jaynagar Majilpur
Municipality

Technically Vetted Rs. 51,215.00

(Rupees Fifty one thousand two hundred and two

Hundred fifteen only.)

60
07-07-25
Junior Engineer
Electrical & Mechanical Division
SUDA

ASDA
7-7-25
ASSISTANT ENGINEER
ELECTRICAL & MECHANICAL DIVISION
SUDA

ASDA
9/7/25
Executive Engineer (E/M)
O/O the Secretary M.E. Dto.
Government of West Bengal