

NAME OF WORK:- CONSTRUCTION OF WOMEN'S TOILET COMPLEX CUM BABY CARE ROOMS UNDER 'KOLKATA 10 DIGANTA' SCHEME AT 25/3, OPPOSITE OF ASHUBABU BAZAR, PAIKPARA IN WARD NO 03 UNDER BOROUGH I

ELECTRICAL WORKS											
Sl. No	Chk Lst	Sch. Item	Description of Item	No	L	B	Ht.	Quantity	Unit	Rate	Amount Rs.
1	M5	PWD Electrical works Nov-2017 D-9/11	Supplying and fixing MCB SS enclosure with IP-20/30 protection, powder coated provision for two/four pole MCB, concealed in wall after cutting the wall & mending good the damages to original finish incl painting, connection & provision for earthing attachment ; 2 Way	1.00				1.00	Each	270.00	270.00
2	M5	PWD Electrical works Nov-2017 D-5/6	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection DP, L&T 40 A	1.00				1.00	Each	315.00	315.00
3		PWD 2017, Item No. 2b, Page No. E11	Distribution wiring in 2 x 22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1x22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no suitable size "Ph & N" copper bar incl bakelite/Perspex (wall matching color) top cover 3 mm thick and incl 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish Average run 6 mtr	6.00				6.00	Point	691.00	4146.00
4		PWD Electrical works. Nov-2014 E-11/2/c	Distribution wiring in 2 x 22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1x22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no suitable size "Ph & N" copper bar incl bakelite/Perspex (wall matching color) top cover 3 mm thick and incl 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish Average run 8 mtr	6.00				6.00	Point	849.00	5094.00
5		PWD Electrical works. Nov-2017, E-11/2/e	Distribution wiring in 2 x 22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1x22/0 3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no suitable size "Ph & N" copper bar incl bakelite/Perspex (wall matching color) top cover 3 mm thick and incl 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish Average run 10 mtr	10.00				10.00	Point	1007.00	10070.00

Handwritten signature and date: 17/2/26

Handwritten signature and date: 17/2/26

S. No	Chk Lst	Sch. Item	Description of item	No	L	B	Ht.	Quantity	Unit	Rate	Amount Rs.
6		PWD Electrical works. Nov-2017. E-11/2/e	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no suitable size "Ph & N" copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish Average run 12 mtr	14.00				14.00	Point	1165.00	16310.00
7		PWD Electrical works. Nov-2017. E-15/4/a	Distribution wiring in 1 1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish (a) on board	2.00				2.00	Point	67.00	134.00
8		PWD Electrical works. Nov-2017. E-15/4/f	Distribution wiring in 1 1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish (f) Average run 7.5 mtr	3.00				3.00	Point	775.00	2325.00
9		PWD Electrical works. Nov-2017. E-18/9/b	Supply & Fixing 240 V, 16 A, 3 pin Modular type plug socket (Brand approved by EIC) with 16A Modular type switch, without plug top on 4 Module GI Modular type switch board with top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	1.00				1.00	Each	456.00	456.00
10		PWD Electrical works. Nov-2017. E-14/1/a/ii	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necy. fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm)	100.00				100.00	MTR	119.00	11900.00
11		PWD Electrical works. Nov-2017. E-14/1/a/iii	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necy. fittings as required 2 x 56/0.3 (4 sqmm) + 1 x 36/0.3 (2.5 sqmm)	60.00				60.00	MTR	149.00	8940.00

amamm
AEQ
17/2/26

AEQ
17/2/26



S. No	Chk Lst	Sch. Item	Description of item	No	L	B	Ht.	Quantity	Unit	Rate	Amount Rs.
12		PWD Electrical works. Nov-2017. E-14/1/a/i	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make) incl. necy. fittings as required 2 x 22/0.3 (1.5 sqmm) + 1 x 22/0.3 (1.5 sqmm)	25.00				25.00	RM	102.00	2550.00
13		PWD Electrical works. Nov-2017. D-10/13	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. L&T make 2+6 way, Enclosure (LTSD08N)	1.00				1.00	NO.	1202.00	1202.00
14		PWD Electrical works. Nov-2017. D-6/7	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection. L&T make, DP, 6-32 Amp	1.00				1.00	NO	478.00	478.00
15		PWD Electrical works. Nov-2017. D-6/7	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection. L&T make, SP, 6-32 A	6.00				6.00	NO	160.00	960.00
16		PWD Electrical works. Nov-2014. F-4/7 a	Supplying and fixing compression type gland complete with brass gland, brass ring & rubber ring for dust & moisture-proof entry of XLPE/PVC armoured cables as below : For 2 core upto 10 sqmm	2.00				2.00	Each	115.00	230.00
17		PWD Electrical works. Nov-2014. F-5/8b	Finishing the end of following XLPE/PVC armoured cables by crimping method incl. supplying and fixing solderless socket (Dowels make), tapes, anticorrosive paste & jointing materials : 2 core 10 sqmm cable	2.00				2.00	Each	34.00	68.00
18		PWD Electrical works. Nov-2014. F-1/2a	Laying of cable upto 2 core 25 sqmm on wall/surface incl. S & F MS saddles with earthing attachment in 10 SWG GI (Hot Dip) Wire, making holes etc. as necy. mending good damages and painting	45.00				45.00	RM	57.00	2565.00
19		UDMA, E&M, 2018, 11/1/c/(i)	Supplying of 1.1 KV. Grade PVC insulated Conductor of following cables (make: Polycab/Gloster/Havells): 2 core 10 sq mm.	45.00				45.00	RM	101.00	4545.00
20		KMC Fair Rate 2018	Supply of street lighting LED luminaire 70 w to 80 w having top opening cover make Crompton, Philips, Havells	2.00				2.00	Each	9700.00	19400.00
21		PWD Electrical works. Nov-2017. D-14/32/a	Supply & Fixing louver shutter on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For Al 23 cm Exhaust fan (9")	6.00				6.00	Each	152.00	912.00
22		PWD Electrical works. Nov-2017. K-2/67	Two way Circular Box & cover	8.00				8.00	Each	15.00	120.00
23		PWD Electrical works. Nov-2017. K-2/69	3 way Ceiling Rose/Batten Holder	10.00				10.00	Each	18.30	183.00
24		UDMA, E&M, 2018, 15/15/a	Supply & delivery of the following 50 Hz, AC, Direct on Line Starter of continuous duty in sheet steel enclosure (make L&T/ABB/SCHNEIDER): 2 HP Single Phase (Max. Relay range 10.5-17.5 Amp)	2.00				2.00	Each	903.00	1806.00

Signature
17/2/26

Signature
AEC
17/2/26

No	Chk Lst	Sch. Item	Description of item	No	L	B	Ht.	Quantity	Unit	Rate	Amount Rs.
25		PWD IRRIGATION MECH & ELEC2022 PAGE-127 ITEM 5.3 L2	S&F ACRYLIC LETTER SCRIPTED IN ENGLISH/ BENGALI SIZE AND MATTER OF LETTER AS PER APPROVED DRAWING BY EIC FRONT SIDE OF THE LETTER TO BE MADE 6 MM THICK IMPORTED (WHITE-0 40) UV STABILIZED EXCELLENT TO SELF DISPLAY. MAKE ACAST, MIITSUBISHI ALL LETTER WILL BE RAISED MINIMUM 2" TO BE FIXED BY SPECIAL TYPE OF SOLUTION.(TOTAL SQ M OF EACH LETTER IS TO BE MEASURED BASED ON ITS FRONT SURFACE AREA.	1.00	2.00	1.00		2.00	SQ MTR	11448.00	22896.00
26		PWD Electrical works. Nov-2017 H-5/5	Supplying & Fixing GI waterproof type looping cable box size 200x150x100 mm deep having 4 mm thick comprising of one 250 V 15 A kit-kat fuse unit, one NL on porcelain insulator, one compression type brass cable gland for upto 2- core 16 sqmm PVC/A cable and having lined with rubber gasketed GI top cover with brass machine screws etc., earthing terminal with lug, on steel tubular pole near base, including S&F 40x6 mm thick, MS clamps with bolts, nuts etc. including painting with anticorrosive paint	2.00				2.00	NO	458.00	916.00
27		PWD Electrical works Nov-2017 H-5/3	Fixing outdoor type fluorescent/SV/MV light fitting on pole including S&F 40 mm dia x 1.68 mts. long GI Pipe (ISI-Medium) bracket with 40 mmx10 mm thick, MS clamp etc. and providing wiring with 2x1/1.40 PVC insulated & sheathed wire (single core) partly in GI conduit & partly through above bracket from OH line to the fitting, without control switch, incl. making connections and painting	2.00				2.00	NO	1400.00	2800.00
28		PWD 2017 Item No. 7/a Page No. C-1	Fixing only starters (for motor control) on flat iron frame / angle iron frame on wall, Star-Delta starter for motor (above 5 HP upto 15 HP), On angle iron frame (for higher rating)	2.00				2.00	Each	215.00	430.00
29		PWD Electrical works. Nov-2017 G-1/2e	Earthing with 80 mm dia GI pipe (TATA-Medium)x 3.0 Mts. long and 1 No. 65 mm x 8 mm galvanized (Hot Dip) steel strip (4 Mts. long), 20 mm dia x 125 mm long galvanized bolt, double nuts, double washers including finishing both ends by making holes etc. and S & F 80 mm dia GI pipe (ISI-Medium) protection (3 Mts. long) to be filled with bitumen partly under the ground level and partly above ground level to an average depth of 3.65 Mts	4.00				4.00	SET	5349.00	21396.00
30		PWD Electrical works. Nov-2014 G-2/3A	Extra for providing masonry enclosure on the top of the earth electrode of overall size 86.36 cm x 86.36 cm x 46 cm deep (below Ground level) complete with cemented brick work(1.6) of 25 cm width duly plastered with cement mortar (inside) CI hinged inspection cover of size 36.56 cm x 35.56 cm with locking arrangement, GI reducer including drilling of 46 nos 12 mm dia holes on the GI pipe	4.00				4.00	SET	915.00	3660.00
31		PWD Electrical works. Nov-2014 G-1/1/a	Excavation of soil for installation of Earth Electrode and filling & ramming. For Soft Soil	4.00				4.00	Cu mtr.	215.00	860.00
32		PWD Electrical works. Nov-2017 G-2/4B	Supplying & fixing earth busbar of galvanized (Hot Dip) MS flat 40 mm x 6 mm on wall having clearance of 6 mm from wall including providing drilled holes on the busbar complete with GI bolts, nuts, washers, spacing insulators etc. as required	10.00				10.00	MTR	194.00	1940.00
33		PWD Electrical works. Nov-2014 G-2/5 A.ii	Connecting the equipments to earth busbar including S & F GI (Hot Dip) wire of size as below on wall/floor with staples buried inside wall/floor as required and making connection to equipments with bolts, nuts, washers, cable lugs etc. as required and mending good damages. Solid GI wire, No. 6 SWG	30.00				30.00	MTR	13.00	390.00

Amrta
12/2/26

AFC
13/2/26

Sl. No	Chk Lst	Sch. Item	Description of item	No	L	B	Ht.	Quantity	Unit	Rate	Amount Rs.
34		UDMA Schedule 2018/Pg-14/6	Supply and delivery of 230V,50Hz Heavy duty Metal 9"exhaust fan.	6.00				6.00	Each	1863.00	11178.00
35	M5	UDMA Schedule 2018/Pg-23/71/a	Supply and delivery of Wall fan 16" Sweep metal blade (a) Crompton Make	4.00				4.00	Each	2946.00	11784.00
36	M5	PWD Electrical works. Nov-2017.c-4/28/a	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter (a) 23 cm (9")	3.00				6.00	Each	247.00	1482.00
37	M4	PWD Electrical works. Nov-2017.c-4/30/a	Fixing only louver shutter/cowl on wall with necy. bolts & nuts (6 mm dia x 62 mm long) (a) for 23 cm (9") Exhaust Fan	3.00				6.00	Each	82.00	492.00
38	M4	PWD Electrical works. Nov-2017.c-4/29	Fixing only cabin fan on wall/ceiling by S&F rag bolts, nuts & washers (6 mm dia x 62 mm long) or as reqd. incl. S&F 24/0 20 PVC insulated flexible copper wire 0.5 mt. length	4.00				4.00	Each	92.00	368.00
39	A8	KMC Passed File rate	9-15 W round type LED luminaires Make Philips/Havells/Wipro	24.00				24.00	Each	1112.00	26688.00
40	A8	PWD IRRIGATION MECH & ELEC2022 PAGE-127 ITEM 5.3 L3	S&F LED LAMP INCLD. BEST QUALITY LED LIGHTING TO BE FIXED BY PROPER ARRANGEMENT WITH COMPLETE CONNECTION. (1 MODULE CONTAIN 3 NOS LED, 0.5 W EACH)	416.00				416.00	MODULE	53.00	22048.00
TOTAL											224307.00
Add 18% G.S.T= Rs.											40375.26
Total											264682.26
Add 1% labour welfare cess											2646.82
Gross Total											267329.00

Signature
17/02/26

Signature
17/02/26

Signature
17.02.26

Executive Engineer (Civil)
Uttaran Services Department
K. M. C.

Signature
17/02/26
Dy. Chief Engineer (Civil)
Uttaran Services Department
K. M. C.

Signature
D. G.
Uttaran Services Department
K. M. C.