





Construction of Public Toilet(PT) at Mata Mandir (New Settlement) at Ward no-18 Under Kharagpur Municipality Model No - C Civil Works Toilet Seat- 2 Nos & Urinal- 3 Nos Annexure- C , NON SCHEDULE ITEMS					
SL.NO	Item Description & Item No.	Quantity	Rate	Unit	Amount
1	Non Shedule Item Sl. No. 91-106 ( Order as per SUDA) standard plastic dustbin (12lits)	2	350	Each	700.00
2	Sinage APC based & Reflective vinyl	5	3776	each	18880.00
3	Supplying and fixing sinage with fixing stand post for public toilet for visible to passersby	5	1000	Each	5000.00
4	Installation of Sinage	1	2071	each	2071.00
5	Air freshner(pack of 4nos)	8	216	Each	1728.00
6	Air freshner (Napthaline 250 gm)	5	210	Each	1050.00
7	Supplying paper Napkin	5	50	Each	250.00
8	Supplying Sanitary Napkin ( Whisper or similar make 50 pcs )	4	520	Each	2080.00
9	Harpic (blue 500 ml)	4	300	Each	1200.00
10	Harpic (Red 500 ml)	4	150	Each	600.00
11	Gala double lip floor wiper	4	350	Each	1400.00
12	Colin glass or surface cleaner	2	200	Lit	400.00
13	Muriatic Acid	2	145	Lit	290.00
14	Bleaching powder	4	120	Kg	480.00
15	Dettol ,lifeboy or similar make liquid soap	8	140	Lit	1120.00
16	Rubber hand gloves	6	80	Pair	480.00
17	Double side plastic brush	6	125	Each	750.00
18	Plastic Broom	4	170	Each	680.00
19	SMS/any otherICT based feedback system ( With number displayed on which SMS has to be sent )	1	5000	each	5000.00
20	Mini Tulu Pump	1	4000	each	4000.00
21	supplying roaster /register for keeping accoount of regular cleanig	3	200	Each	600.00
22	Lettering on Toilet Wall for display of name and contact details of ULB ward number and name of maintanance authority , saniinspector, etc.	1	1000	each	1000.00
			<b>TOTAL</b>	Rs.	49759.00


  
 Municipal Civil Engineer  
 HFA-(U) CLTC  
 Kharagpur Municipality


  
 Assistant Engineer  
 Kharagpur Municipality


  
 Executive Officer  
 Kharagpur Municipality

  
 Chairperson  
 Kharagpur Municipality

*Rate are taken from approved rates of non Schedule Items approved by SUDA vide memo no- 924/2021/7746 on dt-05/03/21.*

  
 Junior Engineer  
 West Midnapore Division  
 M. E. Directorate  
 Govt. of West Bंगा.

MAY BE VETTED  
  
 Assistant Engineer  
 West Midnapore Division  
 M. E. Directorate  
 Govt. of West Bengal

VETTED  
  
 Executive Engineer,  
 West Midnapore Division  
 M.E. Directorate  
 Govt. of West Bengal

**NAME OF WORK:- ESTIMATE FOR ELECTRICAL WORK OF 2 SEATED PUBLIC TOILET AT Mata Mandir (New Settlement), WARD NO. - 18 UNDER KHARAGPUR MUNICIPALITY OF WEST BENGAL (MODEL NO - C) [ASPIRATIONAL PARAMETER]**

\* As per PWD & I & WD schedule district charges will be applicable on PWD & I & WD schedule items

\* No district charges will be applicable on non-schedule items

SI No.	Iteam Description	Unit	Quantity	Rate	Adding district charges	Final rate	Amount
1	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire(Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switchfixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size "Ph & N" copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish. [PWD Schedule Page No-E-14 Iteam No-2a]	Point	12	612.00	18.36	630.36	7564.32
	Average run 5 mtr						
2	Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish <b>On Board (only for pay counter)</b> [PWD Schedule Page No-E-15; I-4a]	Point	2	67.00	2.01	69.01	138.02
3	Supplying and fixing 240V 32A Double Pole AC Type 30mA RCCB.(Complete Set) (ISI marked) [Make- Legrand] (Cat No 4113/95) [ Legrand Page No-92 ]	Nos	1	5942.00	0.00	5942.00	5942.00
4	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ) incl. necy. fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm) ECC [PWD Schedule Page No-E-14 Iteam No-1a(ii)]	mtr	12	119.00	3.57	122.57	1470.84

5	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. <b>a) For (2+4 way) (Make -Havells)</b> <b>[PWD Schedule Page No-D-9;Iteam No-13]</b>	No	1	935.00	28.05	963.05	963.05
6	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection 6-32A SP MCB (Make -Havells) <b>[PWD Schedule Page No-D-6;Iteam No-7]</b>	Nos	4	168.00	5.04	173.04	692.16
7	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection. 40A DP MCB Isolator (Make -Havells) <b>[PWD Schedule Page No-D-5;Iteam No-6]</b>	Nos	1	208.00	6.24	214.24	214.24
8	Supply of TMC501 conventional industrial batten (Philips make) LED Tube,model no- TMC501 P1xT-LED 22W P3241 <b>(WB I &amp; WD schedule P-113, I- 5:3 F.22)</b>	Nos	3	451.00	9.02	460.02	1380.06
9	Fixing only single/twin fluroscnt light fitting complete with all accessories directly on wall/ceiling by screws etc.. <b>[PWD Schedule Page No-C-2;Iteam No-14a]</b>	Nos	3	86.00	2.58	88.58	265.74
10	Supply & fixing Bulk head light fittings with die cast aluminium housing frosted/clear glass on wall/ceiling incl S/F 9 watt LED Lamp complete set. [Make - Havells] <b>(PWD sch - Page--D-13, I-23)</b>	Nos	3	579+ District Charges+75=	92.37	671.37	2014.11
11	Supply & fixing smart bright street light complete with all accessories to be fixed from the wall of building or on pole incl. making holes /providing clamping arrangement & necy. GI reducer as required.S&F 40 mm GI Pipe 1.5 mtr average length & s&f necy length of 1.5 sqmm pvc insulated single core copper wire & making connections as required & mending good damages incl wall paingting. (30 Watt) (Make - Bajaj) <b>[WB I&amp;WD sch P-111, I-f.9.0.2]</b>	Nos	1	3016.00	60.32	3076.32	3076.32
12	Supply of 9" domestic metal exhaust fan 9" (225mm)SWEEP. TRANS AIR - <b>( Make-Crompton/Havells/Bajaj)</b> <b>(UD &amp; MA schedule P-14, I-5))</b>	Nos	3	1863.00	0.00	1863.00	5589
13	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: 22.5 cm ( 9" ) <b>[PWD Schedule Page No-C-4;Iteam No-28(b)]</b>	Nos	3	247.00	7.41	254.41	763.23
14	Fixing only louver shutter/cowl on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For 22.5 cm(9") Exhaust fan <b>[PWD Schedule Page No-C-4;Iteam No-30(b)]</b>	Nos	3	82.00	2.46	84.46	253.38
15	Supply of 240V A.C Ceiling fan ( 48 sweep,1200 mm complete) <b>[Make -Crompton ] for ceasing only]</b>	Each	1	2283.00	0.00	2283.00	2283

16	Fixing only Ceiling Fan [PWD sch P- C-3, I-21(a)]	Each	1	66.00	1.98	67.98	67.98
17	Supply & Fixing 240 V, 16/20 A Piano key type switch (Brand approved by EIC) on sheet metal switch board incl. S & F 100x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brass screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required. (For Hand Dryer machine) [PWD sch P- E-6, I-17(b)]	Each	2	201.00	6.03	207.03	414.06
18	S/F 240V 25A Modular type starter (brand approved by EIC)with 25 A. Modular switch DP MCB (C-Curve)and 4 Module G.I. Moduar type switch board with 4 Module Top Cover Plate flushed in wall incl. S/F switch board and Cover Plate and making necy. Connections with PVC Copper wire and earth connectivity wire etc. as per schedule [for Pump] [PWD Schedule Page No-E-19, Item No-17] (Please follow in details)	Nos	1	784.00	23.52	807.52	807.52
19	Supply and Fixing of 2 mm Polyvinyl glow sign board made of 22 SWG GI sheet box with 1"X1" aluminum channel for fixing the vinyl board after necessary cutting the letter as required & s/f LED tube light fittings along with all accessories. (16 sqft @495.00/sqft) (UD & MA schedule P-14, I-4)	Nos	1	7920.00	0.00	7920.00	7920
20	Earthing installation by GI earth Spike (1830 X 20 mm) including 8SWG GI EarthWire & GI nuts, bolts, washer etc.	Nos	1	450.00	0.00	450.00	450
				Total			42269.03
				Add 18% GST			7608.43
				Total With GST (A)			49877.46
				<u>Cess@1%</u>			498.77
				<u>total</u>			50376.23
	Contingency Amount on "A"			<u>Contingency@3%</u>			1496.32
	(Total+GST)=Rs:			<b>Total</b>			51872.55
				<b>Say Rs.</b>			51873.00
<b>Service Connection Charges as per Quotation</b>							

Sub-Assistant Engineer(E) Kharagpur Municipality  
 Municipal Civil Engineer Kharagpur Municipality  
 Assistant Engineer Kharagpur Municipality  
 Executive officer Kharagpur Municipality  
 Chairperson Kharagpur Municipality  
 Sub-Assistant Engineer (Elect.) Kharagpur Municipality  
 Municipal Civil Engineer Kharagpur Municipality  
 HFA-(U) CLTC Kharagpur Municipality  
 Assistant-Engineer Kharagpur Municipality  
 Executive Officer Kharagpur Municipality  
 Chairperson Kharagpur Municipality  
 Technically Votted Rs. 51,873.00  
 (Rupees Fifty one thousand eight hundred and seventy three only.)  
 09-09-25  
 Junior Engineer Electrical & Mechanical Division SUDA  
 ASSISTANT ENGINEER ELECTRICAL & MECHANICAL DIVISION SUDA  
 Executive Engineer (E/M) O/O the Secretary M.E. Dto. Government of West Bengal

**Construction of Public Toilet (PT) at Mata Mandir (New Settlement) at Ward no-18 Under Kharagpur**

**Municipality Model No - F Civil Works**

**Toilet Seat- 2 Nos & Urinal- 3 Nos Annexure- A**

**( p.w.d.s.o.r.w.e.f.1.11.2017 including 11th corrigenda on dt.14.02.2020)**

<b>SL. NO</b>	<b>Ref</b>	<b>Item Description &amp; Item No.</b>	<b>Quantity</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1	PWD Building Works schedule Page - 1, Item -2.a	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. PWD COLM. $2 \times 2 \times 1.20 \times 1.20 \times 1.00 = 5.76 \text{ M}^3$ partition wall $1 \times 1.00 \times 0.375 \times 0.150 = 0.056 \text{ m}^3$	5.816	119.27	Cu.m	693.67
2	PWD Building Works schedule, Page - 1, Item -3.a	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). (a) With earth obtained from excavation of foundation. $5.816 \times 1/5 = 1.16 \text{ m}^3$	1.160	77.54	%um	89.95
3	PWD Building Works schedule, Page - 2, Item -4.a	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) $1 \times 4.850 \times 2.8250 \times 0.325 = 4.453 \text{ m}^3$	4.453	599.61	Cum	2670.06
4	PWD Building Works schedule, Page- 14, Item - 1 ( Corri. Page-01, Date-04-06-2018)	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. $2 \times 2 \times 1.20 \times 1.20 = 5.76 \text{ m}^2$ $2 \times 2.50 \times 0.375 = 1.88 \text{ m}^2$ $1 \times 1.00 \times 0.375 = 0.375 \text{ m}^2$ $1 \times 4.85 \times 2.825 = 13.70 \text{ m}^2$	21.72	344.00	Sqm	7471.68
5	PWD Building Works schedule, p-26 Item 10 a	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes. a) Pakur Variety /Chandil Variety $2 \times 2 \times 1.20 \times 1.20 \times 0.150 = 0.864 \text{ m}^3$ $2 \times 2 \times (1.20 \times 1.20) + (0.250 \times 0.250) / 2 \times 0.150 = 0.451 \text{ m}^3$ $2 \times 2 \times 0.250 \times 0.250 \times 3.250 = 0.813 \text{ m}^3$ $2 \times 4.60 \times 0.250 \times 0.250 = 0.575 \text{ m}^3$ $3 \times 2.325 \times 0.250 \times 0.250 = 0.436 \text{ m}^3$ $3 \times 2.325 \times 0.250 \times 0.150 = 0.262 \text{ m}^3$ $2 \times 2.325 \times 0.250 \times 0.150 = 0.174 \text{ m}^3$ $1 \times 4.85 \times 2.8250 \times 0.125 = 1.970 \text{ m}^3$	5.545	5618.05	Cum	31152.09
6	PWD Building Works schedule, Page -23, Item - B.1.a, ( Corri. Page-09, Date-04-06-2018)	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering In ground floor and foundation. (a) 1:3:6 proportion $2 \times 2 \times 1.20 \times 1.20 \times 0.10 = 0.576 \text{ m}^3$ $2 \times 2.50 \times 0.375 \times 0.100 = 0.188 \text{ m}^3$ $2 \times 1.50 \times 1.00 \times 0.100 = 0.300 \text{ m}^3$ $1 \times 4.85 \times 2.8250 \times 0.100 = 1.370 \text{ m}^3$	2.434	5078.51	m3	12361.09

7	PWD Building Works schedule, Page -47, Item -1	25mm. thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacturer's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2 nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately).( Chequering not required over concrete or painted surface). [Note: - Waterproofing as per item 9, polymer based paint as per item 8 (a) of subhead C of Section (C). $2 \times 4.85 \times 0.250 = 3.69 \text{ m}^2$ $3 \times 2.8250 \times 0.250 = 2.11 \text{ m}^2$	5.80	195.00	Sqm	1131.00
8	Page -16, Item-16, cori page -3, date -04.06.2018	125 mm brick work with 1st class bricks in cement mortar ( 1:4) in ground floor. $5 \times 1.20 \times 3.00 = 18.00 \text{ m}^2$ $3 \times 1.00 \times 3.00 = 9.00 \text{ m}^2$	15.00	705.00	Sq.M.	10575.00
9	PWD Building Works schedule, Page -47, Item-3	Supplying and laying polythine sheet ( 150 gm/sq.m ) over damp proof course or below flooring or roof terracing or foundation or foundation trenches.	37.87	24.00	Sq.M.	908.88
10	PWD Building Works schedule, Page -42, Item- 36.f	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (f) 25 mm to 30 mm shuttering without staging in foundation $2 \times 2 \times 4.85 \times 0.250 = 4.85 \text{ m}^2$ $2 \times 2 \times 2.825 \times 0.25 = 2.85 \text{ m}^2$ $2 \times 2 \times 4 \times 1.20 \times 0.150 = 2.88 \text{ m}^2$	10.58	203.00	Sqm	2147.74
11	PWD Building Works schedule, Page -42, Item- 36.a	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. $1 \times 4.85 \times 2.8250 = 13.70 \text{ m}^2$ $2( 4.85 + 2.825 ) \times 0.125 = 1.209 \text{ m}^2$ $4(.30+.025 ) \times 3.00 = 6.60 \text{ m}^2$ $2 \times 2 \times 4.85 \times 0.1250 = 2.46 \text{ m}^2$ $2 \times 2 \times 2.825 \times 0.125 = 1.41 \text{ m}^2$	25.38	321.00	Sqm	8146.98
13	PWD Building Works schedule, Page - 43, Item - 40.a.i.1( Corri. 10th Page-01, Date-23-01-2020)	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m. (i) Tor steel/Mild Steel , JSPL/SWAYN/ELETRO/STEEL vol of conc. $3.853 \times 1.20 \% = 0.046 \text{ m}^3 \times 35.315 \text{ c.ft} = 1.624 \text{ c.ft} \times 225 \text{ kg} = 365.40 \text{ kg} = 0.365 \text{ MT}$	0.522	55196.64	M.T.	28812.65
14	PWD Building Works schedule, Page -106, Item- .18	Collapsible gate with 40 mm x 10 mm x 6 mm Tee as top and bottom guide rail , 20 mm x 10 mm x 2 mm vertical channels 100 mm apart in full stretched position 20m x 5 mm MS flats as collapsible bracings properly reveted and washered including 38 mm steel roller including locking arrangements , fitted and fixed in position with lugs set in cement concrete including cutting necessary hives chasing etc in walls , floors etc and making good all damages . $2 \times 1.00 \times 2.10 = 4.20 \text{ m}^2$	4.83	3402.00	Sqm	16431.66

15	PWD Building Works schedule, Page -15, Item-7.a	Brick work with 1st class bricks in cement mortar (1:4) (a) Foundation and plinth ground floor $2 \times 4.85 \times 0.250 \times 0.600 = 1.455 \text{ m}^3$ $3 \times 2.8250 \times 0.250 \times 0.600 = 1.271 \text{ m}^3$ $2 \times 2.50 \times 0.250 \times 0.600 = 0.750 \text{ M}^3$ $2 \times 1.00 \times 0.500 \times 0.300 = 0.300 \text{ M}^3$	3.776	5408.00	Cu.m	20420.61
16	PWD Building Works schedule, Page -15, Item-7.b	Brick work with 1st class bricks in cement mortar (1:4) (b) superstructure ground floor $2 \times 4.85 \times 0.250 \times 3.00 = 7.275 \text{ m}^3$ $3 \times 2.825 \times 0.25 \times 3.00 = 6.356 \text{ M}^3$	9.00	5631.00	Cu.m	50679.00
17	PWD Building Works schedule, P-192, It-1	Labour for Chipping of concrete surface before taking up Plastering work.	13.70	21.00	Sqm	287.70
18	PWD Building Works schedule, P-189 It- No. 1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster $2(4.85 + 2.8250) \times 3.75 = 57.56 \text{ m}^2$ $2(4.85 + 2.8250) \times 3.00 = 46.05 \text{ m}^2$ $1 \times 2 \times 2.325 \times 3.00 = 13.95 \text{ m}^2$ $2 \times 2 \times 1.60 \times 3.00 = 19.200 \text{ m}^2$	136.56	134.00	Sqm	18299.04
19	PWD Building Works schedule, P-189 It- No. 1 (ii)©	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (c) 10 mm thick plaster $4.85 \times 2.8500 = 13.70 \text{ m}^2$	13.70	122.00	Sqm	1671.40
20	PWD Building Works schedule, P-192 It- No. 15	Neat cement punning about 1.5 mm thick in wall ,dado, window sills, floors etc . Note cement 0.152 m <sup>3</sup> /100 m <sup>2</sup> $2(4.850 + 2.825) \times 0.75 = 11.51 \text{ m}^2$	11.51	34.00	Sq.m	391.34
21	PWD Building Works schedule, P-115, It - 3 (i)	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria.. (i) 66mm x 90mm $2(2 \times 2.10 + 0.75) = 9.90 \text{ M}$	9.90	497.00	Mtr	4920.30
22	P-125, It- 14(ii)	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. ii) 25 mm thick $2 \times 2.10 \times 0.75 = 3.15 \text{ m}^2$	3.15	2581.00	Sqm	8130.15
23	PWD Building Works schedule, P-144, It No. 26 (vii)	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws . (vii) 225mm long x 10mm dia. bolt.	5.00	84.00	Each	420.00
24	PWD Building Works schedule, P-140, It No. -5 (viii)	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (viii) 100mm X 75mm X 3.50mm	15.00	66.00	Each	990.00
25	PWD Building Works schedule, Page -146 . Item no-31,(i)	Anodised aluminium decorative handle (hexagonal / fluted) of approed quality fitted and fixed complete. (i) 150mm plate x 10mm dia rod x 12mm hexagonal/fluted.	8.00	87.00	Each	696.00

26	PWD Building Works schedule, Page -141 . Item no-10 b)	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with concrete bolt and round fitting. .b)250mm long.	2.00	159.00	Each	318.00
27	PWD Building Works schedule, Page -74 , Item no-46(i)	Supplying and laying chequered tiles of any shade and of approved quality with (1:1.5:3) cement concrete laid in pannels or patterns as directed in pavement ,footpath etc including necessary underlay 25 mm thick (avg)cement mortar (1:3) complete in all respect with all labour and materials. ( Using cement slurry @4.4kg/sq.m at back side and @2.4 kg/sq.m for joint filling ). (i). 25 mm thick 1 x 2.00 x1.00 = 2.00 m2 1 x 1.00 x 2.125 = 2.13 m2	4.13	455.00	sq.m	1879.15
28	PWD Building Works schedule, PWD, P- 198, I - 5	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) In Ground Floor 136.56 + 13..70 = 150.26 M2	150.26	122.00	Sqm	18331.72
29	PWD Building Works schedule, Page -74 , Item no-46(i).	Applying interior grade Acrylic Primer of approved quality and brand on plastered and concrete surface old or new surface to receive Distemper Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the E-I-C ( Ground Floor ) ( b ) Two Coats 44.63 +19.20 +13.90 -13.7 0 = 66.03 M2	32.00	44.20	m2	1414.40
30	PWD Building Works schedule, Page -196 , Item no- 9(b)	Dry Destempering interial walls or ceiling including cleaning, washing, smoothening surface (b) two coats .	66.06	49.00	m2	3236.94
31	PWD Building Works schedule, Page -196 , Item no- 8(b)	Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Decorative Textured (Martt Finish) or Smooth Finish Acrylic exterior emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC in Ground Floor (b) two coats.	57.70	45.10	m2	2602.27
32	PWD Building Works schedule, Page -197 , Item no- 17(a)	Protective and Decorative Acrylic Exterior emulsion paint of approved quality, as per manufacturer's specification and as per dirction of EIC to be applied overf Acrylic primer as required. The rate includes cost of materials, labour, scaffolding and all incidental charges but excluding the cost of primer in ground floor (two coats)(a) normal acrylic emulsion. 79.69+18.00 +36.00 = 136.69 m2	57.70	67.00	m2	3865.90
33	PWD Building Works schedule, Page -200 . Item no- 1 (b)	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	6.35	38.00	Sqm	241.30
34	PWD Building Works schedule, Page -200 . Item no- 2(A)(a)(iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : Page - 200 . Item no- 1 (b) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	6.35	81.00	Sqm	514.35
35	PWD Building Works schedule, P-104 Item-13 A (i) (3rd Corrigendam Page No 91)	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr. 64 x 0.600 x 0.600 = 1.44 m2 = 1.44 m2 x 10..00 kg = 14.40 kg = 0.144 qtl	0.144	9888.00	Qntl	1423.87

36	PWD Building Works schedule, P/200 Item-1(a)	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. PWD Building Works schedule, P/200 Item-1(a)	5.64	29.00	Sqm	163.56
37	PWD Building Works schedule, P-200 Item-2(b)(iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white)	5.64	79.00	Sqm	445.56
38	PWD Building Works schedule, Page-66 Item-36 (A)	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring Pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrr]e) I (I) With application slurry @1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White Floor 4.85 x 2.825 = 13.70 m2	13.70	1680.00	Sqm	23016.00
39	PWD Building Works schedule, page-64, Item:35.(B.) (b).(ii)	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. B) Wall Area of each tile above 0.09 Sq.m ii) Other than Coloured decorative including white $2(4.85 + 2.8250) \times 2.10 = 36.84 \text{ m}^2$ $1 \times 2 \times 2.325 \times 2.10 = 9.77 \text{ m}^2$ $2 \times 2 \times 1.60 \times 2.10 = 13.44 \text{ m}^2$	45.00	1029.00	Sqm	46305.00
40	PWD Building Works schedule, PWD, P-233, I-1(h) i	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In- Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film I) Natural white h) Louvered window. i) Top, bottom and side member.	6.50	183.00	M	1189.50
41		ii) Louvered Section.	7.20	658.00	M	4737.60
42		iii) Cleat angle ( Non-anodized).	6.48	263.00	M	1704.24
43	Building Works schedule, P-243, I-9	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. iv) 5mm thick coloured / tinted / smoke glass.	1.08	585.00	Sq.M.	631.80

44	PWD Building Works schedule, P-268, It-17€	Painting block letters or digits in Black Japan or any approved paint as per direction. e) Size above 7.5 cm. and upto 10 cm.	450.00	12.00	Each	5400.00
45	PWD Building Works schedule, Page -261, It- 9 (i)	Supplying and planting of different plants / trees (supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads and lifts, carriage, handling, manuring applying pesticide and fertilizer etc. i) Furcaria Veriegated 10 to 12 leaves in height 20-30 cm in earthen pot of size 25 cm	10.00	162.00	Each	1620.00
46	PWD Building Works schedule, Page -261, It- 9 (x)	x) Ficus blakii (F. Vivicon) well branched (Bushy) of height 120cm - 135 cm in earthen pot of size 30cm.	3.00	187.00	Each	561.00
47	PWD Building Works schedule, Page -261, It- 9 (xxvi)	xxvi) Areca Palm 4 - 5 suckers of height 90 cm to 105 cm in earthen pots of size 25 cm. PWD Building Works schedule, Page -261, It- 9 (xxvi)	3.00	127.00	Each	381.00
		<b><u>SANITARY AND PLUMBING WORKS</u></b>				0.00
48	PWD S&P Schedule, page-79, item no -3 (a)	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. a) With 'P' trap (with vent)	2.00	3104.00	Each	6208.00
49	PWD S&P Schedule, page-81, item no 10.b.i	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete .(b) Anglo Indian (i) Plastic (hallow type) White	2.00	371.00	Each	742.00
50	PWD S&P Schedule, page.80,item no-6/(ii)	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (ii) 470 mm X 280 mm X 340 mm	2.00	945.00	Each	1890.00
51	PWD S&P Schedule, page.80,item no-7/(i)	Supplying fitting and fixing squatting plate with integrated flushing in white vitreous set in cement concrete (6:3:1) with jhama chips complete. ( Payment of concrete will be paid seperately ) ( I ) 450 mm x 350 mm	1.00	881.00	each	881.00
52	PWD S&P Schedule, Page No.-36 Item No.-2,	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete,C.I. brackets including two coats of painting to bracket etc	2.00	1015.00	Nos	2030.00
53	PWD S&P Schedule, Page no 81. Item no. 11(i)	Supplying,fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete. i) Polythene Flush Pipe	2.00	155.00	Each	310.00
54	PWD S&P Schedule, S.P.81,item-12/a	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. (a) C.P. urinal flush pipe fittings range of one	2.00	414.00	Each	828.00
55	PWD S&P Schedule, P-41, It 2 (ii)	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., mending good all damages and painting the brackets with two coats of approved paint. (ii) 550 mm X 400 mm size	2.00	2208.00	Each	4416.00
56	PWD S&P Schedule, P-41, It 3	Supplying fitting and fixing pedestal of approved make for wash basin ( White )	2.00	1497.00	Each	2994.00
57	PWD S&P Schedule, Page No.-43 Item No.-9-iii	Supplying,fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia., (iii) 600 mm long	5.00	107.00	Each	535.00

58	PWD S&P Schedule, Page No.-43 Item No. 10-iv	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iv) 1050 mm long each	2.00	91.00	Each	182.00
59	PWD S&P Schedule, Page No.-3 Item No.- 3 f,	(f) Hand Shower(Health Faucet) with 1mtr Fexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	0.00	1251.00	Each	0.00
60	PWD S&P Schedule, Page No.-6 Item No.-7-a-i	(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	5.00	539.00	Each	2695.00
61	PWD S&P Schedule, Page No.-6 Item No.-7-b-i	(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	2.00	493.00	Each	986.00
62	PWD S&P Schedule, Page No.-6 Item No.-7-d-i,	Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand).	4.00	815.00	Each	3260.00
63	(P. No. - 45, Item. No. - 19(a)i, Pwd Sanitary Plumbing Schedule 2017)	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	2.00	555.00	Each	1110.00
64	Page No.-12 Item No.-19-i(a), PWD,VOL-II , 2017-18	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads,fitting, fixing etc. complete in all respect including cost of all necessary fittings as required,jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will be made seperately) (a) For Exposed Work PVC Pipes, 25 mm	15.00	177.00	Mtr	2655.00
65	Page No.-12 Item No.-19-i(a), PWD,VOL-II , 2017-18	(a) (a) For Exposed Work PVC Pipes, 15 mm	10.00	101.00	Mtr	1010.00
66	Page No.-12 Item No.-19-i(b), PWD,VOL-II , 2017-18	(b) For Concealed Work PVC Pipes, 15 mm	10.00	137.00	Mtr	1370.00
67	PWD S&P Schedule, P-5 It-5,vii),	Supplying and fitting fixing of gunmetal wheel valve of approved brand and make tested to 21 Kg per sq. cm. 25 mm dia(E5)	2.00	778.00	Each	1556.00
68	PWD S&P Schedule, page.37,item no-6 (b)	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity	1.00	5128.00	Each	5128.00
69	PWD S&P Schedule, page.37,item no-10 (i)(a)	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L.	1.00	96.00	Each	96.00
70	PWD S&P Schedule, (P. No. - 38, Item. No. - 13	Labour for punching hole in plastic water storage tank upto 50 mm dia.	4.00	19.00	Each	76.00
71	PWD S&P Schedule, Page No.-68 Item No. 23,(A)(i)(b)	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992.(A) (i) Single Socketed 3 Meter Length, (b) 110 mm	30.00	292.00	Mtr	8760.00

72		(B) Fittings(i) Coupler, (b) 110 mm	8.00	85.00	Each	680.00
73		(ii) Plain Tee, (b) 110 mm	12.00	85.00	Each	1020.00
74		(iii) Door Tee, (b) 110 mm	10.00	195.00	Each	1950.00
75		ix) Bend 45°, (b) 110 mm	10.00	89.00	Each	890.00
76		xi) Door Bend (T.S.), (b) 110 mm	7.00	147.00	Each	1029.00
77		xvi) Pipe Clip, (b) 110 mm	30.00	21.00	Each	630.00
78		xxvii) W.C. Connector (150 mm long) 125 X 110(W/WC Ring) 75 mm	4.00	142.00	Each	568.00
79		xxxix) Plain Floor Trap with Top tile & Strainer 75 mm	7.00	144.00	Each	1008.00
80		L) Rubber Ring, (b) 110 mm	15.00	17.00	Each	255.00
81		C)Rubber Lubricant 500 ML	1.00	187.00	500 ML	187.00
82		D)Solvent Cement 250 ML	1.00	103.00	250 ML	103.00
83	PWD S&P Schedule, (P. - 74, Item. No. - 24 (B)	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in the total pipeline including specials. (B) Under ground, (ii) 110 mm dia.	20.00	84.00	Mtr	1680.00
84	Pwd volume- i, 2017)(P. - 212, Item. No. - 21 (A)(i) , (B),(c),(i) & (B), (d),(i),	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materails (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete. A) UPVC Pipes: (i) 75 mm. Dia.	20.00	188.00	Mtr	3760.00
85		B) UPVC Fittings: c) Bend 87.5 degree (i) 75 mm. Dia.	6.00	95.00	Mtr	570.00
86		B) UPVC Fittings: d) Shoe (i) 75 mm. Dia.	2.00	78.00	Mtr	156.00
87	PWD S&P Schedule, S.P.87,Item No- 1/(i), 7th Corrigenda Volume ii	Constructing Inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling,15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm.thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. i) With Pakur variety (Other than SAIL/TATA/RINL).	2.00	7028.00	Each	14056.00

88	PWD S&P Schedule, S.P.88,Item No-3(ii)(A) 7th Corrigenda Volume ii	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover(heavy type)of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C(1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials. (ii) For 20 users A) With Pakur variety. (JSW/JSPL/SHYAM/SRMB/ELECTROSTEEL/SSL)	1.00	47129.00	Each	47129.00
89	S.P.89,Item No-4 7th Corrigenda Volume ii	Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm intermediate cement brick work (1:4) band all round and cement brick work (1:4) upto 0.90 metre from top with 20mm thick cement plastering (1:4) to inside face upto the depth of cement brick work, 15mm thick cement plaster (1:4) on outer face from top of the well upto G.L. and 6 mm thick cement plaster (1:4) on top of the R.C.C. cover slab including filling bottom 1.00 metre of inside of the well with brick metal (50 mm to 63 mm size) including R.C.C. cover slab of 100 mm thick with cement conc (1:1.5:3) with stone chips with necessary reinforcement and shuttering including one 560 mm dia. R.C.C. manhole cover (heavy type)of approved make supplied, fitted and fixed in the cover slab with necessary fittings, making necessary arrangements for pipe connections, excavation of well including shoring, dewatering and removing the excess earth from the premises as per direction complete in all respect with all costs of labour and materials. With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia. (Other than SAIL/TATA/RINL)	1.00	16159.00	Each	16159.00
90	PWD S&P Schedule, p No 82 I No- 22 (a)(ii)	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long	2.00	430.00	Each	860.00
91	PWD S&P Schedule, P-81, It-15(ii)	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	2.00	484.00	Each	968.00
92	Sanitary and plumbing work schedule P-82, It-18(b)	Supplying, fitting and fixing soap holder. (b) Fibre glass	2.00	58.00	Each	116.00

93	Sanitary and plumbing work schedule P-81, It-16(a)(i)	Supplying, fitting and fixing glass shelf with aluminium guard rails. (a) Ordinary type with 5.5 mm sheet glass (i) 450 mm X 125 mm	2.00	341.00	Each	682.00
			<b>A</b>	<b>Total</b>	<b>490862.21</b>	
			<b>B</b>	<b>18% GST on "A"</b>	<b>88355.20</b>	
			<b>C</b>	<b>Total (A+B)</b>	<b>579217.41</b>	
			<b>D</b>	<b>1% Cess on "C"</b>	<b>5792.17</b>	
			<b>E</b>	<b>Total (C+D)</b>	<b>585009.58</b>	
			<b>F</b>	<b>3% Contingency on "C"</b>	<b>17376.52</b>	
			<b>G</b>	<b>Total (E+F)</b>	<b>602386.10</b>	

  
Municipal Civil Engineer  
Kharagpur Municipality

  
Assistant Engineer  
Kharagpur Municipality

  
Executive Officer  
Kharagpur Municipality

  
Chairperson  
Kharagpur Municipality

  
18/11/25  
Junior Engineer  
West Midnapore Division  
M. E. Directorate  
Govt. of West Bengal.

**MAY BE VETTED**  
  
Assistant Engineer  
West Midnapore Division  
M.E. Directorate  
Govt. of West Bengal

**VETTED**  
  
14/11/25  
Executive Engineer,  
West Midnapore Division  
M.E. Directorate  
Govt. of West Bengal

**NAME OF WORK:- ESTIMATE FOR ELECTRICAL WORK OF 2 SEATED COMMUNITY TOILET AT Bala Seva Sangam Club, WARD NO. - 18 UNDER KHARAGPUR MUNICIPALITY OF WEST BENGAL (MODEL NO - C) [ASPIRATIONAL PARAMETER]**

\* As per PWD & I & WD schedule district charges will be applicable on PWD & I & WD schedule items

\* No district charges will be applicable on non-schedule items

SI No.	Iteam Description	Unit	Quantity	Rate	Adding district charges	Final rate	Amount
1	Distribution wiring in 2 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire(Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ), with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Piano Key type switchfixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall complete with 2 no. suitable size "Ph & N" copper bar incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. 175mmx100mmx65mm inspection box, making earthing attachment, painting the MS box and mending good the damages to original finish. [PWD Schedule Page No-E-14 Iteam No-2a]	Point	12	612.00	18.36	630.36	7564.32
	Average run 5 mtr						
2	Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 5A 3 pin flush type plug socket & Piano Key type switch fixed on MS CRC sheet metal (16 SWG) switch board cum JB on wall incl. bakelite/Perspex (wall matching color) top cover 3 mm thick and incl. painting the MS box and mending good the damages to original finish <b>On Board (only for pay counter)</b> [PWD Schedule Page No-E-15; I-4a]	Point	2	67.00	2.01	69.01	138.02
3	Supplying and fixing 240V 32A Double Pole AC Type 30mA RCCB.(Complete Set) (ISI marked) [Make- Legrand] (Cat No 4113/95) [ Legrand Page No-92 ]	Nos	1	5942.00	0.00	5942.00	5942.00
4	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' ( <b>Precision make</b> ) incl. necy. fittings as required 2 x 36/0.3 (2.5 sqmm) + 1 x 22/0.3 (1.5 sqmm) ECC [PWD Schedule Page No-E-14 Iteam No-1a(ii)]	mtr	12	119.00	3.57	122.57	1470.84

5	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. <b>a) For (2+4 way) (Make -Havells)</b> <b>[PWD Schedule Page No-D-9;Iteam No-13]</b>	No	1	935.00	28.05	963.05	963.05
6	Supplying and fixing 240/415 V MCB of Breaking capacity 10kA & C characteristics on din rail of existing DBs and necessary connection 6-32A SP MCB (Make -Havells) <b>[PWD Schedule Page No-D-6;Iteam No-7]</b>	Nos	4	168.00	5.04	173.04	692.16
7	Supplying and fixing 240/415 V MCB Isolator on din rail of existing DBs and necessary connection. 40A DP MCB Isolator (Make -Havells) <b>[PWD Schedule Page No-D-5;Iteam No-6]</b>	Nos	1	208.00	6.24	214.24	214.24
8	Supply of TMC501 conventional industrial batten (Philips make) LED Tube,model no- TMC501 P1xT-LED 22W P3241 <b>(WB I &amp; WD schedule P-113, I- 5:3 F.22)</b>	Nos	3	451.00	9.02	460.02	1380.06
9	Fixing only single/twin fluroscnt light fitting complete with all accessories directly on wall/ceiling by screws etc.. <b>[PWD Schedule Page No-C-2;Iteam No-14a]</b>	Nos	3	86.00	2.58	88.58	265.74
10	Supply & fixing Bulk head light fittings with die cast aluminium housing frosted/clear glass on wall/ceiling incl S/F 9 watt LED Lamp complete set. [Make - Havells] <b>(PWD sch - Page--D-13, I-23)</b>	Nos	3	579+ District Charges+75=	92.37	671.37	2014.11
11	Supply & fixing smart bright street light complete with all accessories to be fixed from the wall of building or on pole incl. making holes /providing clamping arrangement & necy. GI reducer as required.S&F 40 mm GI Pipe 1.5 mtr average length & s&f necy length of 1.5 sqmm pvc insulated single core copper wire & making connections as required & mending good damages incl wall paingting. (30 Watt) (Make - Bajaj) <b>[WB I&amp;WD sch P-111, I-f.9.0.2]</b>	Nos	1	3016.00	60.32	3076.32	3076.32
12	Supply of 9" domestic metal exhaust fan 9" (225mm)SWEEP. TRANS AIR - <b>( Make-Crompton/Havells/Bajaj)</b> <b>(UD &amp; MA schedule P-14, I-5))</b>	Nos	3	1863.00	0.00	1863.00	5589
13	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: 22.5 cm ( 9" ) <b>[PWD Schedule Page No-C-4;Iteam No-28(b)]</b>	Nos	3	247.00	7.41	254.41	763.23
14	Fixing only louver shutter/cowl on wall with necy. bolts & nuts (6 mm dia x 62 mm long) For 22.5 cm(9") Exhaust fan <b>[PWD Schedule Page No-C-4;Iteam No-30(b)]</b>	Nos	3	82.00	2.46	84.46	253.38
15	Supply of 240V A.C Ceiling fan ( 48 sweep,1200 mm complete) <b>[Make -Crompton ] for ceasing only]</b>	Each	1	2283.00	0.00	2283.00	2283

16	Fixing only Ceiling Fan [PWD sch P- C-3, I-21(a)]	Each	1	66.00	1.98	67.98	67.98
17	Supply & Fixing 240 V, 16/20 A Piano key type switch (Brand approved by EIC) on sheet metal switch board incl. S & F 100x100x65mm MS (16SWG) switch board and bakelite/perspex top cover of 3mm thick by Brass screws after making housing for switch by cutting bakelite/perspex cover and making necessary connections as required. (For Hand Dryer machine) [PWD sch P- E-6, I-17(b)]	Each	2	201.00	6.03	207.03	414.06
18	S/F 240V 25A Modular type starter (brand approved by EIC)with 25 A. Modular switch DP MCB (C-Curve)and 4 Module G.I. Moduar type switch board with 4 Module Top Cover Plate flushed in wall incl. S/F switch board and Cover Plate and making necy. Connections with PVC Copper wire and earth connectivity wire etc. as per schedule [for Pump] [PWD Schedule Page No-E-19, Item No-17] (Please follow in details)	Nos	1	784.00	23.52	807.52	807.52
19	Supply and Fixing of 2 mm Polyvinyl glow sign board made of 22 SWG GI sheet box with 1"X1" aluminum channel for fixing the vinyl board after necessary cutting the letter as required & s/f LED tube light fittings along with all accessories. (16 sqft @495.00/sqft) (UD & MA schedule P-14, I-4)	Nos	1	7920.00	0.00	7920.00	7920
20	Earthing installation by GI earth Spike (1830 X 20 mm) including 8SWG GI EarthWire & GI nuts, bolts, washer etc.	Nos	1	450.00	0.00	450.00	450
				Total			42269.03
				Add 18% GST			7608.43
				Total With GST (A)			49877.46
				Cess@1%			498.77
				total			50376.23
	Contingency Amount on "A"			Contingency@3%			1496.32
	(Total+GST)=Rs:			Total			51872.55
				Say Rs.			51873.00
<b>Service Connection Charges as per Quotation</b>							

*P. S. S.*  
Sub-Assistant Engineer(E)  
Kharagpur Municipality

*dv*  
Municipal Civil Engineer  
Kharagpur Municipality

*biggipoy*  
Assistant Engineer  
Kharagpur Municipality

*P. S. S.*  
Executive officer  
Kharagpur Municipality

Chairperson  
Kharagpur Municipality

*Sub-Assistant Engineer (Elect.)*  
Kharagpur Municipality

*Municipal Civil Engineer*  
HFA-(U) CLTC  
Kharagpur Municipality

*Assistant-Engineer*  
Kharagpur Municipality

*Executive Officer*  
Kharagpur Municipality

*Bhosh*  
Chairperson  
Kharagpur Municipality

*09-09-25*  
Junior Engineer  
Electrical & Mechanical Division  
SUDA

*15/12/25*  
ASSISTANT ENGINEER  
ELECTRICAL & MECHANICAL DIVISION  
SUDA

Technically Voted Rs. **51,873.00**  
(Rupees Fifty one thousand eight hundred and seventy three only.)

*ds*  
15/12/25  
Executive Engineer (E/M)  
D/O the Secretary M.E. Dto.  
Government of West Bengal

# PROBIR

Construction of Community Toilet (CT) at Bala Seva Sangam Club at Ward no-18 Under Kharagpur Municipality Model No - C Civil Works  
 Toilet Seat- 3 Nos & Urinal- 3 Nos Annexure- C, NON SCHEDULE ITEMS

# MUKHOPADHYAY

# OPADHYAY

# HYAY

Digitally signed by

PROBIR

MUKHOPADHYAY

HYAY

Date:

2025.12.19

16:00:27

+05'30'

SL.NO	Item Description & Item No.	Quantity	Rate	Unit	Amount
1	Non Shedule Item Sl. No. 91-106 ( Order as per SUDA) standard plastic dustbin (12lit)	2	350	Each	700.00
2	Sinage AP coated & structure vinyl	5	3776	each	18880.00
3	Supplying and fixing sinage with fixing stand post for public toilet for visible to passersby	5	1000	Each	5000.00
4	Installation of Sinage	1	2071	each	2071.00
5	Air freshner(pack of 4nos)	8	216	Each	1728.00
6	Air freshner (Naps name 250 gm)	5	210	Each	1050.00
7	Supplying paper napkin	5	50	Each	250.00
8	Supplying Saatar Napkin ( Whisper or similar make 50 pcs )	4	520	Each	2080.00
9	Harpic (blue 500 ml)	4	300	Each	1200.00
10	Harpic (Red 500 ml)	4	150	Each	600.00
11	Gala double lip floor wiper	4	350	Each	1400.00
12	Polishing glass or surface cleaner	2	200	Lit	400.00
13	Murder Acid	2	145	Lit	290.00
14	Bleaching powder	4	120	Kg	480.00
15	Detto / feboy or similar make liquid soap	8	140	Lit	1120.00
16	Rubber hand gloves	6	80	Pair	480.00
17	Double side plastic brush	6	125	Each	750.00
18	Plastic Broom	4	170	Each	680.00
19	SM many other CT based feedback system ( With number displayed on which SMS has to be sent )	1	5000	each	5000.00
20	Supplying 20000 SMS	1	4000	each	4000.00
21	Supplying 20000 SMS for keeping account of regular cleaning	3	200	Each	600.00
22	Lettering on Toilet Wall for display of name and contact details of UB ward number and name of maintenance authority , sanitinspector, etc.	1	1000	each	1000.00
				<b>TOTAL</b>	Rs. 49759.00

*(Handwritten signatures and stamps)*  
 Assistant Engineer, Kharagpur Municipality  
 Executive Officer, Kharagpur Municipality  
 Chairperson, Kharagpur Municipality

*(Handwritten note in red)*  
 Rate are taken from approved rates of non Schedule Items approved by SUDA vide memo no- 924/2021/7746 on dt- 05/03/21.

*(Official stamps and signatures)*  
 MAY BE VETTED  
 Assistant Engineer, West Midnapore Division, M.E. Directorate, Govt. of West Bengal  
 VETTED  
 Executive Engineer, West Midnapore Division, M.E. Directorate, Govt. of West Bengal

**Construction of Community Toilet (CT) at Bala Seva Sangam Club at Ward no-18 Under Kharagpur**

**Municipality Model No - F Civil Works**

**Toilet Seat- 2 Nos & Urinal- 3 Nos Annexure- A**

**( p.w.d.s.o.r.w.e.f.1.11.2017 including 11th corrigenda on dt.14.02.2020)**

<b>SL. NO</b>	<b>Ref</b>	<b>Item Description &amp; Item No.</b>	<b>Quantity</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1	PWD Building Works schedule Page - 1, Item -2.a	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. PWD COLM. $2 \times 2 \times 1.20 \times 1.20 \times 1.00 = 5.76 \text{ M}^3$ partition wall $1 \times 1.00 \times 0.375 \times 0.150 = 0.056 \text{ m}^3$	5.816	119.27	Cu.m	693.67
2	PWD Building Works schedule, Page - 1, Item -3.a	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work). (a) With earth obtained from excavation of foundation. $5.816 \times 1/5 = 1.16 \text{ m}^3$	1.160	77.54	%um	89.95
3	PWD Building Works schedule, Page - 2, Item -4.a	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) $1 \times 4.850 \times 2.8250 \times 0.325 = 4.453 \text{ m}^3$	4.453	599.61	Cum	2670.06
4	PWD Building Works schedule, Page- 14, Item - 1 ( Corri. Page-01, Date-04-06-2018)	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. $2 \times 2 \times 1.20 \times 1.20 = 5.76 \text{ m}^2$ $2 \times 2.50 \times 0.375 = 1.88 \text{ m}^2$ $1 \times 1.00 \times 0.375 = 0.375 \text{ m}^2$ $1 \times 4.85 \times 2.825 = 13.70 \text{ m}^2$	21.72	344.00	Sqm	7471.68
5	PWD Building Works schedule, p-26 Item 10 a	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes. a) Pakur Variety /Chandil Variety $2 \times 2 \times 1.20 \times 1.20 \times 0.150 = 0.864 \text{ m}^3$ $2 \times 2 \times (1.20 \times 1.20) + (0.250 \times 0.250) / 2 \times 0.150 = 0.451 \text{ m}^3$ $2 \times 2 \times 0.250 \times 0.250 \times 3.250 = 0.813 \text{ m}^3$ $2 \times 4.60 \times 0.250 \times 0.250 = 0.575 \text{ m}^3$ $3 \times 2.325 \times 0.250 \times 0.250 = 0.436 \text{ m}^3$ $3 \times 2.325 \times 0.250 \times 0.150 = 0.262 \text{ m}^3$ $2 \times 2.325 \times 0.250 \times 0.150 = 0.174 \text{ m}^3$ $1 \times 4.85 \times 2.8250 \times 0.125 = 1.970 \text{ m}^3$	5.545	5618.05	Cum	31152.09
6	PWD Building Works schedule, Page -23, Item - B.1.a, ( Corri. Page-09, Date-04-06-2018)	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering In ground floor and foundation. (a) 1:3:6 proportion $2 \times 2 \times 1.20 \times 1.20 \times 0.10 = 0.576 \text{ m}^3$ $2 \times 2.50 \times 0.375 \times 0.100 = 0.188 \text{ m}^3$ $2 \times 1.50 \times 1.00 \times 0.100 = 0.300 \text{ m}^3$ $1 \times 4.85 \times 2.8250 \times 0.100 = 1.370 \text{ m}^3$	2.434	5078.51	m3	12361.09

7	PWD Building Works schedule, Page -47, Item -1	25mm. thick damp proof course with cement concrete with stone chips (1:1.5:3) [with graded stone aggregate 10 mm nominal size] and admixture of water proofing compound as per manufacturer's specification followed by two coat of polymer based paint, (1st coat after 4 to 5 days of concrete laying and 2 nd coat just before brick masonry work) as directed (cost of water proofing compound & polymer based paint to be paid separately).( Chequering not required over concrete or painted surface). [Note: - Waterproofing as per item 9, polymer based paint as per item 8 (a) of subhead C of Section (C). $2 \times 4.85 \times 0.250 = 3.69 \text{ m}^2$ $3 \times 2.8250 \times 0.250 = 2.11 \text{ m}^2$	5.80	195.00	Sqm	1131.00
8	Page -16, Item-16, cori page -3, date -04.06.2018	125 mm brick work with 1st class bricks in cement mortar ( 1:4) in ground floor. $5 \times 1.20 \times 3.00 = 18.00 \text{ m}^2$ $3 \times 1.00 \times 3.00 = 9.00 \text{ m}^2$	15.00	705.00	Sq.M.	10575.00
9	PWD Building Works schedule, Page -47, Item-3	Supplying and laying polythine sheet ( 150 gm/sq.m ) over damp proof course or below flooring or roof terracing or foundation or foundation trenches.	37.87	24.00	Sq.M.	908.88
10	PWD Building Works schedule, Page -42, Item- 36.f	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (f) 25 mm to 30 mm shuttering without staging in foundation $2 \times 2 \times 4.85 \times 0.250 = 4.85 \text{ m}^2$ $2 \times 2 \times 2.825 \times 0.25 = 2.85 \text{ m}^2$ $2 \times 2 \times 4 \times 1.20 \times 0.150 = 2.88 \text{ m}^2$	10.58	203.00	Sqm	2147.74
11	PWD Building Works schedule, Page -42, Item- 36.a	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge. $1 \times 4.85 \times 2.8250 = 13.70 \text{ m}^2$ $2( 4.85 + 2.825 ) \times 0.125 = 1.209 \text{ m}^2$ $4(.30+.025 ) \times 3.00 = 6.60 \text{ m}^2$ $2 \times 2 \times 4.85 \times 0.1250 = 2.46 \text{ m}^2$ $2 \times 2 \times 2.825 \times 0.125 = 1.41 \text{ m}^2$	25.38	321.00	Sqm	8146.98
13	PWD Building Works schedule, Page - 43, Item - 40.a.i.1( Corri. 10th Page-01, Date-23-01-2020)	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m. (i) Tor steel/Mild Steel , JSPL/SWAYN/ELETRO/STEEL vol of conc. $3.853 \times 1.20 \% = 0.046 \text{ m}^3 \times 35.315 \text{ c.ft} = 1.624 \text{ c.ft} \times 225 \text{ kg} = 365.40 \text{ kg} = 0.365 \text{ MT}$	0.522	55196.64	M.T.	28812.65
14	PWD Building Works schedule, Page -106, Item- .18	Collapsible gate with 40 mm x 10 mm x 6 mm Tee as top and bottom guide rail , 20 mm x 10 mm x 2 mm vertical channels 100 mm apart in full stretched position 20m x 5 mm MS flats as collapsible bracings properly reveted and washered including 38 mm steel roller including locking arrangements , fitted and fixed in position with lugs set in cement concrete including cutting necessary hives chasing etc in walls , floors etc and making good all damages . $2 \times 1.00 \times 2.10 = 4.20 \text{ m}^2$	4.83	3402.00	Sqm	16431.66

15	PWD Building Works schedule, Page -15, Item-7.a	Brick work with 1st class bricks in cement mortar (1:4) (a) Foundation and plinth ground floor $2 \times 4.85 \times 0.250 \times 0.600 = 1.455 \text{ m}^3$ $3 \times 2.8250 \times 0.250 \times 0.600 = 1.271 \text{ m}^3$ $2 \times 2.50 \times 0.250 \times 0.600 = 0.750 \text{ M}^3$ $2 \times 1.00 \times 0.500 \times 0.300 = 0.300 \text{ M}^3$	3.776	5408.00	Cu.m	20420.61
16	PWD Building Works schedule, Page -15, Item-7.b	Brick work with 1st class bricks in cement mortar (1:4) (b) superstructure ground floor $2 \times 4.85 \times 0.250 \times 3.00 = 7.275 \text{ m}^3$ $3 \times 2.825 \times 0.25 \times 3.00 = 6.356 \text{ M}^3$	9.00	5631.00	Cu.m	50679.00
17	PWD Building Works schedule, P-192, It-1	Labour for Chipping of concrete surface before taking up Plastering work.	13.70	21.00	Sqm	287.70
18	PWD Building Works schedule, P-189 It- No. 1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster $2(4.85 + 2.8250) \times 3.75 = 57.56 \text{ m}^2$ $2(4.85 + 2.8250) \times 3.00 = 46.05 \text{ m}^2$ $1 \times 2 \times 2.325 \times 3.00 = 13.95 \text{ m}^2$ $2 \times 2 \times 1.60 \times 3.00 = 19.200 \text{ m}^2$	136.56	134.00	Sqm	18299.04
19	PWD Building Works schedule, P-189 It- No. 1 (ii)©	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (c) 10 mm thick plaster $4.85 \times 2.8500 = 13.70 \text{ m}^2$	13.70	122.00	Sqm	1671.40
20	PWD Building Works schedule, P-192 It- No. 15	Neat cement punning about 1.5 mm thick in wall ,dado, window sills, floors etc . Note cement 0.152 m <sup>3</sup> /100 m <sup>2</sup> $2(4.850 + 2.825) \times 0.75 = 11.51 \text{ m}^2$	11.51	34.00	Sq.m	391.34
21	PWD Building Works schedule, P-115, It - 3 (i)	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria.. (i) 66mm x 90mm $2(2 \times 2.10 + 0.75) = 9.90 \text{ M}$	9.90	497.00	Mtr	4920.30
22	P-125, It- 14(ii)	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolitaheic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor. ii) 25 mm thick $2 \times 2.10 \times 0.75 = 3.15 \text{ m}^2$	3.15	2581.00	Sqm	8130.15
23	PWD Building Works schedule, P-144, It No. 26 (vii)	Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws . (vii) 225mm long x 10mm dia. bolt.	5.00	84.00	Each	420.00
24	PWD Building Works schedule, P-140, It No. -5 (viii)	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (viii) 100mm X 75mm X 3.50mm	15.00	66.00	Each	990.00
25	PWD Building Works schedule, Page -146 . Item no-31,(i)	Anodised aluminium decorative handle (hexagonal / fluted) of approed quality fitted and fixed complete. (i) 150mm plate x 10mm dia rod x 12mm hexagonal/fluted.	8.00	87.00	Each	696.00

26	PWD Building Works schedule, Page -141 . Item no-10 b)	Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with concrete bolt and round fitting. .b)250mm long.	2.00	159.00	Each	318.00
27	PWD Building Works schedule, Page -74 , Item no-46(i)	Supplying and laying chequered tiles of any shade and of approved quality with (1:1.5:3) cement concrete laid in panels or patterns as directed in pavement ,footpath etc including necessary underlay 25 mm thick (avg)cement mortar (1:3) complete in all respect with all labour and materials. ( Using cement slurry @4.4kg/sq.m at back side and @2.4 kg/sq.m for joint filling ). (i). 25 mm thick 1 x 2.00 x1.00 = 2.00 m2 1 x 1.00 x 2.125 = 2.13 m2	4.13	455.00	sq.m	1879.15
28	PWD Building Works schedule, PWD, P- 198, I - 5	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick) In Ground Floor 136.56 + 13..70 = 150.26 M2	150.26	122.00	Sqm	18331.72
29	PWD Building Works schedule, Page -74 , Item no-46(i).	Applying interior grade Acrylic Primer of approved quality and brand on plastered and concrete surface old or new surface to receive Distemper Acrylic emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the E-I-C ( Ground Floor ) ( b ) Two Coats 44.63 +19.20 +13.90 -13.7 0 = 66.03 M2	32.00	44.20	m2	1414.40
30	PWD Building Works schedule, Page -196 , Item no- 9(b)	Dry Destempering interior walls or ceiling including cleaning, washing, smoothening surface (b) two coats .	66.06	49.00	m2	3236.94
31	PWD Building Works schedule, Page -196 , Item no- 8(b)	Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Decorative Textured (Martt Finish) or Smooth Finish Acrylic exterior emulsion paint including scraping and preparing the surface thoroughly , complete as per manufacturer's specification and as per direction of the EIC in Ground Floor (b) two coats.	57.70	45.10	m2	2602.27
32	PWD Building Works schedule, Page -197 , Item no- 17(a)	Protective and Decorative Acrylic Exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over Acrylic primer as required. The rate includes cost of materials, labour, scaffolding and all incidental charges but excluding the cost of primer in ground floor (two coats)(a) normal acrylic emulsion. 79.69+18.00 +36.00 = 136.69 m2	57.70	67.00	m2	3865.90
33	PWD Building Works schedule, Page -200 . Item no- 1 (b)	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	6.35	38.00	Sqm	241.30
34	PWD Building Works schedule, Page -200 . Item no- 2(A)(a)(iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : Page - 200 . Item no- 1 (b) (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	6.35	81.00	Sqm	514.35
35	PWD Building Works schedule, P-104 Item-13 A (i) (3rd Corrigendam Page No 91)	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr. 64 x 0.600 x 0.600 = 1.44 m2 = 1.44 m2 x 10..00 kg = 14.40 kg = 0.144 qtl	0.144	9888.00	Qntl	1423.87

36	PWD Building Works schedule, P/200 Item-1(a)	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. PWD Building Works schedule, P/200 Item-1(a)	5.64	29.00	Sqm	163.56
37	PWD Building Works schedule, P-200 Item-2(b)(iv)	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white)	5.64	79.00	Sqm	445.56
38	PWD Building Works schedule, Page-66 Item-36 (A)	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring Pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contrr]e) I (I) With application slurry @1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. (A) Deep Colour & White Floor 4.85 x 2.825 = 13.70 m2	13.70	1680.00	Sqm	23016.00
39	PWD Building Works schedule, page-64, Item:35.(B.) (b).(ii)	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. B) Wall Area of each tile above 0.09 Sq.m ii) Other than Coloured decorative including white $2(4.85 + 2.8250) \times 2.10 = 36.84 \text{ m}^2$ $1 \times 2 \times 2.325 \times 2.10 = 9.77 \text{ m}^2$ $2 \times 2 \times 1.60 \times 2.10 = 13.44 \text{ m}^2$	45.00	1029.00	Sqm	46305.00
40	PWD Building Works schedule, PWD, P-233, I-1(h) i	Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Anodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding & casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In- Charge. (Payment will be made on finished length of the work). (A) In 10-12 Micron thickness Anodizing film I) Natural white h) Louvered window. i) Top, bottom and side member.	6.50	183.00	M	1189.50
41		ii) Louvered Section.	7.20	658.00	M	4737.60
42		iii) Cleat angle ( Non-anodized).	6.48	263.00	M	1704.24
43	Building Works schedule, P-243, I-9	Supplying bubble free float glass of approved make and brand conforming to IS: 2835-1987. iv) 5mm thick coloured / tinted / smoke glass.	1.08	585.00	Sq.M.	631.80

44	PWD Building Works schedule, P-268, It-17€	Painting block letters or digits in Black Japan or any approved paint as per direction. e) Size above 7.5 cm. and upto 10 cm.	450.00	12.00	Each	5400.00
45	PWD Building Works schedule, Page -261, It- 9 (i)	Supplying and planting of different plants / trees (supplying well grown plants bushy and healthy, minimum height as specified i.e. exposed height including all leads and lifts, carriage, handling, manuring applying pesticide and fertilizer etc. i) Furcaria Veriegated 10 to 12 leaves in height 20-30 cm in earthen pot of size 25 cm	10.00	162.00	Each	1620.00
46	PWD Building Works schedule, Page -261, It- 9 (x)	x) Ficus blakii (F. Vivicon) well branched (Bushy) of height 120cm - 135 cm in earthen pot of size 30cm.	3.00	187.00	Each	561.00
47	PWD Building Works schedule, Page -261, It- 9 (xxvi)	xxvi) Areca Palm 4 - 5 suckers of height 90 cm to 105 cm in earthen pots of size 25 cm. PWD Building Works schedule, Page -261, It- 9 (xxvi)	3.00	127.00	Each	381.00
		<b><u>SANITARY AND PLUMBING WORKS</u></b>				0.00
48	PWD S&P Schedule, page-79, item no -3 (a)	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc. a) With 'P' trap (with vent)	2.00	3104.00	Each	6208.00
49	PWD S&P Schedule, page-81, item no 10.b.i	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete .(b) Anglo Indian (i) Plastic (hallow type) White	2.00	371.00	Each	742.00
50	PWD S&P Schedule, page.80,item no-6/(ii)	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete (ii) 470 mm X 280 mm X 340 mm	2.00	945.00	Each	1890.00
51	PWD S&P Schedule, page.80,item no-7/(i)	Supplying fitting and fixing squatting plate with integrated flushing in white vitreous set in cement concrete (6:3:1) with jhama chips complete. ( Payment of concrete will be paid seperately ) ( I ) 450 mm x 350 mm	1.00	881.00	each	881.00
52	PWD S&P Schedule, Page No.-36 Item No.-2,	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete,C.I. brackets including two coats of painting to bracket etc	2.00	1015.00	Nos	2030.00
53	PWD S&P Schedule, Page no 81. Item no. 11(i)	Supplying,fitting and fixing 32 mm dia. Flush Pipe of approved make with necessary fixing materials and clamps complete. i) Polythene Flush Pipe	2.00	155.00	Each	310.00
54	PWD S&P Schedule, S.P.81,item-12/a	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. (a) C.P. urinal flush pipe fittings range of one	2.00	414.00	Each	828.00
55	PWD S&P Schedule, P-41, It 2 (ii)	Supplying, fitting and fixing white vitreous china best quality approved make wash basin with C.I. brackets on 75 mm X 75 mm wooden blocks, C.P. waste fittings of 32 mm dia., mending good all damages and painting the brackets with two coats of approved paint. (ii) 550 mm X 400 mm size	2.00	2208.00	Each	4416.00
56	PWD S&P Schedule, P-41, It 3	Supplying fitting and fixing pedestal of approved make for wash basin ( White )	2.00	1497.00	Each	2994.00
57	PWD S&P Schedule, Page No.-43 Item No.-9-iii	Supplying,fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia., (iii) 600 mm long	5.00	107.00	Each	535.00

58	PWD S&P Schedule, Page No.-43 Item No. 10-iv	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iv) 1050 mm long each	2.00	91.00	Each	182.00
59	PWD S&P Schedule, Page No.-3 Item No.- 3 f,	(f) Hand Shower(Health Faucet) with 1mtr Fexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	0.00	1251.00	Each	0.00
60	PWD S&P Schedule, Page No.-6 Item No.-7-a-i	(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	5.00	539.00	Each	2695.00
61	PWD S&P Schedule, Page No.-6 Item No.-7-b-i	(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	2.00	493.00	Each	986.00
62	PWD S&P Schedule, Page No.-6 Item No.-7-d-i,	Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand).	4.00	815.00	Each	3260.00
63	(P. No. - 45, Item. No. - 19(a)i, Pwd Sanitary Plumbing Schedule 2017)	Supplying, fitting and fixing pillar cock of approved make. a) (i) CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	2.00	555.00	Each	1110.00
64	Page No.-12 Item No.-19-i(a), PWD,VOL-II , 2017-18	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads,fitting, fixing etc. complete in all respect including cost of all necessary fittings as required,jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will be made seperately) (a) For Exposed Work PVC Pipes, 25 mm	15.00	177.00	Mtr	2655.00
65	Page No.-12 Item No.-19-i(a), PWD,VOL-II , 2017-18	(a) (a) For Exposed Work PVC Pipes, 15 mm	10.00	101.00	Mtr	1010.00
66	Page No.-12 Item No.-19-i(b), PWD,VOL-II , 2017-18	(b) For Concealed Work PVC Pipes, 15 mm	10.00	137.00	Mtr	1370.00
67	PWD S&P Schedule, P-5 It-5,vii),	Supplying and fitting fixing of gunmetal wheel valve of approved brand and make tested to 21 Kg per sq. cm. 25 mm dia(E5)	2.00	778.00	Each	1556.00
68	PWD S&P Schedule, page.37,item no-6 (b)	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity	1.00	5128.00	Each	5128.00
69	PWD S&P Schedule, page.37,item no-10 (i)(a)	Labour for hoisting plastic water storage tank. (i) Upto 1500 litre capacity. (a) Upto 1st story from G.L.	1.00	96.00	Each	96.00
70	PWD S&P Schedule, (P. No. - 38, Item. No. - 13	Labour for punching hole in plastic water storage tank upto 50 mm dia.	4.00	19.00	Each	76.00
71	PWD S&P Schedule, Page No.-68 Item No. 23,(A)(i)(b)	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992.(A) (i) Single Socketed 3 Meter Length, (b) 110 mm	30.00	292.00	Mtr	8760.00

72		(B) Fittings(i) Coupler, (b) 110 mm	8.00	85.00	Each	680.00
73		(ii) Plain Tee, (b) 110 mm	12.00	85.00	Each	1020.00
74		(iii) Door Tee, (b) 110 mm	10.00	195.00	Each	1950.00
75		ix) Bend 45°, (b) 110 mm	10.00	89.00	Each	890.00
76		xi) Door Bend (T.S.), (b) 110 mm	7.00	147.00	Each	1029.00
77		xvi) Pipe Clip, (b) 110 mm	30.00	21.00	Each	630.00
78		xxvii) W.C. Connector (150 mm long) 125 X 110(W/WC Ring) 75 mm	4.00	142.00	Each	568.00
79		xxxix) Plain Floor Trap with Top tile & Strainer 75 mm	7.00	144.00	Each	1008.00
80		L) Rubber Ring, (b) 110 mm	15.00	17.00	Each	255.00
81		C)Rubber Lubricant 500 ML	1.00	187.00	500 ML	187.00
82		D)Solvent Cement 250 ML	1.00	103.00	250 ML	103.00
83	PWD S&P Schedule, (P. - 74, Item. No. - 24 (B)	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in the total pipeline including specials. (B) Under ground, (ii) 110 mm dia.	20.00	84.00	Mtr	1680.00
84	Pwd volume- i, 2017)(P. - 212, Item. No. - 21 (A)(i) , (B),(c),(i) & (B), (d),(i),	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary clamps nails, including making holes in walls, floor etc. cutting trenches in any soil through masonry concrete structures etc if necessary and mending good damages including joining with jointing materails (Spun Yarn, Valamoid/Bitumen/M-Seal etc) complete. A) UPVC Pipes: (i) 75 mm. Dia.	20.00	188.00	Mtr	3760.00
85		B) UPVC Fittings: c) Bend 87.5 degree (i) 75 mm. Dia.	6.00	95.00	Mtr	570.00
86		B) UPVC Fittings: d) Shoe (i) 75 mm. Dia.	2.00	78.00	Mtr	156.00
87	PWD S&P Schedule, S.P.87,Item No- 1/(i), 7th Corrigenda Volume ii	Constructing Inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling,15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm.thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials. i) With Pakur variety (Other than SAIL/TATA/RINL).	2.00	7028.00	Each	14056.00

88	PWD S&P Schedule, S.P.88,Item No-3(ii)(A) 7th Corrigenda Volume ii	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover(heavy type)of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C(1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and refilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials. (ii) For 20 users A) With Pakur variety. (JSW/JSPL/SHYAM/SRMB/ELECTROSTEEL/SSL)	1.00	47129.00	Each	47129.00
89	S.P.89,Item No-4 7th Corrigenda Volume ii	Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm intermediate cement brick work (1:4) band all round and cement brick work (1:4) upto 0.90 metre from top with 20mm thick cement plastering (1:4) to inside face upto the depth of cement brick work, 15mm thick cement plaster (1:4) on outer face from top of the well upto G.L. and 6 mm thick cement plaster (1:4) on top of the R.C.C. cover slab including filling bottom 1.00 metre of inside of the well with brick metal (50 mm to 63 mm size) including R.C.C. cover slab of 100 mm thick with cement conc (1:1.5:3) with stone chips with necessary reinforcement and shuttering including one 560 mm dia. R.C.C. manhole cover (heavy type)of approved make supplied, fitted and fixed in the cover slab with necessary fittings, making necessary arrangements for pipe connections, excavation of well including shoring, dewatering and removing the excess earth from the premises as per direction complete in all respect with all costs of labour and materials. With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia. (Other than SAIL/TATA/RINL)	1.00	16159.00	Each	16159.00
90	PWD S&P Schedule, p No 82 I No- 22 (a)(ii)	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (ii) 25 mm dia. and 600 mm long	2.00	430.00	Each	860.00
91	PWD S&P Schedule, P-81, It-15(ii)	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (ii) 600 mm X 450 mm	2.00	484.00	Each	968.00
92	Sanitary and plumbing work schedule P-82, It-18(b)	Supplying, fitting and fixing soap holder. (b) Fibre glass	2.00	58.00	Each	116.00

93	Sanitary and plumbing work schedule P-81, It-16(a)(i)	Supplying, fitting and fixing glass shelf with aluminium guard rails. (a) Ordinary type with 5.5 mm sheet glass (i) 450 mm X 125 mm	2.00	341.00	Each	682.00
			<b>A</b>	<b>Total</b>	<b>490862.21</b>	
			<b>B</b>	<b>18% GST on "A"</b>	<b>88355.20</b>	
			<b>C</b>	<b>Total (A+B)</b>	<b>579217.41</b>	
			<b>D</b>	<b>1% Cess on "C"</b>	<b>5792.17</b>	
			<b>E</b>	<b>Total (C+D)</b>	<b>585009.58</b>	
			<b>F</b>	<b>3% Contingency on "C"</b>	<b>17376.52</b>	
			<b>G</b>	<b>Total (E+F)</b>	<b>602386.10</b>	

  
Municipal Civil Engineer  
Kharagpur Municipality

  
Assistant Engineer  
Kharagpur Municipality

  
Executive Officer  
Kharagpur Municipality

  
Chairperson  
Kharagpur Municipality

  
18/11/25  
Junior Engineer  
West Midnapore Division  
M. E. Directorate  
Govt. of West Bengal.

**MAY BE VETTED**  
  
Assistant Engineer  
West Midnapore Division  
M. E. Directorate  
Govt. of West Bengal

**VETTED**  
  
14/11/25  
Executive Engineer,  
West Midnapore Division  
M.E. Directorate  
Govt. of West Bengal